

Balliemeanoch Pumped Storage Hydro

Environmental Impact Assessment

Report

Volume 5: Appendices

Appendix 14.1: Transport

Assessment Report

ILI (Borders PSH) Ltd

July 2024

Quality information

Prepared by	Check	red by	Verified by		Approved by	
Jamie Graham lai		amilton	David Dewar		David Lee	
Consultant	Princip	oal Consultant	sultant Associate Director		Technical Director	
Revision His	story					
Revision	Revision date	Details	Authorized	Name	Position	
1	July 2024	Submission	DL	David Lee	Technical Director	
Distribution	List					
# Hard Copies	PDF Required	Association / C	Company Name			

$\hbox{@}$ 2024 AECOM Limited. All Rights Reserved.

This document has been prepared by AECOM Limited ("AECOM") for sole use of our client (the "Client") in accordance with generally accepted consultancy principles, the budget for fees and the terms of reference agreed between AECOM and the Client. Any information provided by third parties and referred to herein has not been checked or verified by AECOM, unless otherwise expressly stated in the document. No third party may rely upon this document without the prior and express written agreement of AECOM.

Table of Contents

1.	Introduction	1
1.1	Background	1
1.2	Objective	1
1.3	Site Location	1
1.4	Scoping	1
1.5	Transport Statement Structure	2
2.	Transport Policy and Guidance	3
2.1	Introduction	3
2.2	Policy Compliance	3
2.3	National Policies	3
2.4	Regional Policies	4
2.5	Local Policies	4
3.	Transport Baseline	5
3.1	Introduction	5
3.2	Study Area Roads	5
3.3	A819	5
3.4	A83	5
3.5	A85	6
3.6	B840	6
3.7	Baseline Traffic Data	7
3.8	Study Area Discrete Road Links	8
3.9	Traffic Growth Forecast	9
3.10	Injury Accident Records	10
3.11	Core Paths	10
4.	The Development	12
4.1	Construction Programme and Phasing	12
4.2	Site Access and Construction Traffic Routes	12
4.3	Marine Facility	13
4.4	B840 Realignment	13
4.5	A819 Electric Cottage	13
5.	Construction Traffic	15
5.1	Introduction	15
5.2	Construction Programme	15
5.3	Vehicles, Plant and Equipment Requirement	15
5.4	Construction Traffic Generation Calculations	15
5.5	Construction Personnel Traffic Generation	16
5.6	Peak Month Construction Traffic Generation	17
5.7	Construction Traffic Distribution	17
5.8	Abnormal Indivisible Loads	18
5.9	Operational Traffic	18
6.	Sensitivity of Receptors	19
6.1	Introduction	
6.2	Determining Sensitivity of Receptors	
6.3	Results	
7.	Fear and Intimidation	
7.1	Introduction	
7.2	Methodology	
73	Results	23

8.	HGV / AIL Swept Path Analysis	24
8.1	Introduction	24
8.2	Proposed Inveraray Bypass	24
8.3	Proposed AIL Route (Upper Avenue)	24
8.4	Site Access	
9.	Cumulative Development	25
9.1	Introduction	25
9.2	Cumulative Effects	25
9.3	Assumptions	
9.4	Cumulative Development Traffic	
10.	Traffic Impacts	27
10.1	Introduction	
10.2	Assumptions	
10.3	Traffic Impacts	
10.4	AIL	
10.5	Road Traffic Accidents.	
11.	Framework Construction Traffic Management Plan	
11.1	Purpose	
11.2	CTMP Development	
11.3	Hours of Work	
11.4	Site Access	
11.5	Construction Traffic Routing	
11.6	Deliveries	
11.7	Enforcement	
11.8 11.9	Speed Limit	
12.	Summary and Conclusions	
	•	
12.1	Summary & Conclusions	35
	x A – Scoping Correspondence	
	x B – Traffic Survey Data	
	x C - Network Flow Diagrams	
Annex	x D - Road Links	
Annex	x E - Road Accident History	
Annex	x F - Construction Traffic Programme	
Annex	x G- Marine Facility	
Annex	x H - B840 Realignment	
	x I - Fear and Intimidation	
	x J - Swept Path Analysis	
	x K – Cumulative Development	
	·	
	x L- Axle Loadings	
	x M – Accident Forecast	
Annex	x L- Axle Loadings	

Tables

Table 1-1. Summary of Scoping	
Table 3-1. ATC Result Summary	
Table 3-2. Road Links	9
Table 3-3. Baseline Accident History on Study Area Roads	10
Table 4-1. Construction Activities	12
Table 5-1. Staff Vehicular Trip Generation	16
Table 5-2. Construction Traffic Distribution (Month 11 - 2027)	17
Table 6-1 Sensitivity of Receptors	19
Table 6-2. Sensitivity of Receptors Assessment	21
Table 7-1. Fear and Intimidation Degree of Hazard Scoring	22
Table 7-2. Levels of Fear and Intimidation	22
Table 7-3. Fear and Intimidation - Magnitude of Change	23
Table 7-4. Fear and Intimidation Magnitude of Change Assessment Summary	23
Table 9-1. Cumulative Development Traffic and Transport Data Sources	25
Table 10-1. Traffic Impact on Study Area Roads	27
Table 10-2. Traffic Impact on Study Area Roads of Cumulative Development	28
Table 10-3. Study Area Roads Capacity Assessment	29
Table 10-4. Forecast Road Accidents on Study Area Roads	30
Table 10-5. Forecast Road Accidents on Study Area Roads (Cumulative Development)	31

1. Introduction

1.1 Background

- 1.1.1 AECOM has been commissioned by the Applicant to prepare a Transport Impact Assessment (TA) to accompany an Environmental Impact Assessment Report (EIAR) Chapter (*Chapter 14: Access, Traffic and Transport*) (*Volume 2: Main Report*) for a Pumped Storage Hydro (PSH) scheme (the Development) near Balliemeanoch Farm Steading, Argyll and Bute.
- 1.1.2 For a description of the Development and the Site, see EIAR Volume 2 (Chapter 2: Project and Site Description).

1.2 Objective

1.2.1 The objective of this TA is to examine and report on potential transport impacts resulting from the preconstruction and construction phase of the Development and to provide additional detail and technical information to support the conclusions reached in the EIAR Traffic and Transport Chapter (Chapter 14: Access, Traffic and Transport) (Volume 2: Main Report).

1.3 Site Location

1.3.1 The Development is located at central national grid reference NN 03615 17578 approximately 4.4 km to the south of the village of Portsonachan and 9 km northwest of Inveraray in Argyll and Bute with the red line boundary shown on *Figure 1.1 Location Plan (EIA Volume 3: Figures*).

1.4 Scoping

1.4.1 AECOM has scoped the parameters of the assessment with Argyll and Bute Council and Transport Scotland. The Scoping Opinion can be found within *Appendix 4.2 Scoping Opinion (Volume 5 Appendices)* with additional consultation found within *Appendix 4.3 Consultation Tracker (Volume 5 Appendices)*. A summary of the consultation is shown in *Table 1-1 Summary of Scoping*, below. The transport specific scoping correspondence is also included in *Annex A Scoping Correspondence*, at the end of this TA.

Table 1-1. Summary of Scoping

Consultee	Key Issue	Summary of Response	Action Taken	
Argyll and Bute Council	Cumulative Impacts	Proposals which would impact the roads network should take account of the cumulative impacts on the network having regards to the fact that many energy related infrastructure projects are proposed in the area.	An assessment of the cumulative impacts of nearby development has been undertaken.	
	Excess Rock / Waste Material	A "duty to cooperate" utilising best endeavours between the two S36 hydro proposal developers should be required to ensure waste from Cruachan which could be utilised at the Development is not transport away from the local area.	Council position duly noted.	
	B840 Realignment	Preliminary route alignment drawings issued to Argyll and Bute Council.	Council reviewing and considering B840 realignment drawings.	
Transport Scotland	Traffic Data Collection	Transport Scotland required that base traffic in the vicinity of the A85(T)/ A819 junction should be used.	ATC traffic surveys have been undertaken on the A85 both immediately east and west of the A85 / A819 junction and have been included within the assessment.	
	Proposed jetty on the A83	Transport Scotland required that any proposed changes to the trunk road network must be discussed and approved (via technical approval process by the appropriate area manager). They required that 1:500 scale plans of any new or modified access from the trunk road should be submitted along with visibility splay plans.	Plans of access and traffic management for A83 at jetty produced.	

Consultee Key Issue		Summary of Response	Action Taken	
		An abnormal Loads Assessment and swept path analysis is required.	Swept path analysis for abnormal loads from the proposed jetty on the A83 undertaken. Abnormal load route bypasses Inveraray via Upper Avenue to reach A819.	
Argyll Estate	Inveraray Bypass	More information requested on the types of vehicles using the bypass, time of day, over what duration and how traffic will be managed. Request information on upgrades required to the roads and impact on trees and bridges.	Information provided to Argyll Estate on number and type of vehicles and how long the route will be used.	

1.5 Transport Statement Structure

1.5.1 This TS is structured as follows.

- Section 2: Transport Policy and Guidance Reviews relevant national, regional, and local transport planning policies and guidance.
- Section 3: Transport Baseline Reviews existing transport networks and their characteristics in the vicinity of the site, including traffic flows and recorded accident injuries.
- Section 4: The Development Provides a description of the Development and the construction phases associated with it.
- Section 5: Construction Traffic Contains a detailed breakdown of how construction traffic numbers
 were calculated to undertake the assessment in Chapter 14: Access, Traffic and Transport (Volume 2:
 Main Report).
- Section 6: Sensitivity of Receptors Details the assessment undertaken to inform the sensitivity of receptors used in Chapter 14: Access, Traffic and Transport (Volume 2: Main Report).
- Section 7: Fear and Intimidation Details the calculations undertaken in line with IEMA Guidelines 2023 to determine the likely Fear and Intimidation impacts contained within *Chapter 14: Access, Traffic and Transport (Volume 2: Main Report*).
- Section 8: Swept Path Analysis Shows swept path analysis of the proposed bypass routes for AIL movements on Upper Avenue and HGV movements on the proposed Inveraray Bypass route.
- Section 9: Cumulative Development Provides the background for the cumulative development assessment undertaken in *Chapter 14: Access, Traffic and Transport (Volume 2: Main Report)*.
- Section 10: Traffic Impacts Presents the anticipated traffic impacts of the construction of the Development, including temporary increases in traffic on Study Area roads and forecast injury accidents.
- Section 11: Framework Construction Traffic Management Plan Provides a framework for a future detailed Construction Traffic Management Plan to be enforced during the construction phase of the Development. A detailed CTMP will be the responsibility of the construction contractor once appointed.
- Section 12: Framework Staff Travel Plan Provides a framework for a future detailed Full Travel Plan to be enforced during the construction phase of the Development.
- Section 13: Summary and Conclusions

2. Transport Policy and Guidance

2.1 Introduction

2.1.1 In accordance with development planning process, the Development is required to comply with various national, regional, and local planning policies. This chapter therefore incorporates a brief overview of the relevant policy documents and highlights how the Development satisfies these policies. In addition to this, relevant aspects of specific transport guidance are also detailed.

2.2 Policy Compliance

2.2.1 The Development is required to comply with national, regional, and local transport planning policies, and follow relevant guidance as required. This chapter provides an overview of relevant policy and guidance and summarises how the Development will satisfy these.

2.3 National Policies

National Transport Strategy NTS2 (2020)

- 2.3.1 NTS2 sets out an ambitious and compelling vision for Scotland's transport system for the next 20 years. The vision is to have a sustainable, inclusive, safe, and accessible transport system, helping to deliver a healthier, fairer, and more prosperous Scotland for communities, businesses, and visitors.
- 2.3.2 Four priorities support the vision.
 - Reduce inequality.
 - Take climate action.
 - Help deliver inclusive economic growth.
 - Improve health and wellbeing.

Climate Change Plan Update (2020)

- 2.3.3 The Scottish Government's Climate Change Plan, originally published in 2018, sets out a path to Carbon Neutrality and securing the wider benefits of a greener, fairer, and healthier Scotland. The Plan covers the period of 2018 to 2032.
- 2.3.4 The Climate Change Plan was updated in 2020 to reflect the impacts of the COVID-19 pandemic and the Government's commitment to a 'green recovery' which captures opportunities of the transition to net zero. The Plan sets new ambitious targets to reduce Scotland's contribution to climate change by 2045 and a commitment to reduce emissions by 75% by 2030.

National Planning Framework 4

- 2.3.5 The National Planning Framework 4 (NPF4) was adopted by the Scottish Ministers on 13 February 2023, following approval by the Scottish Parliament in January. This replaces National Planning Framework 3 (NPF3) 2014, Scottish Planning Policy (SPP) 2014 and Regional Plans and is now part of the statutory Development Plan for Argyll and Bute, along with the Local Development Plan.
- 2.3.6 The NPF4 sets out overarching spatial principles to support the planning and delivery of the three key National Planning Policy areas:
 - Sustainable Places.
 - Liveable Places.
 - Productive Places.
- 2.3.7 NPF4 published in 2023 identifies 'National Spatial Strategy' and states that development proposals of all forms of renewable, low carbon and zero emissions technologies will be supported including pumped storage hydro. Under Policy 11 (Energy), development proposals for renewable energy projects must demonstrate how the following impacts are mitigated and addressed:

- Impacts on public access, including long distance walking and cycling routes and scenic routes.
- Impacts on road traffic and on adjacent trunk roads, including during construction; and
- Cumulative impacts.

Transport Assessment Guidance (2012)

2.3.8 Transport Assessment Guidance (TAG) produced by Transport Scotland in 2012 provides guidance and information for the content, methodology and approach of producing Transport Assessments, Transport Statements and Travel Plans in support of development sites.

Planning Advice Note (PAN) 75 - Planning for Transport (2005)

- 2.3.9 Scottish Planning Advice Note (PAN) 75 Planning for Transport is a planning circular produced by the Scottish Government which provides good practice on planning and transport. This includes guidance on integrating transport, transport modelling, policy development, development management, planning agreements and environmental assessment.
- 2.3.10 In terms of Transport Assessments/Statements, it states in Paragraph 41 that "all planning applications that involve the generation of person trips should provide information which covers the transport implications of the development." It identifies that for smaller developments, "the information on transport implications will enable local authorities to monitor potential cumulative impact."

2.4 Regional Policies

2.4.1 The Transport (Scotland) Act 2005 placed a statutory duty on the seven Regional Transport Partnerships (RTPs) in Scotland to produce a Regional Transport Strategy (RTS) for their area. The Development, located within Argyll and Bute, is within the Highland Transport Partnership region (HITrans).

HITrans Regional Transport Strategy Refresh (2018)

- 2.4.2 HITrans produced a Draft Updated Regional Transport Strategy in May 2017. This remains subject to approval by Scottish Ministers and therefore the RTS produced in 2008 is the currently adopted RTS for the region.
- 2.4.3 HITrans' RTS 2008 provides a regional policy context for the Development. It sets out a vision to "enhance the region's viability." To deliver the vision, the strategy notes that the critical issue of connectivity needs to be addressed and thus "improving interconnectivity of the whole region to strategic services and destinations" is included as a delivery objective. The planning objectives for the strategy are to:

Enable the region to compete and to support growth.

Enable the people of the region to participate in everyday life.

Improve the safety and security of travel.

Manage the impacts of travel on the region's environmental assets; and

Improve the health of the region's people.

2.5 Local Policies

Argyll and Bute Local Development Plan 2

- 2.5.1 Argyll and Bute Council (ABC) adopted their new Local Development Plan (LDP2) in February 2024. The key proposed policies of relevance to this chapter include:
 - Policy 30 The Sustainable Growth of Renewables,
 - Policy 35 Design of New and Existing, Public Roads and Private Access Regimes,
 - Policy 37 Development Utilising an Existing Private Access or Existing Private Road,
 - Policy 38 Construction Standards for Public Roads, and
 - Policy 39 Construction Standards for Private Access.

3. Transport Baseline

3.1 Introduction

3.1.1 This chapter summarises transport networks and baseline traffic within the Study Area for the site.

3.2 Study Area Roads

- 3.2.1 Study Area roads are identified in Figure 14.1 Study Area Roads (EIAR Volume 3 Figures):
 - A819 between Inveraray and Dalmally. It is a single carriageway which is largely rural in character.
 - A83 between Rest and Be Thankful and Lochgilphead. This is a single-carriageway section of trunk
 road carrying two-way traffic. It is primarily rural in character and passes through the settlement of
 Inveraray.
 - A85 between Taynuilt and Dalmally, east of the A85 / A819 junction. This is a single-carriageway section of trunk road carrying two-way traffic. It is primarily rural in character.
 - B840 is a single-track road with passing places between the A819 and Ford, routing adjacent to the banks of Loch Awe.
- 3.2.2 Additionally, there are upgrades proposed to multiple existing access tracks to facilitate the Development. These include:
 - An upgraded access track from the A819 will facilitate movements of construction traffic between the A819 and the Site.
 - A section of unclassified access track between the A83 and A819, north of Inveraray Castle will be upgraded and allow construction traffic to bypass the town of Inveraray.
 - A section of unclassified road (Upper Avenue) between the A83 west of Inveraray and the A819.
 This track will be upgraded to support construction traffic movements between the proposed jetty
 on the A83 and the A819, bypassing the town of Inveraray. It is anticipated that this route will
 principally be used byabnormal load traffic.

3.3 A819

Description

3.3.1 The A819 is a two-way, single carriageway road which routes north to south between the A85 in the north and the A83 in the south. It connects to the A85 west of Dalmally, in proximity of Kilchurn Castle, via a priority junction and connects to the A83 in Inveraray, also via a priority junction. The road has a national speed limit of 60mph for the majority of its route, with a small section immediately north of Inveraray with a 40mph speed limit and a 30mph speed limit within the town of Inveraray. The route is primarily rural in nature, providing access to a very small number of residential properties on its route.

Pedestrians

3.3.2 The A819 has no pedestrian infrastructure on its route outside of the urban environment of Inveraray. Within Inveraray the A819 has footways on the west side of the carriageway between the A83 / A819 junction and Inveraray Shinty Club.

Cyclists

3.3.3 This is no dedicated cycle infrastructure on the A819.

Public Transport

3.3.4 As a primarily rural road, there are no bus stops located on the A819.

3.4 A83

Description

3.4.1 The A83 is a two-way, single carriageway road which routes east and west between the A82 in the east and terminates at Campbeltown in the west. The A83 routes via the Rest and Be Thankful, Inveraray and Lochgilphead and is the access road for the proposed jetty, west of Inveraray. The road has a national speed limit of 60mph out with urban areas and a 30mph speed limit within towns on its route, including Inveraray. The route is primarily rural in nature but is known as a popular scenic route for tourists to access recreational areas in Argyll and Bute.

Pedestrians

3.4.2 The A83 has no pedestrian infrastructure on the vast majority of its route, being primarily rural in nature. There are however footways on both sides of the carriageway as it routes through Inveraray and has footways in other towns along its route.

Cyclists

3.4.3 This is no dedicated cycle infrastructure on the A83.

Public Transport

- 3.4.4 On the A83, bus services are accessible within the town of Inveraray. The town is served by the 926 Intercity service to Campbeltown from Glasgow which operates 7 days per week, with four services daily on weekdays, increasing to six daily services on weekends.
- 3.4.5 Local services are available in the form of the 428 and 486 services. The 428 service operates between Inveraray and Ardrishaig with two services operating each way during the AM and PM, 4 total daily services each way. The 428 service does not operate on weekends. The 486 service operates 6 days per week (no Sunday services) between Dunoon and Inveraray, providing a connection to the Ferry Terminal in Dunoon. On weekdays there are 5 daily services in each direction, reduced to two daily services each way on Saturdays.

3.5 A85

Description

3.5.1 The A85 is a two-way, single carriageway road which routes east and west between the A82 in the east and terminates at Oban in the west. The A83 routes via Dalmally, Taynuilt and Connel and provides a connection to the ferry terminal at Oban. The road has a national speed limit of 60mph out with urban areas and a 30mph speed limit within towns on its route. The route is primarily rural in nature but forms a key construction route for other nearby development such as a Cruachan 2 project.

Pedestrians

3.5.2 The A85 has no pedestrian infrastructure on the vast majority of its route, being primarily rural in nature. There are however footways on both sides of the carriageway as it routes through urban areas including Taynuilt.

Cyclists

3.5.3 This is no dedicated cycle infrastructure on the A85.

Public Transport

- 3.5.4 On the A85, bus services are accessible within the town of Dalmally, Taynuilt and Oban. The route is served by the 975 and 976 Intercity services between Oban and Glasgow which operates 7 days per week, with four services daily.
- 3.5.5 Local services are available in the form of the 403 and 415 services. The 403 service operates between Oban and Dalmally with two services operating each way during the AM and PM, 4 total daily services each way. The 403 service does not operate on weekends. The 415 service operates 6 days per week (no Sunday services) between Oban and Dalavich, providing a connection to the Ferry Terminal in Oban. Every day there are two daily services in each direction.

3.6 B840

Description

3.6.1 The B840 is a single-track road with passing places which routes north to south between the A819 in the north and the A816 in the south, near Ford. It connects to the A818 at Cladich via a priority junction and connects to the A816 also via a priority junction. The road has a national speed limit of 60mph out with small villages on the route. The route is primarily rural in nature, providing access to a very small number of residential properties on its route.

Pedestrians

3.6.2 The A819 has no pedestrian infrastructure on its route.

Cyclists

3.6.3 This is no dedicated cycle infrastructure on the A819.

Public Transport

3.6.4 As a primarily rural road, there are no bus stops located on the A819.

3.7 Baseline Traffic Data

- 3.7.1 Traffic surveys were undertaken throughout the Study Area in the form of eight Junction Turning Counts (JTC) and fifteen Automatic Traffic Counters (ATC). EIA Volume 3 Figure 14.3 shows the locations of the traffic surveys. Automatic traffic counters were in place for 7 days between Tuesday 6th June 2023 and Monday 12th June 2023, collecting data for 24 hours each day. JTC were in place on the 8th June 2023 and were recording between 07:00 10:00 and 16:00 19:00. The full outputs of the traffic surveys are included in *Annex B Traffic Survey Data*, at the end of this Appendix, and are summarised below.
- 3.7.2 JTCs were undertaken at the following locations:
 - JTC1 A83 / A819 junction in Inveraray
 - JTC2 A83 / Upper Ave junction south of Inveraray
 - JTC3 Aray Bridge signalised bridge crossing
 - JTC4 A819 / Residential property access junction
 - JTC5 A819 / Access Track junction
 - JTC6 A819 / Access Track junction
 - JTC7 A819 / B840 junction
 - JTC8 A85 / A819 junction
- 3.7.3 Network flow diagrams showing the results of the junction turning count surveys are included in *Annex C Network Flow Diagrams*, at the end of this Appendix.
- 3.7.4 ATCs were undertaken at the following locations:
 - ATC1 On A83, south of Inveraray
 - ATC2 On A83, approximately 150m south of Inveraray Parish Church
 - ATC3 On A819, approximately 75m north of the Inveraray Castle Car Park
 - ATC4 On A83, approximately 100m south of Aray Bridge
 - ATC5 On A83, approximately 350m south of Garron Bridge
 - ATC6 On A819, approximately 150m south of the residential property access
 - ATC7 On A819, approximately 150m north of access track
 - ATC8 On A819, approximately 100m north of access track
 - ATC9 On B840, approximately 100m west of A819 / B840 junction
 - ATC10 On A85, approximately 150m east of the A85 / A819 junction
 - ATC11 On A85, approximately 150m west of the A85 / A819 junction
 - ATC12 On A815, approximately 100m north of the A815 / A886 junction

- ATC13 On B840, approximately 300m east of Ford
- ATC14 On A83, approximately 300m north of the A83 / B828 junction
- ATC15 On A85, approximately 200m east of A85 / B845 junction

3.7.5 A summary of the results of the ATC surveys are included in Table 3-1 below.

Table 3-1. ATC Result Summary

ATC	Average W	eekday Traffic Flo	Average	85 th Percentile	
		2023 Survey		Vehicle Speed (mph)	Vehicle Speed (mph)
	Light	HGV	Total`		
ATC1 – On A83, south of Inveraray	3,232	219	3,451	46	52
ATC2 - On A83, approximately 150m south of Inveraray Parish Church	3,926	222	4,148	25	30
ATC3 - On A819, approximately 75m north of the Inveraray Castle Car Park	1,771	85	1,856	40	47
ATC4 – On A83, approximately 100m south of Aray Bridge	3,934	227	4,161	34	39
ATC5 – On A83, approximately 350m south of Garron Bridge	3,854	210	4,064	49	56
ATC6 – On A819, approximately 150m south of the residential property access	1,602	84	1,686	55	64
ATC7 – On A819, approximately 150m north of access track	1,589	91	1,680	52	60
ATC8 – On A819, approximately 100m north of access track	1,524	89	1,613	49	57
ATC9 – On B840, approximately 100m west of A819 / B840 junction	345	6	351	24	28
ATC10 – On A85, approximately 150m east of the A85 / A819 junction	3,590	179	3,769	43	51
ATC11 – On A85, approximately 150m west of the A85 / A819 junction	4,121	181	4,302	47	54
ATC12 – On A815, approximately 100m north of the A815 / A886 junction	2,278	124	2,402	39	44
ATC13 – On B840, approximately 300m east of Ford	179	2	181	25	32
ATC14 – On A83, approximately 300m north of the A83 / B828 junction	4,216	312	4,528	41	49
ATC15 – On A85, approximately 200m east of A85 / B845 junction	4,761	183	4,944	33	38

Source: 2023 Traffic Surveys

3.8 Study Area Discrete Road Links

3.8.1 The 2023 traffic count data for Study Area roads has been used to identify discreet road links for assessment purposes. These have been development using professional, engineering judgement with appropriate start and end points identified for each link. The start and end points usually come in the form of a junction or another appropriate landmark on the Study Area road. The road links identified as well as the ATC counter

associated with those links is shown in *Table 3-2* below and the extents of each road link is shown in *Annex D Road Links*, at the end of this Appendix.

Table 3-2. Road Links

Road Links	Extent	ATC
A85 Taynuilt	A85 / B845 Junction to Kilchurn Bridge	ATC15
A85 West	Kilchurn Bridge to A85 / A819 Junction	ATC11
A85 East	A85 / A819 Junction to Dalmally	ATC10
B840 Cladich	A819 / B840 Junction to Balliemeanoch	ATC9
A819 Dalmally	A85 / A819 Junction to Site Access Junction	ATC8
Site Access Track	Site Access Junction to Site	N/A
A819 Site Access	Site Access Junction to Potential Site Egress Junction	ATC7
A819 Inveraray	Potential Site Egress Junction to A819 / Upper Avenue Junction	ATC6
A819 Inveraray Town Centre	A819 / Upper Avenue Junction to A83 / A819 Junction	ATC3
Inveraray Bypass	A819 / Inveraray Bypass Junction to A83 / Inveraray Bypass Junction	N/A
A83 Aray Bridge	A83 / A819 Junction to A83 / Inveraray Bypass Junction	ATC4
A83 Garron Bridge	A83 / Inveraray Bypass Junction to Dunderave Castle	ATC5
A83 Rest and Be Thankful	Dunderave Castle to A83 / A815 Junction	ATC14
A815 Strachur	A83 / A815 Junction to A815 / A886 Junction	ATC12
Upper Avenue AIL Route	A83 / Upper Avenue Junction to A819 / Upper Avenue Junction	N/A
A83 Inveraray Town Centre	A83 / A819 Junction to Westernmost Inveraray Property	ATC2
A83 Lochgilphead	Westernmost Inveraray Property to A83 / Argyll Caravan Park Junction	ATC1
B840 Ford	Balliemeanoch to Ford	ATC13

3.9 Traffic Growth Forecast

- 3.9.1 To provide an appropriate baseline against which to compare forecast construction traffic flows, it has been necessary to apply a growth factor to the 2023 baseline data to arrive at anticipated baseline flows during the peak construction year of 2027. To obtain this, the Trip End Model Presentation Program (TEMPro) version 8.1 has been used. The software uses National Trip End Model (NTEM) data to forecast the percentage increase in traffic flows between two years, in this case 2023 and 2027. Analysis of NTEM data can be made by:
 - Geographical area
 - Transport mode
 - Travel time of day
 - Purpose of journey
 - Years of interest
 - Type of trip
- 3.9.2 For the Development, the following details have been applied to obtain the growth factor:
 - Dataset version 80
 - Dataset scenario Regional
 - Result type Trip ends by time period
 - Base year 2023
 - Future year 2027
 - Trip Purpose Group All purposes

- Time Period Weekday AM peak period
- Trip End Type Origin / Destination
- Area Description Argyll and Bute
- Mode Car Driver
- 3.9.3 The resulting output from the TEMpro calculations was that a growth factor of 1.0326 should be applied to 2023 data to achieve a baseline traffic flow level for 2027. This is effectively similar to an NRTF 'low' growth scenario which was agreed to be used in the assessment during scoping with Transport Scotland.

3.10 Injury Accident Records

3.10.1 The Crashmap online database (www.crashmap.co.uk) provides historical injury accident records for the most recent five-year period (2018-2022). The location and severity of all accidents on Study Area roads is included within Annex E Road Accident History, and is summarised in Table 3-3 below.

Table 3-3. Baseline Accident History on Study Area Roads

Road Link	Baseline Injury Accidents (2018 – 2022)				
	Slight	Serious	Fatal		
A85 Taynuilt	7	8	1		
A85 West	0	0	0		
A85 East	0	0	0		
B840 Cladich	0	0	0		
A819 Dalmally	1	5	0		
Site Access Track	0	0	0		
A819 Site Access	0	3	0		
A819 Inveraray	1	1	0		
A819 Inveraray Town Centre	0	0	0	_	
Inveraray Bypass	0	0	0		
A83 Aray Bridge	1	2	0		
A83 Garron Bridge	3	3	0		
A83 Rest and Be Thankful	8	8	0		
A815 Strachur	3	3	2		
Upper Avenue AIL Route	0	0	0		
A83 Inveraray Town Centre	0	0	0		
A83 Lochgilphead	0	0	0		
B840 Ford	0	0	0		
· · · · · · · · · · · · · · · · · · ·		·			

Source: Crashmap Database

3.10.2 Most links within the Study Area would be considered to have a negligible history of injury accidents with no noticeable accident clusters in the last 5 years. The A85 Taynuilt, and A819 Dalmally and A83 Rest and be Thankful all have slightly higher rates of accidents than the other links. There was a total of 20 'serious' accidents on these links over the 5-year period. It is considered that the only notable accident cluster on the Study Area roads is at the A83 / A815 junction which recorded 2 'slight' accidents, 4 'serious' accidents and 1 'fatal' accident over the 5-year period.

3.11 Core Paths

3.11.1 Within the Study Area, there are two core paths of note. Path C203(a) and C203(d) form part of the same path which utilises a small section of Upper Avenue. The core path routes from where Upper Avenue connects to the A83 to the bend in Upper Avenue where it changes course to the north east.

3.11.2 Path C201 routes from the town centre of Inveraray to the north east, past Inveraray Castle. This core path crosses the track which is proposed to be used as a construction route to bypass Inveraray just north of Inveraray Castle.

4. The Development

4.1 Construction Programme and Phasing

4.1.1 The construction programme and associated forecast vehicle movements are included in *Annex F Construction Traffic Programme*. Traffic generating activities during the construction stage of the Development are summarised in *Table 4-1* below.

Table 4-1. Construction Activities

Activity	Timescale	Description of Transport Activities			
Enabling Works	6 Months	Site set-up will include delivery of plant to improve existing site accesses.			
General Mobilisation	12 Months	Delivery of plant and materials to set up construction compound, conduct site investigations, open borrow pits and commence pontoon works.			
Headpond	23 Months	Delivery of plant and materials for removal of topsoil, creation of embankments and spillway construction.			
Tailpond	17 Months	Delivery of plant and materials to excavate rock, create inlet/ outlet structure and construct B840 diversion.			
Tunnelling Works	4 Months	Delivery of plant and materials to undertake tunnelling works.			
Construction Tunnel	24 Months	Delivery of plant and materials, including concrete to construct and line the tunnel.			
Emergency Egress and Access Tunnel	24 Months	Delivery of plant and materials, including concrete to construct and line the emergency tunnel.			
Headrace Tunnel (low pressure)	3 Months	Delivery of plant and materials, including concrete to construct and line the headrace tunnel.			
Tailrace Tunnel (low pressure)	29 Months	Delivery of plant and materials, including concrete to construct and line the tailrace tunnel.			
Power Tunnel (low pressure)	37 Months	Delivery of plant and materials, including concrete to construct and line the power tunnel.			
Ventilation Tunnel (low pressure)	37 Months	Delivery of plant and materials, including concrete to construct and line the ventilation tunnel.			
Switchroom Building and HV Switchyard	12 Months	Delivery of plant and materials to undertake ground works and building super structures for switchroom and switchyard.			
Powerhouse / Power Cavern	15 Months	Delivery of plant and materials, including delivery of concrete to undertake excavation works, create turbine and transformer halls, remove spoil and transport crane structure and superstructure.			

Source: <Source>

4.2 Site Access and Construction Traffic Routes

- 4.2.1 Access to the site is anticipated to be facilitated by the following routes, also shown in *Figure 14.1 Study Area Roads (EIA Volume 3 Figures):*
 - A819 between Inveraray and Dalmally. It is a single carriageway which is largely rural in character.
 - A83 between Rest and Be Thankful and the proposed jetty location. This is a single-carriageway
 section of trunk road carrying two-way traffic. It is primarily rural in character and passes through the
 settlement of Inveraray.
 - A85 between Taynuilt and east of the A85 / A819 junction. This is a single-carriageway section of trunk road carrying two-way traffic. It is primarily rural in character.
- 4.2.2 In addition to the public roads listed above, two dedicated construction traffic routes are proposed in the vicinity of Inveraray. Figure 14.2 Inveraray Study Area Roads (EIA Volume 3: Figures) shows these routes. East of Inveraray a dedicated route for construction traffic is proposed between the A83 and A819. This route runs north of Inveraray Castle and avoids the town and is referred to in this TA and throughout the EIAR as the Inveraray Bypass. This route will be used by construction traffic in both directions. West of Inveraray a new temporary marine facility with jetty is proposed on Loch Fyne. This jetty will be used to deliver abnormal indivisible loads (AIL) into the Study Area. AIL will leave the jetty and cross directly over

- the A83 before continuing on a dedicated construction traffic route that links into Upper Avenue and connects to the A819 north of Inveraray.
- 4.2.3 Construction traffic will leave the public road from the A819 at Craig nan Sassanach where an existing track access to Old Military Road will route traffic towards the Development site. Upgrades will be required to the network of forest tracks that are proposed to accommodate construction traffic.
- 4.2.4 The B840 runs along the shore of Loch Awe, west of the Development site. However, construction traffic is not proposed to route via the B840 as it will use the A819 Craig nan Sassanach access. The proposed inlet / outlet structure at Loch Awe will require the existing alignment of the B840 to be revised and routed inland over a short distance to bypass the proposed inlet / outlet structure.

4.3 Marine Facility

- 4.3.1 The marine facility will consist of a temporary jetty, provided for the delivery of abnormal indivisible loads (AIL), such as transformers, turbine, and gantry cranes. Several different types of plant and equipment will be required for the construction and operation of the proposed marine facility. These include, but are not limited to:
 - Barges.
 - Long reach excavators.
 - Tugs.
 - · Jack up barges.
 - Workboats.
 - · Temporary harbour cranes.
 - Mobile cranes; and
 - Piling rigs.
- 4.3.2 Annex G Marine Facility contains AECOM drawing number S03-Z2-06-DR-CE-326301 showing a conceptual arrangement for the proposed temporary marine facility with jetty.

4.4 B840 Realignment

- 4.4.1 The Development will have an inlet / outlet structure on Loch Awe in the vicinity of Balliemeanoch Farm Steading. This will be a physically substantial piece of permanent infrastructure. Drawings in *Annex H B840 Realignment* how the location and extents of the proposed inlet / outlet construction. It will have a significant impact on the B840 road in this location, both during the construction phase and thereafter when the pumped storage hydro scheme is operational.
- 4.4.2 It has been considered whether a temporary closure, or temporary local diversion, of the B840 would allow the inlet / outlet works to be completed, with the B840 retaining its current alignment once construction is complete. However, a temporary closure is not considered feasible as the work is programmed over several years, and the diversion route would be a considerable length. Furthermore, the completed inlet / outlet structure will be so significant in scale AECOM are of the view the B840 could not be retained on its current alignment.
- 4.4.3 As such, a permanent realignment of the B840 in the vicinity of the inlet / outlet structure is proposed. The proposed realignment of the B840 is to the landward side of the proposed inlet / outlet structure. *Annex H B840 Realignment* contains drawings with a conceptual realignment for the B840.

4.5 A819 Electric Cottage

4.5.1 Public consultation has raised a concern from the occupiers of Electric Cottage on the A819. They state the existing A819 road alignment (mainly the vertical geometry) and traffic speeds in the vicinity of their access can make exiting the cottage onto the A819 challenging. Fast moving traffic from the direction of Inveraray is their main concern, as the A819 is a national speed limit road past the access to the cottage. The occupiers are concerned that additional traffic on the A819 associated with the Development may exacerbate their access issues and concerns.

4.5.2 AECOM consider that a temporary extension to the 40mph limit on the A819 to encompass the Electric Cottage entrance may alleviate the occupiers' concerns. The current A819 40mph / National Speed Limit boundary is south of the cottage access. Moving the speed limit boundary some 580 meters north to include the cottage would be an appropriate solution for the duration of the Development's construction programme (some 72 months).

5. Construction Traffic

5.1 Introduction

5.1.1 This section presents the anticipated vehicular trip generation associated with the Development.

5.2 Construction Programme

5.2.1 The construction period is expected to last approximately 7 years, anticipated to begin in 2027 and being completed by 2034.

5.3 Vehicles, Plant and Equipment Requirement

- 5.3.1 Several different types of plant and equipment will be required for construction of the Development. These include, but are not limited to:
 - Bulldozers.
 - Mobile cranes.
 - · Mobile crushing and screening plant.
 - Dump trucks for the transportation of materials within the Development Site.
 - Electric shuttle cars.
 - Excavators.
 - Graders.
 - Low loaders for delivery of plant and equipment.
 - Mechanical breaking plant.
 - Pumps.
 - · Drilling, piling, and blasting rigs.
 - Rollers.
 - 8-wheel tippers.
 - Tractors and trailers.
 - Temporary concrete batching plant.
 - Temporary bunded fuelling station.
 - Temporary floating track i.e. bogmats or trackway system.
 - Tunnel services i.e. lighting, electricity, ventilation etc.
 - Silt busters, silt curtains and dewatering tubes.
 - Water bowsers and water cannons.
 - Wheel wash facilities.

5.4 Construction Traffic Generation Calculations

- 5.4.1 The full output of calculations for forecasting construction traffic throughout the construction programme are included *Annex F Construction Traffic Programme*. The section details how these numbers were calculated, and the assumptions made to arrive at the forecast level of construction traffic.
- 5.4.2 AECOM has calculated materials required to be transported to site at various stages of the construction programme and have used professional judgement to determine how these would be transported to site. Different types of materials will clearly require different vehicle types to transport then with varying capacities. It has been determined that the different types of material would require the following vehicle types to transport them:

- Aggregate HGV (20 tonne capacity)
- Geotextiles HGV (20 tonne capacity)
- Rebar HGV (20 tonne capacity)
- Steel HGV (20 tonne capacity)
- Concrete Concrete Mixer (7.6m³ capacity)
- Topsoil HGV (20 tonne capacity)
- Rock HGV (20 tonne capacity)
- Timber / Wood HGV (20 tonne capacity)
- Plant Low loader (AIL)
- Turbines Low loader (AIL)
- Transformers Low loader (AIL)
- 5.4.3 Knowing the quantities of each material projected to be required at each stage of construction has allowed the number of vehicles required throughout the construction programme to be determined by dividing the materials required by the capacity of the vehicle required to transport them. This is then multiplied by two to account for the two-way nature of material deliveries.
- 5.4.4 A detailed construction programme has been provided indicating the number of months that each stage of the construction will last for. It has been assumed that the total number of delivery vehicles required at each stage of construction will be spread uniformly across each month that stage will take place. For example, it is forecast that the removal of topsoil for the headpond will take two months to complete and required 90 two-way vehicle trips in total, therefore 45 two-way vehicle trips have been assigned to each of those months.

5.5 Construction Personnel Traffic Generation

- 5.5.1 It is anticipated that there will be 600 staff on-site during the peak period of construction. At present, the arrangements for accommodation for staff has not been determined, however it is likely that workers will be housed locally (see workers' accommodation annex). This would provide accommodation for most staff working on site; however, some staff would still be expected to travel to site from elsewhere.
- 5.5.2 To determine the vehicle trips generated by staff during the peak month of construction, the following assumptions have been made:
 - 85% of 600 staff will be transported to site by minibus. At present, it is considered likely that a minibus service will be provided to transport workers from the temporary workers' accommodation to site each day and vice versa. This will minimise the impact of staff vehicle trips to site and mean workers are being transported as sustainably as possible. It is assumed that each minibus has a capacity of 16 staff per bus.
 - The remaining 15% of 600 staff will use private cars / LGVs as transport to and from the site daily. It is
 assumed that workers travelling to the site by private car / LGV will travel at a rate of 2 workers per
 vehicle, allowing for car sharing arrangements. Car sharing will be encouraged among staff to minimise
 the impact of staff trips on local roads and ensure staff are travelling as sustainably as possible.
- 5.5.3 The resulting calculation to determine the number of daily staff vehicle movements is shown in Table 5-1.

Table 5-1. Staff Vehicular Trip Generation

Mode	Share	Staff	Ratio	Vehicles	Two-way Movements
Minibus	85%	510	16 per minibus	32	64
Car / LGV	15%	90	2 per car / LGV	45	90
Total					154

Source: AECOM

5.6 Peak Month Construction Traffic Generation

- 5.6.1 Once construction traffic and staff traffic were assigned to the relevant months within the construction programme, it was necessary to determine the daily number of two-way vehicle trips that would be generated by the site. It was assumed there every month of construction would contain 22 days where construction would be taking place and therefore the site would be generating traffic. Monthly construction traffic has therefore been assigned uniformly across those 22 working days during each month to determine an average daily construction traffic number of vehicles.
- 5.6.2 The forecast HGV movements is then added to the forecast construction staff vehicle movements to arrive at the total daily vehicle movements during each month of the construction period. The month with the highest forecast daily construction movements is then selected for assessment as the peak period for construction traffic.
- 5.6.3 For the Development, the peak period for construction traffic is forecast to occur in month 11 (November) of 2027. This is primarily due to many HGVs being required to deliver aggregate for the formation of access tracks and the setup of the construction compound. It is forecast that, during month 11, there will be an average daily two-way generation of 490 HGV trips and 154 two-way staff trips, resulting in a total of 644 two-way vehicle trips to and from the site.

5.7 Construction Traffic Distribution

- 5.7.1 To allow an assessment on each road link within the Study Area to be undertaken, it has been necessary to make assumptions regarding which routes construction vehicles will take to and from the site. For assessment purposes, it is assumed construction traffic generated by the Development appears on all Study Area roads. This assumption provides a robust assessment of Development traffic on Study Area roads. However, this will not be the case in reality and there is a number of exceptions to this general assumption contained within this assessment. These are:
 - Construction traffic route from A83 Jetty to A819 via Upper Avenue carries AIL traffic only.
 - HGV construction traffic does not route through the town of Inveraray which encompasses the A819
 Inveraray Town, A83 Aray Bridge and A83 Inveraray road links. A dedicated haul route is provided
 between the A83 and A819 north of Inveraray Castle (the Inveraray Bypass).
 - Construction traffic does not route along the B840 which encompasses the B840 Cladich and B840 Ford road links.
- 5.7.2 The distribution of construction traffic and quantum of vehicles assessed on each road link is therefore shown in *Table 5-2* below:

Table 5-2. Construction Traffic Distribution (Month 11 - 2027)

Construction Troffic Comical

Road Link	Construction	on Traffic Carried	Daily Two-way Vehicle Trips			
	HGV	Staff (Car/Van)	HGVs	Cars / Vans	Total	
A85 Taynuilt	100%	100%	490	154	644	
A85 West	100%	100%	490	154	644	
A85 East	100%	100%	490	154	644	
B840 Cladich	0%	0%	0	0	0	
A819 Dalmally	100%	100%	490	154	644	
Site Access Track	100%	100%	490	154	644	
A819 Site Access	100%	100%	490	154	644	
A819 Inveraray	100%	100%	490	154	644	
A819 Inveraray Town Centre	0%	100%	0	154	154	
Inveraray Bypass	100%	0%	490	0	490	
A83 Aray Bridge	0%	100%	0	154	154	
A83 Garron Bridge	100%	100%	490	154	644	
A83 Rest and Be Thankful	100%	100%	490	154	644	

Road Link	Construction	on Traffic Carried	Daily Two-way Vehicle Trips			
	HGV	Staff (Car/Van)	HGVs	Cars / Vans	Total	
A815 Strachur	100%	100%	490	154	644	
A83 Inveraray Town Centre	0%	100%	0	154	154	
Upper Avenue AIL Route	0%	0%	0	0	0	
A83 Lochgilphead	100%	100%	490	154	644	
B840 Ford	0%	0%	0	0	0	

5.8 Abnormal Indivisible Loads

- 5.8.1 There will be a requirement for some deliveries by abnormal indivisible loads (AIL) during the construction of the Development. These are partly associated with the transport of equipment to the site including cranes but will also be required for the transportation of the transformers, turbines, and other essential components. The environmental assessment of traffic and movement considers the peak month of construction and therefore does not include abnormal loads as they are not forecast during this month of construction.
- 5.8.2 Throughout the entire 108-month construction programme, it is anticipated that a total of 376 abnormal load movements will be required. These deliveries are expected to take place between January 2030 and November 2031 and will therefore be spread over a 23-month period. More detail is provided on abnormal loads at section 10.4 of this report.

5.9 Operational Traffic

- 5.9.1 It is anticipated that, once operational, the site will be minimally staffed. It would be expected that maintenance trips would be required on semi-regular basis. The maintenance visits would be expected to generate approximately 2-4 two-way trips, likely to be an LGV or private car which would be considered to have a negligible impact on the local road network.
- 5.9.2 It is likely that some larger scale maintenance would be required throughout the lifetime of the project on a potentially annual basis. This could involve an increase in LGV trips over the basic general maintenance so could generate in the region of 6-10 two-way LGV trips. Depending on the type of maintenance required, a relatively small number of HGV trips could also be required if materials or vehicles require to be transported to the site. As these trips would be relatively low frequency occurrences with a small number of vehicles, it would not be expected that this would have a significant impact on the local transport network.
- 5.9.3 The operational phase of the Development has been scoped out of this assessment and is therefore not considered further in this report.

6. Sensitivity of Receptors

6.1 Introduction

6.1.1 This section sets out the approach for determining the sensitivity of receptors on each road link assessed within *Chapter 14: Access, Traffic and Transport (Volume 2: Main Report)* for the Development.

6.2 Determining Sensitivity of Receptors

6.2.1 Receptors are locations or land-uses categorised by sensitivity or environmental value. *Table 6-1* describes the receptor sensitivity adopted for the assessment of Development traffic.

Table 6-1 Sensitivity of Receptors

Receptor Sensitivity	Description
Very High	The receptor has little or no ability to absorb change without fundamentally altering its present character, is of very high environmental value, or of international importance.
High	The receptor has low ability to absorb change without fundamentally altering its present character, is of high environmental value, or of international importance.
Medium	The receptor has moderate capacity to absorb change without significantly altering its present character, has some environmental value or is of regional importance.
Low	The receptor is tolerant of change without detriment to its character, is low environmental value, or local importance.
Negligible	The receptor is resistant to change and is of little environmental value.

- 6.2.2 For the purposes of this assessment, the Institute of Environmental Management and Assessment (IEMA) Guidelines identify receptors which are:
 - People at home
 - People at work
 - Sensitive and/or vulnerable groups (including young age; older age; income; health status; social disadvantage; and access and geographic factors)
 - Locations with concentrations of vulnerable users (e.g. hospitals, places of worship, schools)
 - Retail areas
 - Recreational areas
 - Tourist attractions
 - Collision clusters and routes with road safety concerns
 - Junctions and highway links at (or over capacity)
- 6.2.3 Each road link within the Study Area has been assessed against the criteria above. Professional engineering judgement has been used to assign a rating of Negligible, Low, Medium, High or Very High for each road link against each of the categories above. To assign each road link an overall sensitivity score, a numbering system has been used which assigns scores for each category based on the sensitivity level as set out above. The scoring system works as follows:

- Negligible 1 point
- Low − 2 points
- Medium 3 points
- High 4 points
- Very High 5 points
- 6.2.4 Once each link had been assigned a score for each category, an average score was obtained across all the categories to determine the overall score each link. The average score allowed an overall sensitivity for each link to be determined as per the same point system as above.

6.3 Results

6.3.1 The full assessment result of the assessment is shown in *Table 6-2* overleaf.

Table 6-2. Sensitivity of Receptors Assessment

Road Link	Sensitivity Criteria					Total Score	Average Score	Overall Sensitivity Rating				
	People at Home	People at Work	Sensitive and/or vulnerable Groups	Locations with concentratio ns of vulnerable users	Retail Areas	Recreational Areas	Tourist Attractions	Collision Clusters and routes with road safety concerns	Junctions and highway links at (or over) capacity			
A85 Taynuilt	Medium	Low	Negligible	Low	Low	Medium	Negligible	Medium	Negligible	18	2.00	Low
A85 West	Negligible	Negligible	Negligible	Negligible	Low	low	Medium	Negligible	Negligible	13	1.44	Negligible
A85 East	Low	Low	Negligible	Negligible	Negligible	Low	Negligible	Negligible	Negligible	12	1.33	Negligible
B840 Cladich	High	Negligible	Medium	Medium	Negligible	High	Medium	Negligible	Medium	23	2.56	Medium
A819 Dalmally	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	9	1.00	Negligible
Site Access Track	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	9	1.00	Negligible
A819 Site Access	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	9	1.00	Negligible
A819 Inveraray	Low	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	10	1.11	Negligible
A819 Inveraray Town Centre	Very High	Very High	Very High	Very High	Very High	Very High	Very High	Negligible	Negligible	41	4.56	Very High
Inveraray Bypass	Negligible	Negligible	Negligible	Negligible	Negligible	Medium	Medium	Negligible	Negligible	13	1.44	Negligible
A83 Aray Bridge	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	High	Negligible	High	15	1.67	Negligible
A83 Garron Bridge	Negligible	Low	Low	Low	Negligible	Negligible	Negligible	Low	Negligible	13	1.44	Negligible
A83 Rest and Be Thankful	Negligible	Low	Low	Negligible	Medium	Medium	Negligible	High	Medium	20	2.22	Low
A815 Strachur	Low	Low	Low	Negligible	Low	Low	Low	High	Negligible	18	2.00	Low
A83 Inveraray Town Centre	Very High	Very High	Very High	Very High	Very High	Very High	Very High	Negligible	Negligible	41	4.56	Very High
Upper Avenue AIL Route	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	9	1.00	Negligible
A83 Lochgilphead	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	9	1.00	Negligible
B840 Ford	Low	Low	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	Negligible	11	1.22	Negligible

7. Fear and Intimidation

7.1 Introduction

7.1.1 This section sets out the process by which the Fear and Intimidation on and by Road Users assessment was undertaken with Chapter 14 of the EIA (Chapter 14: Access, Traffic and Transport (Volume 2: Main Report)). This assessment has been undertaken in line with guidance set out in IEMA Guidelines 2023.

7.2 Methodology

- 7.2.1 IEMA Guidelines 2023 states that fear and intimidation on a given road link is dependent on:
 - The total volume of traffic
 - The heavy vehicle composition
 - The speed of vehicles
 - The proximity of traffic to people
- 7.2.2 A weighting system is set out in IEMA Guidelines 2023 to allow assessors to determine the likelihood of fear and intimidation given the characteristics set out above. This is achieved by determining a 'degree of hazard' which allows a score to be provided for each highway link within the Study Area and a resulting 'magnitude of impact' to be determined.
- 7.2.3 A degree of hazard score for each of total volume of traffic, heavy vehicle flow and average vehicle speed is determined using *Table 3.1* in the IEMA Guidelines 2023, replicated below.

Table 7-1. Fear and Intimidation Degree of Hazard Scoring

Average Traffic Flow over 18- hour day – all vehicles/hour 2- way (a)	Total 18-hour heavy vehicle flow (b)	Average vehicle speed (c)	Degree of hazard score
+1,800	+3,000	>40	30
1,200–1,800	2,000-3,000	30-40	20
600–1,200	1,000-2,000	20-30	10
<600	<1,000	<20	0

Source: Table 3.1 IEMA Guidelines 2023

7.2.4 The total degree of hazard score from all three elements (total volume of traffic, heavy vehicle flow and average vehicle speed) is combined to provide a level of fear and intimidation. *Table 3.2* in IEMA Guidelines 2023 provides the thresholds that should be used to determine this.

Table 7-2. Levels of Fear and Intimidation

Level of Fear and Intimidation	Total Degree of Hazard Score (a)+(b)+(c)
Extreme	71+
Great	41-70
Moderate	21-40
Small	0-20

Source: Table 3.2 IEMA Guidelines 2023

7.2.5 The magnitude of change for fear and intimidation for a Development is then approximated with reference to the changes in the level of fear and intimidation from baseline conditions. *Table 3.3* from the IEMA Guidelines is used to determine the magnitude of change from a given change in level of fear and intimidation. This table is replicated below.

Table 7-3. Fear and Intimidation - Magnitude of Change

Magnitude of Change	Change in Fear and Intimidation Level from Baseline Conditions		
High	Two step changes in Fear and Intimidation Level		
Medium	One step change in Fear and Intimidation Level, but with: >400 veh increase in average 18hr AV two-way all vehicle flow; and/or >500 HV increase in total 18hr HV flow		
Low	One step change in Fear and Intimidation Level, but with: <400 veh increase in average 18hr AV two-way all vehicle flow; and/or <500 HV increase in total 18hr HV flow 		
Negligible	No step change in Fear and Intimidation Level		

Source: Table 3.3 IEMA Guidelines 2023

7.3 Results

7.3.1 The results of the fear and intimidation assessment for the Development and Cumulative development are included in *Annex I Fear and Intimidation* and are summarised in *Table 7-4* below.

Table 7-4. Fear and Intimidation Magnitude of Change Assessment Summary

Road Link Magnitude of Change

<u>Medium</u> <u>Negligible</u> <u>Negligible</u>
<u>Negligible</u>
<u>Negligible</u>

8. HGV / AIL Swept Path Analysis

8.1 Introduction

- 8.1.1 HGV / AIL swept path analysis has been undertaken on Study Area roads as follows.
 - The proposed Inveraray Bypass north of Inveraray Castle between the A83 and A819
 - The proposed AIL route on Upper Avenue, between the A83 jetty and the A819.
 - A819 site access.
- 8.1.2 The swept path analysis drawings are contained with Annex J Swept Path Analysis.

8.2 Proposed Inveraray Bypass

- 8.2.1 The proposed Inveraray Bypass will route HGV construction traffic between the A83 and A819. Its purpose is to avoid routing HGV construction traffic over the Aray Bridge and through Inveraray town centre.
- 8.2.2 AECOM drawings S03-ZD-02-DR-TR-302208 to S03-ZD-02-DR-TR-302210 show the swept path analysis for the proposed Inveraray Bypass between the A83 and A819. The drawings show the locations where marshalling points will be located to allow stacking of vehicles off the main carriageway. These will be located close to either end of the route (A83 end and A819 end) and will ensure construction vehicles are not disrupting the flow of the traffic on the public road network.
- 8.2.3 These drawings also show the proposed locations of passing places on the route which will operate on a line-of-sight basis, allowing two-way flow. For the proposed passing places, inbound (westbound) vehicles will give way to outbound (eastbound) vehicles.
- 8.2.4 The analysis shows that the route would have sufficient width to accommodate the HGV movements which are proposed to utilise it. Although a strict traffic management plan will be in place throughout to manage vehicles leaving and joining the route.

8.3 Proposed AIL Route (Upper Avenue)

- 8.3.1 The Upper Avenue AlL route has been assessed for the worst case AlL load. That is a 280-tonne transformer with dimensions 10.5m x 4m x 4.8m. This represents the largest and heaviest AlL to be transported from the jetty to the A819 via Upper Avenue.
- 8.3.2 AECOM drawings S03-ZD-02-DR-TR-302202 to S03-ZD-02-DR-TR-302204 show the swept path analysis for the proposed AIL Route utilising Upper Avenue. The drawings show a marshalling area immediately north of the A83 which will allow vehicles to turn. The route will accommodate one-way AIL movements only and traffic will be co-ordinated to ensure that only one vehicle is utilising the route at any time. The drawings show that some widening, and realignment is required on the route but that AIL movements can be achieved. Additionally, some vegetation clearance is required at the A819 / Upper Avenue junction. The proposed Upper Avenue AIL route will be provided to ensure vehicles can safely pass a memorial stone.
- 8.3.3 AECOM drawings S03-ZD-02-DR-TR-302212 shows the proposed traffic management at the location where the proposed jetty meets the A83 carriageway. This includes appropriate signage indicating works, heavy plant crossing and forewarning of temporary traffic signals when loads are being moved. Part time signals will be installed on the A83 carriageway to the east and west of the A83 / Upper Avenue junction as well as on Upper Avenue and at the proposed jetty access road. All signs will be compliant with The Traffic Signs Regulations and General Directions (TSRGD).

8.4 Site Access

8.4.1 AECOM drawings S03-ZD-02-DR-TR-302206 and S03-ZD-02-DR-TR-302217 show how worst-case abnormal loads will interact with proposed site access from the A819 to site. The swept path analysis shows where areas of widening are required at the accesses to ensure AIL can negotiate them in one movement.

9. Cumulative Development

9.1 Introduction

9.1.1 This section sets out the process by which cumulative development traffic was incorporated into the Traffic and Transport assessment in *Chapter 14: Access, Traffic and Transport (Volume 2: Main Report*).

9.2 Cumulative Effects

- 9.2.1 The effects of the Development will be assessed in combination with other projects that are either under construction or currently going through planning. Those approved or under construction will be considered as part of our baseline, those still going through the planning process will be considered as part of our cumulative assessment. Projects to be included within the cumulative assessment will be identified through consultation and a search of the ABC planning portal as well as that of the ECU.
- 9.2.2 Chapter 4: Approach to EIA (Volume 2: Main Report) Table 4.8 Cumulative Developments lists developments that have been identified as either going through screening or scoping, with a granted planning application, or under construction at present to be included within the cumulative assessment.
- 9.2.3 Cumulative developments which have been identified as operational are accounted for in the baseline traffic data. The remaining developments are shown in *Table 9-1*.
- 9.2.4 The data used in the traffic and transport assessment for the remaining three developments to be considered has been obtained from the following documents:

Table 9-1. Cumulative Development Traffic and Transport Data Sources

Scheme	Document	Date	Section
Cruachan II Hydro Scheme	Cruachan Expansion Project EIA Report – Volume 1 Main Report	May 2022	Table 9.15
	Cruachan Expansion Project - Transport Assessment	May 2022	Table 5.2
Blarghour Wind Farm	Blarghour Wind Farm - Section 36C Variation Application EIA Report (Volume 2: Main Report)	February 2023	Table 10.9
Upper Sonachan Wind Farm	Upper Sonachan Wind Park – Volume 1: Environmental Statement Chapters	October 2015	Table 12.12 – Table 12.15
Ladyfield Wind Farm	Ladyfield Renewable Energy Park - Environmental Impact Assessment Volume 1 Chapter 13	January 2024	Section 13.7.1 and Figures 13.1 – 13.4
Inveraray to Taynuilt (ITE/ITW) Tie-In to Creag Dhubh Substation	Volume 2 Technical Annex 2.2 Traffic Calculations	February 2023	Technical Annex 2.2
An Suidhe Substation Overhead Line Connection	An Suidhe EA Chapter 9	August 2022	Section 9.5
Creag Dhubh to Dalmally OHL	Section 37 EIA Volume 2 Chapter 13	April 2022	Section 13.5
Creag Dhubh – Inveraray OHL	EA Volume 2 Chapter 12	October 2022	Section 12.4
An Carr Dubh Wind Farm	EA Volume 1 Chapter 12	April 2023	Table 12.10

Scheme	Document	Date	Section
33kv Overhead Line - ETU 166 - Dalmally	Small development consisting of installation of 15 no. poles. No traffic information available therefore not considered.	N/A	N/A
Creag Dhubh substation	Creag Dhubh to Dalmally OHL Section 37 EIA Volume 2 Chapter 13	April 2022	Section 13.6
Inverary to Crossaig OHL	Inveraray to Crassaig 275kv Overhead Line Reinforcement EIA Report: Volume 2: Main Report	July 2018	Section 8.4
An Suidhe Substation	Project currently at screening, no traffic data available	N/A	N/A

9.3 Assumptions

9.3.1 A key assumption for the cumulative development assessment is that the peak period for forecast construction traffic generation for each of the developments will coincide with the peak period for construction traffic generation of the Development. In practice, this is highly unlikely to occur, and it would be anticipated that discussions would be undertaken to minimise the cumulative impact of all cumulative development in the area. However, to present a worst-case scenario of potential effects on the Study Area roads, this assumption has been made.

9.4 Cumulative Development Traffic

9.4.1 The cumulative development traffic data is included within *Annex K*.

10. Traffic Impacts

10.1 Introduction

10.1.1 This section presents the traffic and transport impacts of the construction traffic associated with the Development and presents an assessment of Cumulative Development.

10.2 Assumptions

- 10.2.1 For assessment purposes, it is assumed construction traffic generated by the Development appears on all Study Area roads. This assumption provides a robust assessment of Development traffic on Study Area roads. However, this will not be the case in reality and there is a number of exceptions to this general assumption contained within this assessment. These are:
 - Construction traffic route from A83 Jetty to A819 via Upper Avenue carries AIL traffic only.
 - HGV construction traffic does not route through the town of Inveraray which encompasses the A819 Inveraray Town, A83 Aray Bridge and A83 Inveraray road links.
 - HGV construction traffic does not route along the B840 which encompasses the B840 Cladich and B840 Ford road links.
 - Car / LGV trips associated with construction personnel have been assumed to occur on all Study Area
 roads. At present it is not known where staff will originate from, therefore, to provide a robust
 assessment, it has been assumed they will be on all Study Area roads. (Not including construction
 traffic haul routes: Inveraray Bypass and Upper Avenue AlL Route).

10.3 Traffic Impacts

10.3.1 The results of the assessment of the impacts of the Development as well as the Cumulative Development Assessment have been included in network flow diagrams, contained within *Appendix C Network Flow Diagrams*. *Table 10-1* below summarises the anticipated increases in traffic on Study Area roads.

Table 10-1. Traffic Impact on Study Area Roads

Road Link

	2027 Baseline		The Dev	/elopment	The Development % Impact	
	HGV	All Vehs	HGV	All Vehs	HGV	All Vehs
A85 Taynuilt	189	5,105	490	644	259%	12.6%
A85 West	187	4,442	490	644	262%	14.5%
A85 East	185	3,892	490	644	265%	16.5%
B840 Cladich	6	362	0	0	0%	0%
A819 Dalmally	92	1,666	490	644	533%	38.6%
Site Access Track	0	0	490	644	-	-
A819 Site Access	94	1,735	490	644	521%	37.1%
A819 Inveraray	87	1,741	490	644	564%	36.9%
A819 Inveraray Town Centre	88	1,917	0	154	0%	8.04%
Inveraray Bypass	0	0	490	490	-	-
A83 Aray Bridge	234	4,297	0	154	0%	3.58%
A83 Garron Bridge	217	4,196	490	644	225%	15.3%
A83 Rest and Be Thankful	322	4,676	490	644	152%	13.7%
A815 Strachur	128	2,480	490	644	382%	25.9%
A83 Inveraray Town Centre	229	4,283	0	154	0%	3.6%

Road Link

	2027 Baseline		The De	velopment	The Development % Impact	
	HGV	All Vehs	HGV	All Vehs	HGV	All Vehs
Upper Avenue AIL Route	0	0	0	0	-	-
A83 Lochgilphead	226	3,564	490	644	216%	18%
B840 Ford	2	187	0	0	0%	0%

10.3.2 Forecast cumulative development impacts are summarised on Table 10-2 below, and are also included in network flow diagrams in *Annex C Network Flow Diagrams*.

Table 10-2. Traffic Impact on Study Area Roads of Cumulative Development

Road Link

	2027 Baseline		Cumulative	Development	Cumulative Development % Impact	
	HGV	All Vehs	HGV	All Vehs	HGV	All Vehs
A85 Taynuilt	189	5,105	1,322	6,540	599%	28%
A85 West	187	4,442	1,420	6,021	659%	35%
A85 East	185	3,892	1,318	5,327	612%	36%
B840 Cladich	6	362	6	516	0%	42%
A819 Dalmally	92	1,666	1,137	2,993	1,137%	79%
Site Access Track	0	0	490	644	High	High
A819 Site Access	94	1,735	1,139	3,062	1,112%	76%
A819 Inveraray	87	1,741	1,132	3,068	1,204%	76%
A819 Inveraray Town Centre	88	1,917	643	2,754	632%	43%
Inveraray Bypass	0	0	490	490	High	High
A83 Aray Bridge	234	4,297	288	4,505	23%	4%
A83 Garron Bridge	217	4,196	761	4,894	250%	16%
A83 Rest and Be Thankful	322	4,676	866	5,374	168%	14%
A815 Strachur	128	2,480	618	3,124	382%	25%
Upper Avenue AIL Route	0	0	0	0	0%	0%
A83 Inveraray Town Centre	229	4,283	550	4,886	140%	14%
A83 Lochgilphead	226	3,564	1,037	4,657	358%	30%
B840 Ford	2	187	2	341	0%	82%

10.3.3 Volume 15 of the Economic Assessment of Road Schemes in Scotland¹ contains information regarding the capacity of roads depending on their characteristics, including number of lanes, speed limits and road lane widths. The document also separates roads into urban and rural categories, providing the capacity for roads in vehicles per hour per direction. Given the anticipated increases in traffic on Study Area roads during construction of the Development, a capacity assessment has been undertaken referring to Table 5/3/2 of the above document. To allow a comparison to be made, the capacities, which are stated in vehicles per hour per direction have been multiplied by 18 (for 18 hours of traffic flow daily) and then by 2 (to cover both directions). Table 10-3 below shows the outcome of this assessment.

¹ CD012.004 - DMRB, Volume 15, Economic Assessment of Road Schemes in Scotland, The NESA Manual, Scottish Government (2015)

Table 10-3. Study Area Roads Capacity Assessment

Road Link	Road Type	Capacity (Daily)	Baseline + the Development Vehicles	Over Capacity?	Baseline + Cumulative Development	Over Capacity?
A85 Taynuilt	Rural – Typical Single 7.3m	43,200	5,749	No	6,540	No
A85 West	Rural – Typical Single 7.3m	43,200	5,086	No	6,021	No
A85 East	Rural – Typical Single 7.3m	43,200	4,536	No	5,327	No
B840 Cladich	Rural – Poor Single 5.5m	14,400	516	No	516	No
A819 Dalmally	Rural – Typical Single 7.3m	43,200	2,310	No	2,993	No
Site Access Track	Rural – Poor Single 5.5m	14,400	644	No	644	No
A819 Site Access	Rural – Typical Single 7.3m	43,200	2,379	No	3,062	No
A819 Inveraray	Rural – Typical Single 7.3m	43,200	2,385	No	3,068	No
A819 Inveraray Town Centre	Rural – Typical Single 7.3m	43,200	2,071	No	2,754	No
Inveraray Bypass	Rural – Poor Single 5.5m	14,400	490	No	490	No
A83 Aray Bridge	Rural – Typical Single 7.3m	43,200	4,451	No	4,505	No
A83 Garron Bridge	Rural – Typical Single 7.3m	43,200	4,840	No	4,894	No
A83 Rest and Be Thankful	Rural – Typical Single 7.3m	43,200	5,320	No	5,374	No
A815 Strachur	Rural – Typical Single 7.3m	43,200	3,124	No	3,124	No
Upper Avenue AIL Route	Rural – Poor Single 5.5m	14,400	4,437	No	0	No
A83 Inveraray Town Centre	Rural – Typical Single 7.3m	43,200	0	No	4,886	No
A83 Lochgilphead	Rural – Typical Single 7.3m	43,200	4,208	No	4,657	No
B840 Ford	Rural – Poor Single 5.5m	14,400	341	No	341	No

10.3.4 As shown in *Table 10-3* above, none of the roads identified within the Study Area would exceed their recommended capacity from Volume 15 of the Economic Assessment of Road Schemes in Scotland. This would suggest that, in terms of their geometry and traffic flows, all roads should be able to accommodate the increase in traffic resulting from the construction of the Development.

10.4 AIL

- 10.4.1 All AlL deliveries will arrive at the proposed jetty on Loch Fyne, connecting to the public road network on the A83, west of Inveraray. AlL movements will all follow a prescribed route which will be as follows:
 - Crossing the A83 on the A83 Lochgilphead link via temporary signals only in operation at times of scheduled AIL deliveries.
 - Utilising the proposed AIL route between the A83 and A819 via the upgraded Upper Avenue.
 - A819 to site access.

- 10.4.2 The only road links which will be affected by AIL movements will be:
 - A83 Lochgilphead
 - Upper Avenue AIL Route
 - A819 Inveraray
 - A819 Site Access
- 10.4.3 No other links within the Study Area are proposed to be used for AIL movements.
- 10.4.4 During the full duration of construction, it is anticipated that there will be a total of 376 AIL movements required over 7 years. These are partly associated with the transportation of equipment to site, including cranes and excavators. The gantry cranes, transformers and turbines are also anticipated to be transported to site by AIL.
- 10.4.5 AIL axle loads have been estimated and are included in Annex L AIL Axle Loadings, at the end of this Appendix.
- 10.4.6 AIL deliveries would be scheduled for non-peak times to ensure that the impact on Study Area roads would be minimised however the likely impact of AIL movements would be as follows:
 - Temporary delay on A83 Lochgilphead link for drivers with temporary traffic management in place while AIL are crossing the A83 carriageway from the proposed jetty to Upper Avenue. Delays will only occur at delivery times and the traffic management will not be operational outside of those times. (AECOM Drawing Ref 302212 (Annex J Swept Path Analysis)).
 - No impact on Upper Avenue as this will be a dedicated AIL route for the Development will no general traffic using the route.
 - Temporary delay on A819 Inveraray and A819 Site Access links for drivers following the AIL vehicles. AlL will be slow moving and will likely require an escort, meaning drivers will experience short terms delays on these links while AIL deliveries are taking place.

10.5 Road Traffic Accidents

- 10.5.1 The calculation for forecasting increases in road traffic accidents during the construction period of the Development has been based on 2023 traffic survey data and accident history gather from Crashmap. 2023 traffic survey data has been used to calculate a 'total annual vehicle kilometres' for each link in the Study Area. The Crashmap data for each link has then been used to derive a 'vehicle accident rate' for each link for 'slight,' 'serious' and 'fatal' accident severities. This rate is then applied to the increased vehicle kilometres generated because of the construction of the Development to arrive at a forecast for additional vehicle accidents.
- 10.5.2 Table 10-4 below shows the forecast additional annual road traffic accidents during the construction period for the Development.

Table 10-4. Forecast Road Accidents on Study Area Roads

Road Link

Forecast Annual Injury Accidents by Severity

	Recorded 2018-2022			The Development (Annual)		
	Slight	Serious	Fatal	Slight	Serious	Fatal
A85 Taynuilt	7	8	1	0.1	0.1	0.0
A85 West	0	0	0	0.0	0.0	0.0
A85 East	0	0	0	0.0	0.0	0.0
B840 Cladich	0	0	0	0.0	0.0	0.0
A819 Dalmally	1	5	0	0.0	0.1	0.0
A819 Site Access	0	3	0	0.0	0.1	0.0
A819 Inveraray	1	1	0	0.0	0.0	0.0
A83 Garron Bridge	3	3	0	0.0	0.0	0.0
A83 Rest and Be Thankful	4	7	0	0.0	0.1	0.0

Road Link

Forecast Annual Injury Accidents by Severity

	Re	ecorded 2018-20)22	The D	evelopment (A	nnual)
	Slight	Serious	Fatal	Slight	Serious	Fatal
A815 Strachur	3	3	2	0.1	0.1	0.0
A83 Lochgilphead	0	0	0	0.0	0.0	0.0
B840 Ford	0	0	0	0.0	0.0	0.0

10.5.3 Table 10-4 shows that there is a very small forecast increase in road accidents because of the Development but the magnitude of this is considerably lower than 1 additional accident on each road link annually. It is considered that this represents a very low level of change and that in reality, this effect would be negligible.

10.5.4 Table 10-5 below summarises the forecast cumulative development effect on road traffic accidents.

Table 10-5. Forecast Road Accidents on Study Area Roads (Cumulative Development)

Road Link

Forecast Annual Injury Accidents by Severity

	Re	ecorded 2018-20)22	Cumulati	ve Developmen	t (Annual)
	Slight	Serious	Fatal	Slight	Serious	Fatal
A85 Taynuilt	7	8	1	0.2	0.3	0.0
A85 West	0	0	0	0.0	0.0	0.0
A85 East	0	0	0	0.0	0.0	0.0
B840 Cladich	0	0	0	0.0	0.0	0.0
A819 Dalmally	1	5	0	0.1	0.4	0.0
A819 Site Access	0	3	0	0.0	0.3	0.0
A819 Inveraray	1	1	0	0.1	0.1	0.0
A819 Inveraray Town Centre	0	0	0	0.0	0.0	0.0
A83 Garron Bridge	3	3	0	0.0	0.0	0.0
A83 Rest and Be Thankful	4	7	0	0.0	0.1	0.0
A815 Strachur	3	3	2	0.1	0.1	0.0
A83 Inveraray Town Centre	0	0	0	0.0	0.0	0.0
A83 Lochgilphead	0	0	0	0.0	0.0	0.0
B840 Ford	0	0	0	0.0	0.0	0.0

10.5.5 *Table 10-5* shows there would be a small increase in road traffic accidents forecast because of cumulative development. The forecast increases are considerably smaller than 1 additional road accident on each road link with the largest increase being an additional 0.4 serious accidents on the A819 Dalmally road link. The effect on road traffic accidents is therefore considered to be minor.

10.5.6 The full calculations to arrive at these forecasts is contained within Annex M Accident Forecast Calculations.

11. Framework Construction Traffic Management Plan

11.1 Purpose

11.1.1 The purpose of this Framework CTMP is to provide a framework from which a finalised CTMP can be developed post-consent. This Framework outlines the measures which could be used during the construction of the Development to mitigate transport-related impacts. Access to the Development by HGVs and construction plant vehicles would be planned, managed, and executed by the applicant's appointed contractor to ensure the safety and reliability of deliveries to Site, reduce congestion on the local road network and minimise the environmental impact.

11.2 CTMP Development

- 11.2.1 The opportunity to develop, amend and enhance the finalised CTMP in response to comments received on this Framework document and through the planning and consultation process should be recognised.
- 11.2.2 The CTMP would consider feedback from local residents and community groups and be developed in consultation with Argyll and Bute Council to establish the appropriate methods in which the impact of traffic related to the Development's construction can be minimised.
- 11.2.3 This document would be updated as necessary with input from Argyll and Bute Council following feedback from their consultation and planning process.

11.3 Hours of Work

- 11.3.1 Working hours for construction activities related to the Development would be agreed with Argyll and Bute Council, but are anticipated to be:
 - 07:00 to 19:00 Monday to Friday.
 - Saturday 07:00 to 13:00; and
 - No construction should be carried out on Sundays or bank holidays unless in exceptional circumstances
 - Any work which is required or intended to take place outside of these hours, except for emergency situations, would be subject to prior agreement and/ or reasonable notice to Argyll and Bute Council.

11.4 Site Access

- 11.4.1 The Site would be secured by hoarded gates and during working hours would remain under control of an appointed person who would physically control entry to Site. Traffic entering or exiting the Site would give way to road traffic on the public road network (when required). Vehicles would leave and access the site via the proposed site access tracks and no vehicles would be required to stop on the public highway itself when accessing the Site.
- 11.4.2 Warning signs would be established and maintained throughout the duration of construction works and would be situated at agreed locations to warn road users of the access.

11.5 Construction Traffic Routing

- 11.5.1 It will be a key responsibility of the Applicant or appointed contractor to ensure that each sub-contractor is aware of the route restrictions prior to any works taking place and to enforce the restrictions stated in the Development's CTMP.
- 11.5.2 The Site gates would be manned and controlled during normal Site working hours and any vehicle arriving on Site will be guided to the required location for loading or unloading.
- 11.5.3 The appointed contractor would also be responsible for mitigating, where possible, the cumulative impacts of other construction projects in the area through careful consideration of routing and access timings.

- 11.5.4 Likely routes that construction traffic will follow will be:
 - A85
 - A83
 - A819
 - Proposed Inveraray Bypass
- 11.5.5 It is considered that each of these routes can accommodate the additional construction traffic required for the Development. Staff will make their own way via a variety of routes depending on their home location but the impact of staff journeys on the local road network is expected to be negligible.

11.6 Deliveries

- 11.6.1 Due to the scale of the Development, the number of daily deliveries to Site throughout the construction phases is anticipated to be high and the disruption imposed on other road users would be minimised due to the scheduling of deliveries and material removal.
- 11.6.2 Construction materials that are delivered will be stored on-site.

11.7 Enforcement

11.7.1 All contractors would be required to adhere to the CTMP. Compliance will be monitored by the applicant's Site representative via spot checks to ensure that vehicles follow the measures set out in the CTMP.

11.8 Speed Limit

- 11.8.1 The applicant would ensure that all Site traffic abides by local speed limits to maintain the safety of other road users and pedestrians. A Site speed limit of 5 mph would be established and enforced throughout the duration of construction works to provide a safe environment for Site workers and any pedestrians which pass the Development.
- 11.8.2 Signage would be in place prior to any works taking place which will advise of any temporary speed limits which are in force and all Site workers or haulage sub-contractors would be made aware of the speed requirements as part of their Site induction.

11.9 Summary

- 11.9.1 This chapter discusses the potential traffic management arrangements during construction at the Site and provides an assessment of the impacts on the Site during this period.
- 11.9.2 The hours of work at the Site are expected to be 07:00 19:00 from Monday to Friday and 07:00 13:00 on Saturdays with no work taking place on Sundays and bank holidays.
- 11.9.3 The Site would be secured by hoarded gates and during working hours would remain under control of an appointed person who would physically control entry to Site. Traffic entering or exiting the Site would give way to road traffic on the public road network (when required). No construction vehicles would require stopping on the public highway.
- 11.9.4 It is anticipated that the likely routes of construction traffic would be via the A85, A83, A819 and Inveraray Bypass. Access to the site from the public highway will be facilitated by upgrading existing access tracks. It shall be the responsibility of the appointed contractor to assess these routes for restrictions and mitigate any cumulative impacts of construction traffic.
- 11.9.5 The number of deliveries to the Site is anticipated to be low with all construction materials to be stored and secured on Site.
- 11.9.6 All traffic will abide by local speed limits with a 5mph speed limit enforced within the Site.

12. Summary and Conclusions

12.1 Summary & Conclusions

- 12.1.1 AECOM has been commissioned by Applicant to prepare a Transport Impact Assessment (TA) to accompany an Environmental Impact Assessment (EIA) Chapter (*Chapter 14: Access, Traffic and Transport*) (*Volume 2: Main Report*) for a pumped hydro storage development (the Development) near Balliemeanoch Farm Steading, Argyll and Bute.
- 12.1.2 The TA includes a review of relevant national, regional, and local transport policy.
- 12.1.3 The transport baseline includes a review of existing infrastructure as well as baseline traffic data, gathered by undertaking traffic surveys on the local road network during June 2023. The baseline review also considers the accident history of Study Area roads.
- 12.1.4 The Development is a PSH facility and is likely to be constructed over a programme lasting 7 years. It is proposed that access to the site will be taken from A819 via existing access tracks which will be upgraded. It is also proposed to upgrade existing tracks at Inveraray Castle and Upper Avenue to divert HGV traffic and AIL traffic respectively from Inveraray town centre. The proposed upgrade to Upper Avenue will connect to a jetty on Loch Fyne which shall be used to deliver AIL components to site.
- 12.1.5 A construction programme has been provided which shows that the peak period of construction traffic will be in November 2027. It has been demonstrated how the peak vehicular trip generation of the site has been calculated.
- 12.1.6 The assessment of environmental effects contained within *Chapter 14: Access, Traffic and Transport* (*Volume 2: Main Report*) requires that each road link is assessed for the sensitivity of its receptors. This assessment is included within this TA.
- 12.1.7 The IEMA Guidelines 2023 set out the process by which the fear and intimidation assessment for environmental impact assessments should be undertaken. This assessment is included within this TA.
- 12.1.8 Swept path analysis has been undertaken at various points within the Study Area, including the proposed Inveraray Bypass and Upper Avenue AIL route. It has been demonstrated that these routes can accommodate the construction vehicles proposed to use them.
- 12.1.9 The background for the cumulative development assessment is contained within this TA, analysing 4 cumulative development sites.
- 12.1.10 A Framework Construction Traffic Management Plan is provided, providing a high-level overview of some measures which could be included within the full CTMP. The full CTMP will be the responsibility of the contractor once appointed.

Annex A – Scoping Correspondence

Development and Economic Growth

Acting Director: Kirsty Flanagan



Helensburgh and Lomond Civic Centre, 38East Clyde Street, Helensburgh G84 7PG
Tel: 01546-605-552

22 September 2022

Our Ref.: 22/01453/SCOPE Your Ref.: ECU00003444

Contact: Mr D Moore

Direct Line: (01436) 658916

e-mail address: david.moore@argyll-bute.gov.uk

Scottish Government Energy Consents Unit 5 Atlantic Quay 150 Broomielaw Glasgow G2 8LU

FAO: Joyce.Melrose@gov.scot

Dear Sirs,

ELECTRICITY ACT 1989

THE ELECTRICITY WORKS (ENVIRONMENTAL IMPACT ASSESSMENT) (SCOTLAND) REGULATIONS 2017, SCOPING OPINION REQUEST FOR PROPOSED NEW PUMPED STORAGE HYDRO SCHEME AT BALLIEMEANOCH.

Section 36 Proposal by Intelligent Land Investments (ILI)

I write in reference to your consultation regarding the above and would thank you for agreeing to extend the timescales to allow additional time for this response. Please find the Council's consultation response to the scoping request enclosed.

I should point out that the issuing of this scoping consultation advice should not be taken to indicate support for the proposal on the part of Argyll and Bute Council. The Council's recommendation on any future S36 application would rely upon the consideration of the content of any accompanying environmental information, the responses of consultees, the views of third parties and any other material planning considerations which would be reported to Members to obtain their views.

Please note that in terms of the Council's 'Argyll and Bute Local Development Plan' (adopted 2015) the Council will support renewable energy and associated infrastructure developments where these are consistent with the principles of sustainable development and it can be adequately demonstrated that there would be no unacceptable significant adverse effects, whether individual or cumulative, including on local communities, natural and historic environments, landscape character and visual amenity, and that the proposals would be compatible with adjacent land uses and the Planning Policy Objectives of the Statutory Planning Framework in place at time of submission and determination of the S36 proposals



In respect of the Local Plan Planning Policy framework. Your attention is drawn to the emerging LDP 2. Depending upon the date of any future application this may have reached a stage in the adoption process where the weight to be afforded to this will be increased or it may be adopted.

I trust you find the enclosed information of assistance.

Yours sincerely

David Moore

Senior Planning Officer Argyll and Bute Council



APPENDIX A ELECTRICITY ACT 1989

THE ELECTRICITY WORKS (ENVIRONMENTAL IMPACT ASSESSMENT) (SCOTLAND) REGULATIONS 2017

SCOPING CONSULTATION RESPONSE ON BEHALF OF ARGYLL & BUTE COUNCIL FOR PROPOSED SECTION 36 APPLICATION.

PROPOSAL: PROPOSED NEW PROPOSED NEW PUMPED STORAGE HYDRO SCHEME AT BALLIEMEANOCH.

DESCRIPTION OF PROPOSALS

The Applicant proposes to construct a Pump Storage Hydro (PSH) scheme close to Lochan Airigh approximately 4.4 km to the south of the village of Portsonachan and 9 km northwest of Inveraray in Argyll and Bute as shown on Figure 1.1 Location Plan. The applicant confirms that the Development Site was identified from a Scotland-wide site search exercise and is considered suitable due to a number of factors such as topography, underlying geology, and an appropriately sized catchment. The proposed Development will discharge water from its tailrace back into Loch Awe which is also utilised by the existing Cruachan scheme. Cruachan is a 440 MW pumped storage hydro-electric scheme which has been operating since 1965. There is a current S36 application lodged with the Scottish Minsters for an expansion of the Cruachan scheme.

The total area within the Development Site boundary is approximately 3,054 hectares (ha). The applicants clarify that of this area within the Development Site boundary will be developed). Balliemeanoch PSH will have a storage capacity of up to 45,000 megawatt hours (MWh) with up to 1,500 MW installed electrical generation capacity.

BUILD ELEMENTS

In respect of the current proposals the applicant confirms that these will involve the following main build elements:

- **Headpond** The upper reservoir, including embankment or dam. The headpond intake tower total estimated height is 60 m. Approximately 40 m below water and 20 m above top water level.
- Embankment Embankments or dams around the headpond reservoir/water body.

There are three proposed embankments. The maximum embankment height is 110 m high above existing ground level. (425m AOD)

Embankment Height 1 (Main) 110 m Embankment Height 2 (North) 15 m Embankment Height 3 (East) 20 m

- Reservoir Water body retained within the headpond embankments and the tailpond.
- **Tailpond** The lower reservoir. In this case this is the existing water body of Loch Awe.
- **Inlet / Outlet** The location where the tunnels (headrace / tailrace) enter the headpond and tailpond.
- Headrace The underground high-pressure tunnel connecting the headpond to the power



cavern.

- **Tailrace** The underground low-pressure tunnel connecting the power cavern to the tailpond.
- **Power Cavern** This is a below-ground component that will contain the combined pump / turbines, generators, switchgear and transformers.
- Cable Tunnel The underground tunnel hosting the power cables which will export the generated power from the underground power cavern to the surface at the sub/ switching station.
- **Access Tunnel** The underground tunnel providing access (construction and operation) to the power cavern.
- **Sub / switching station** This station will be an above-ground component that will consist of a secure electrical compound in which electrical equipment will be housed.
- **Spillway /Spillway Channel**. This spillway will consist of a buried pipeline and will be used as a system to drain any excess water from the headpond as well as being used for the scouring and draining down of the headpond in an emergency situation.
- **Surge Shaft(s)** Structures that are provided along the waterways to contain pressure fluctuations within the hydraulic system. The low-pressure tunnel surge shaft will be underground. The high-pressure tunnel surge shaft will be underground but may have section cut into the hillside (subject to design).
- Pier Structure at Inveraray Marine Facility Located on the coast near Inveraray, this
 facility is predominately temporary and will be used for large deliveries to site. The marine
 structure will be a pier structure that will project into Loch Fyne. The height / depth of the
 structure is determined by the seabed and tidal range. Dolphin structures, or equivalent,
 could be associated with the marine structure. These will be used for mooring larger
 vessels to the structure.
- Access Tracks
- Compounds Temporary and permanent compounds will be required across the
 proposed Development. Some will be used for construction related activities such as
 laydown areas, work yards and for general site maintenance. Others will be used for office
 space, parking areas, welfare areas, and accommodation. These may include electric
- **Temporary Accommodation** Some temporary accommodation will be provided within the above compounds, with an additional offsite camp required. It is estimated that the potential footprint of the offsite camp could be approximately 50,000 m² (subject to design). This temporary accommodation will likely be located close to the Development Site and/or along one of the construction access routes. This offsite location has yet to be identified with the relevant studies currently being undertaken.
- charging points for electric shuttle cars/buses.

CONTENT OF SCOPING REPORT

The following matters are addressed in the main chapter headings of the Scoping report

- Landscape and Visual Assessment
- Terrestrial Ecology
- Aquatic Ecology
- Marine Ecology



- Ornithology
- Geology and Ground Conditions
- Water Environment
- Flood Risk and Water Resources
- Cultural Heritage
- Access, Traffic and Transport
- Noise and Vibration
- Socio-Economics, Recreation and Tourism
- Climate
- Arboricultural Impact Assessment
- Marine Physical Environment & Coastal Processes
- Shipping and Navigation
- Commercial Fisheries

The Council is in general agreement with the topics identified in the Scoping Report for evaluation.

LANDSCAPE CHARACTER AND VISUAL IMPACT

The proposed development is located within the North Argyll Area of Panoramic Quality (APQ). Although this is not a national designation it is a development plan designation and reflects both the high quality and sensitivity of the landscape.

In the opinion of the Planning Authority the absence of any clear information associated with the temporary accommodation, location, design and potential impacts over a lengthy construction period (5 years) require to be included in any LVIA exercise. AS does restoration proposals to ensure that no long term adverse landscape/ecologica/peat impact is caused.

The need to ensure cumulative impacts of future development proposals are considered is acknowledged at 5.2.3 and 5.4.8. This is an area of Argyll which is currently subject to considerable number of large infrastructure proposals including S37 Power Line proposals by SSEN and large scale substation proposals at the current time. A current S36 application for an expansion to Cruachan is also before the ECU at the current time with impacts in terms of construction, waste movement and also extraction of water.

On this basis it is considered that landscape impacts, both in respect of the current proposals and associated infrastructure on landscape, together with a cumulative impact analysis in terms of the inter relationship between this proposal and other large infrastructure projects in the APQ area, are properly evaluated and considered in the EIAR at time of submission.

It is anticipated by the applicants that ten compounds will be required for the construction period and that four of these would be retained for the full duration of the proposed Development. The proposed locations use and approximate size of each of the compounds are detailed in Table 2.3 Proposed Construction Compounds and are shown on *Figure 1.2*. Table 2.3 indicates a total site area associated with construction compounds of some 73,000sqm and text further clarifies that:

The proposed construction compounds will be constructed with a mixture of imported material at the commencement of construction works, following which material that is generated from the tunnelling activities will be used. The compound surfaces are anticipated to be unsealed (stone, metalled or gravel surface) in nature and will be either floated (over peat) or built into the hillside depending on the site conditions and anticipated loads. Compounds 5, 6, 7, 8, 9, and 10 will be removed and the areas reinstated once construction is complete.

This is a significant area and although such impacts are most likely temporary, the EIAR requires to clarify impact, mitigation and restoration in respect of any compounds being formed given their scale and length of requirement. (5 year build programme)



It is welcomed that the applicants confirm at 2.7.2.5 that:

The offsite location for temporary workers' accommodation has yet to be identified with the relevant studies currently being undertaken. The Applicant will continue to liaise with the relevant stakeholders to determine this location. As part of this, the Applicant is committed to investigating the provision of permanent housing to the local market.

If this accommodation is proposed within the countryside and not within any settlement envelope or identified site suitable for such construction then LVIA analysis of potential impacts and construction activity associated with the provision of this such development will in the opinion of the planning authority be required as part of the application submission and not left to a conditional matter. However it is hoped that discussions over providing accommodation which may be able to be utilised by the community in the future will be able to be undertaken. At the present time, as no identified locations have been provided it is not considered appropriate to automatically scope such matters out and further details require to be provided as part of the S36 submission.

In terms of the suggested viewpoints as set out at Figure 5.6. Officers consider that views from the Duncan Bann Monument (near Dalmally) should be added as this is a popular and widely visited location for tourists and locals. It is located to the north east of the proposed development and may afford views of the headpond. Views from open water within Loch Awe at maximum visibility locations would also be recommended as this is a popular recreational Area both in summer and in winter associated with boating and fishing..

TRANSPORT AND WASTE MANAGEMENT

The applicants at 2.3 confirm that:

- There are no classified roads or tracks within the Development Site at the headpond or tail
 pond location. However, at Inveraray there is a <1 km section of classified road (A83) at the
 proposed pier location.
- Site access is proposed off the A819 which links the strategic trunk roads A85 to the north
 at Dalmally and A83 to the south at Inveraray. It is anticipated the general construction
 access will come from the north and south along the A819. Construction access from the
 south will bypass Inveraray via a section of unclassified existing track (to be upgraded)
 north of Inveraray Castle which will connect the A83 to the A819.
- Larger construction traffic, such as abnormal loads, will be delivered by boat to the
 proposed pier, where they would be transported to site via the A819. Access to the A819
 will be via an upgraded existing access track that runs to the north, then east, from the A83,
 around the north of Inveraray. There are proposed upgrades to the existing unclassified
 road "Upper Avenue" at Inveraray and a new track linking this to the A83 at the proposed
 pier location.
- These upgrades are proposed to ease traffic and to avoid sensitive bridges within the area
 of Inveraray.

The Scoping Report clarifies that:

From the A819, it is proposed that access will be gained from two existing forestry tracks located at NN 08853 12473 and NN 10064 19980. Each of the proposed access routes will utilise existing forestry tracks as far as possible with some stretches of new track to be constructed. Both access tracks will link the A819 with the proposed headpond area located near Lochan Airigh as shown in Figure 1.2 above Ground Infrastructure.

Internal site access tracks will be required linking the Development components. These will be a mixture of permanent and temporary tracks to enable construction. These tracks will either be sealed or unsealed in nature. Existing access tracks and infrastructure will be utilised as far as possible; however, it is noted that the existing infrastructure such as bridges, culverts, and roads



may require upgrade. The material that will be used to construct the tracks will be made up of both imported material and material that is sourced from within the Development Site.

Access requirements between the construction compounds and the various work areas will change throughout the construction period. The majority of the traffic will be general construction vehicles such as dump trucks, HGV's and general large plant and equipment. General site traffic such as vans, minibuses, and four-wheel drive vehicles will also use the road network.

Construction traffic routes will be developed in parallel with the EIA and will take account of the suitability and capacity of local roads. If any existing roads need to be crossed, they will be crossed perpendicular so as to reduce the potential impact from construction traffic.

Para 2.7.2.2 further clarifies that:

The main vehicle movements would occur during the middle of the construction period, whilst the major earthworks above and below ground are underway. It is anticipated that the large plant and equipment will remain inside the construction areas for each component of the proposed Development and the operators and staff will be shuttled around site via light vehicles such as vans, minibuses and pickup trucks. Also included in the areas will be temporary fuelling stations with fuel bowsers and pumps although it is hoped that alternative fuels will be available in time for construction.

The tunnel boring machine (required if drill and blast construction of the tunnels not suitable) will be transported to the new marine facility, located on Loch Fyne, in a vessel. The components will then be transferred to land by either a roll on roll off vehicle or heavy lift equipment from a vessel to a transporter on land. The components will then be transported to site on the back of a specialised transporter either via the northerly or southerly access route from the A819 to the main development site. The marine facility area, as shown in Figure 1.2 above Ground Infrastructure, will consist of a marine facility that is expected to have both temporary and permanent components. The marine facility will accommodate the delivery of large components associated with the tunnelling and mechanical and electrical components. Several different types of plant and equipment will be required for the construction and operation of the proposed marine facility.

It is noted that the scoping report clarifies that;

The proposed Development requires a significant amount of material to construct the impoundment structures of the headpond. The design, shape, and size of the impoundment will be confirmed through the EIA process. However, at this stage, it is anticipated the main embankment structure could be around 110 m high and have a volume of around 4,600,000 m³.... The approximate material volume calculations are provided in Table 2.5. This is indicative at this stage until preliminary site investigation works have been undertaken in order to inform the design of the proposed Development and the cut and fill balance calculations. Therefore, it is proposed to provide an MMA as part of the EIAR which will provide additional information on the type and volume of materials generated from the proposed Development. This will also determine the requirement for any permanent storage of material which could be considerately landscaped, as opposed to significantly impacting the local transport network with movements offsite.

There will be a requirement to ensure that any proposals which would impact the roads network taken into account cumulative impacts on the network having regard to the fact that a large number of energy related infrastructure projects are proposed in the area. This is a potentially significant impact, not just in terms of road safety and capacity, but also in terms of the wider economy of Argyll and Bute if vital arteries are congested due to ongoing construction of both this and other S36 and S37 projects in the vicinity by both SSEN and Drax (Cruachan) as well as Windfarm and large SSEN substations.

The potential/confirmed construction phasing of other major infrastructure construction projects requires to be evaluated when the EIAR is submitted and not be left as a matter for conditional approval under any deemed consent, as a high level strategic review of road capacity and safety with Transport Scotland and the Argyll and Bute roads is considered to be required and may become a defining matter in the determination of the applications and not a matter suitable to be



addressed by conditions.

The applicants confirm that:

Due to the volume of material anticipated to be required for the construction of various components, a Materials Management Appraisal (MMA) will be undertaken as part of the EIA process and updated prior to construction, to ensure that the material that is generated from construction is classified and reused as far as practically possible

This is a welcomed commitment and waste management, materials and equipment importation and analysis of the safe capacity of the local road network is considered by the Planning Authority to be a substantive matter for the EIAR to address by submission and not a matter for conditional approval.

It is welcomed that the applicants confirm that:

The intention is to use as much of the rock / surplus material generated on site to construct the proposed Development components (embankment, roads, and concrete structures) whilst reducing the excess material to a minimum.

Officers are aware of the need to extract and export large volumes of rock/waste material from the Cruachan expansion proposals if this is approved and proceeds. It is considered that a "duty to cooperate" utilising best endeavours between the two S36 Hydro proposal developers should be required by the Scottish Ministers to ensure any waste from Cruachan which could be utilised at Balliemeanoch is not transported away from the local area if it has the potential to be used locally in accordance with sustainable objectives. A commitment to investigate such an agreement as part of the application proposals should in the opinion of the Planning Authority be provided as part of any S36 application submission.

ECOLOGY /NATURE CONSERVATION/MARINE ENVIRONMENT

The scoping report at 2.7.4.5 clarifies that once the proposed Development is fully commissioned, the working water volume will pass between the headpond and Loch Awe in order to provide the storage and generate electricity at peak times. It is anticipated that the average drawdown level of the headpond will be between 420 and 340 m AOD. The estimated drawdown in Loch Awe, when at Top Water Level (TWL), is estimated to be around 1 m.

The applicant's state that a management/ water use agreement will need to be agreed with other water users in the Awe catchment to ensure there is sufficient water resource for all parties. It should be noted that a PSH scheme will tend to operate on cycles that are dictated by the energy markets, it is therefore considered unlikely that the scheme will fully empty then immediately fill.

Given that there is also a current S36 application to expand Cruachan, there is a need to ensure that potential cumulative impacts of maximum simultaneous water draw for both schemes is considered unless a mechanism to restrict /avoid such a scenario can be suggested by Scottish Ministers. It is the opinion of the Planning Authority that such matters should not be left to the operational cycles of the energy markets to dictate the evaluation of potential maximum draw/discharge scenarios if both Cruachan and Balliemeanoch are operating.

Marine Policy Officer Comments

Overall Scoping Opinion

• It is the Officer's opinion that the proposed development does constitute an Environmental Impact Assessment (EIA) as defined under Schedule 2 of the EIA Regulations. The proposal will also require planning permission for any quayside and or pier/jetty construction, and will need to consider cumulative infrastructure impacts during the works and to ensure continued safe access / egress during this time. I further recommend that a precautionary approach be undertaken for the duration of works.



- The EIAR must provide updated site survey information where appropriate; all surveys and data sets after two years must be updated.
- Together with the EIAR, the applicant is requested to submit their Intertidal Phase 1 Survey, Subtidal Benthic Survey, and walkover fish habitat assessment.
- The applicant is requested to submit a Construction Environment Management Plan (CEMP) and Method Statement for all aspects of the proposed development. With respect to the marine and coastal environment, the CEMP must include a Noise Method Statement for impact piling and include all management plans as set out under section 3.4.1.6 Mitigation.
- In terms of possible introduction and spread of marine Invasive Non-Native Species (INNS), the applicant is requested to submit a Biosecurity Management Plan.
- In terms of water quality, drainage and flooding; all water assessments are to be submitted with the EIAR.
- The applicant is requested to submit a bathymetric survey, review of geotechnical information, a sediment dispersion study, and sediment sampling analysis for the Marine Facility in Loch Fyne.

Section 2.7.2.3 - Materials Management

- 1. It is welcomed that the applicant is proposing to apply for a Waste Management Licence (WML) and develop a Waste Management Plan (WMP) in support of their EIA.
- 2. I further welcome the proposed Materials Management Appraisal (MMA) to be included within the EIAR.

Chapter 5 – Landscape and Visual Amenity

- The Marine Facility proposal at Newtown, Loch Fyne is located within a Main Settlement Zone and the West Loch Fyne Local Landscape Area (LLA), as identified in the adopted Local Development Plan (LDP) 2015.
- Balliemeanoch, West Lochawe is located within the Lorn and Inner Isles Rural Opportunity Area, and the catchment of the Allt Beochlich watercourse is located within Lorn and Inner Isles Very Sensitive Area.
- Given the proposal is highly likely to have visual impacts and cumulative effects during and after the construction phase, the applicant is requested to submit a final Landscape and Visual Impact Assessment (LVIA) together with a Zone of Theoretical Visibility (ZTV), including schematics and photomontages from key viewpoints in support of their application at the final planning stage.
- The development's design and scale should respect the character and appearance of the surrounding area, and be consistent with Policy LDP 9 Development Setting, Layout and Design, associated Supplementary Guidance and the Argyll and Bute Landscape Capacity Assessment.

Chapter 7 – Aquatic Ecology

• The Awe catchment is the largest and most diverse freshwater catchment area in Argyll, which sustains a variety of fish species and habitats that are an important part of the region's biodiversity. These freshwater habitats include; streams, rivers and lochs, which is an important fishery for Atlantic salmon (Salmo salar), brown trout (Salmo trutta), European eel (Anguilla Anguilla) and lamprey species. The Atlantic salmon is protected in its freshwater life-cycle stages under Schedule 3 of the Conservation (Natural Habitats, &c.) Regulations 1994, and is a UK Biodiversity Action Plan (BAP) priority species. Brown trout are also a UK BAP priority species. The health of salmonids and other fish populations are dependent on clean freshwater habitats



throughout the catchment. The general trends in abundance of fish indicate a decline in natal species with consequences for the performance of the fisheries. Human-derived pressures acting on freshwater habitats include; forestry, agriculture, infrastructure development including the increasing development of renewable energy schemes (Awe Catchment Fishery Management Plan 2014-19).

- Loch Awe and its catchment is an important migratory route for salmonids. Changes to water flows can impede successful migration up stream. Correct water flows are essential for allowing access to spawning grounds, including a sufficient water level for the survival of buried eggs. It will therefore be important that throughout the construction and operational phases, the applicant is advised to ensure that all naturally available habitat is accessible to fish, including: sufficient water flows; the hydrology (drainage), underlying geology, and geomorphology is not affected, and to provide mitigation against any habitat loss/damage through a habitat restoration programme.
- The electric fishing and e-DNA surveys that were conducted in October 2021 are welcomed. The field survey results to be published in the Ecological Impact Assessment (EcIA) component of the EIAR is further welcomed and is to be submitted with the EIAR.
- In addition to the previous surveys conducted, it will be important to note that a precommencement walkover Scottish Fisheries Coordination Centre (SFCC) fish habitat assessment should be undertaken on the Allt Beochlich watercourse and main tributary watercourses of Loch Awe and Loch Fyne. The assessment should aim to quantify and evaluate the condition of freshwater habitats utilised for recruitment by fish, and in particular salmonids prior to the commencement of the Construction Phase.
- The applicant is to note that a 'soft start' approach to deter fish from the immediate area and all impact piling works across the development should not be undertaken during the salmonid smolt migration period (March to end of June).
- The applicant is advised to consult with Argyll Fisheries Trust (AFT), Argyll District Salmon Fishery Board (ADSFB) and the Awe District River Improvement Association (ADRIA) in the first instance for further advice on survey methods.
- Otters are classed as European Protected Species (EPS) under the Conservation (Natural Habitats, &c.) Regulations 1994, as translated into domestic legislation post-Brexit and via the Wildlife and Countryside Act 1981 (as amended).
- The applicant has undertaken a survey for protected mammals that included otter. A preconstruction survey and general good practice measures are advised. Welcome mitigation measures as outlined in Section 6.5 Likely Mitigation Measures.
- o An EPS Licence to conduct works will be required through NatureScot: -

https://www.nature.scot/professional-advice/protected-areas-and-species/licensing/species-licensing-z-guide/otters/otters-licences-development.

Chapter 8 – Marine Ecology

- Upper Loch Fyne is designated as a Nature Conservation Marine Protected Area (NCMPA) for burrowed mud habitat and flame shell beds, and has a Marine Conservation Order in place to protect the horse mussel beds. It is important to note that Priority Marine Features (PMFs) have also been recorded in the development area for the proposed Marine Facility, and include:
- o kelp and seaweed communities on sublittoral sediment;
- o fireworks anemone (Pachycerianthus multiplicatus);
- o tall seapen (Funiculina quadrangularis);



- o mud burrowing amphipod (Maera loveni).
- As the construction and operational phases may have Likely Significant Effects (LSEs) to the benthic habitats and PMFs, it is therefore agreed and welcomed that the applicant undertake an Intertidal Phase 1 Survey and a Subtidal Benthic Survey as discussed under section 8.3 Methodology of the Scoping Report. The applicant is further advised to consult with NatureScot to confirm appropriate survey methodologies.
- Loch Shira is an important nursery area for salmon and sea trout populations, and is part of the Loch Fyne Marine Consultation Area.
- The 'Loch Fyne Coastal Strip' Shellfish Growing Water extends throughout most of the policy zone, except for the coastline from Newtown to 1 km north of Inveraray. Native oysters, Pacific oysters, and Purple sea urchin are farmed at Ardkinglas, Loch Fyne Oysters Ltd.

Possible Likely Significant Effects to cetaceans, seals, basking sharks

- Loch Fyne lies out-with formally designated areas for harbour porpoise (Phocoena phocoena), other cetaceans, seals, and basking shark (Cetorhinus maximus).
- It is however important to note that cetaceans, seals, and basking sharks that frequent the area can come into contact with vessel and pier operations. The applicant is therefore advised to operate vessels at low speeds. The Marine Mammal Monitoring Management/Sighting Plan with 'soft start' approach in place over the construction period is welcomed. The applicant is advised to log daily cetacean and basking shark sightings and prepare a report during the construction period. NatureScot should be able to provide further details and a suitable method.
- As a measure of good practice the applicant is advised to apply for:
- 1. European Protected Species (EPS) Licence for possible disturbance to cetaceans;
- 2. Under Part I, section 16(3)(i) of the Wildlife and Countryside Act 1981, a licence to disturb basking sharks (Cetorhinus maximus).

Underwater noise and pier structure piling works

- Limited information has been provided on the proposed piling works for the construction of the Marine Facility. It is recommended that the contractor provide within their Construction Environment Management Plan (CEMP) a Method Statement. The Method Statement must detail the proposed piling works, including duration, type of piling, predicted noise levels and mitigation measures that will be adhered to. The CEMP and Method Statement must be agreed by the Council in consultation with NatureScot prior to works commencing.
- In addition to the above, the applicant will adopt JNCC mitigation protocols to minimise disturbance to marine mammals from piling sound (JNCC, 2010); this approach is welcomed. The JNCC guidance is located under the following web link: Statutory nature conservation agency protocol for minimising the risk of injury to marine mammals from piling noise:

http://jncc.defra.gov.uk/pdf/JNCC Guidelines Piling%20protocol August%202010.pdf.

- The applicant is further advised to review The Protection of Marine European Protected Species from Injury and Disturbance Guidance for Scottish Inshore Waters (July 2020) document on the following web link:
- o https://www.gov.scot/publications/marine-european-protected-species-protection-from-injury-and-disturbance/.
- Shipping activities have the potential to introduce Invasive Non Native Species (INNS) into the waters and coastline of Argyll. I note that the applicant has not developed a biosecurity plan for the potential introduction and spread of INNS, namely; the carpet sea squirt

(Didemnum vexillum), the leathery sea squirt (Styela clava), and wireweed (Sargassum muticum). The applicant is requested to provide a Biosecurity Management Plan (BMP) with their EIAR. The BMP should detail good practice methods to avoid and limit the introduction and spread of INNS that relate to the shipping activities in particular.

- The applicant must adopt pollution prevent strategies for potential diesel, hydraulic and battery spillages into the environment (shoreline & at sea). Further to the applicant's pollution Likely Mitigation Measures outlined under section 8.5, it is advised that the contractor follow appropriate Pollution Prevention Guidelines located on the NetRegs and SEPA web links respectively:
- o https://www.netregs.org.uk/environmental-topics/guidance-for-pollution-prevention-gpp-documents/guidance-for-pollution-prevention-gpps-full-list/;
- o https://www.sepa.org.uk/regulations/water/guidance/.

Chapter 11 – Water Environment

- Under the SEPA Loch classification system, Loch Awe is classified as having an overall Moderate ecological status and a chemical status of Pass. The Awe catchment is classified as a Heavily Modified Water Body (HMWB) due to the alterations of the water body for hydroelectricity generation. SEPA should be able to advise if the proposal is likely to further significantly impact the Awe catchment. The proposed: Water Quality and Water Resource Impact Assessment, Hydromorphological Survey, and Water Framework Directive (WFD) Assessment are welcomed and should be submitted with the EIAR.
- The applicant is requested to submit full details of the Water Management Plan and Surface Water Drainage Strategy, including the Emergency Response Management Plan, and mitigation measures within their Flood Risk Assessment. It will be important that the proposed development does not attribute to an increase in excess surface and ground water accumulations. It will also be important that the development does not attribute to an increase in pollution and any siltation/spoil entering Loch Awe, including the Oban and Kintyre groundwater bodies, and private water supplies.
- The applicant is advised to adhere to good practice measures for working in and near to watercourses during the construction phase, and should include:
- o Installation of silt interception traps to minimise unchecked contaminated run-off;
- o Appropriate artificial drainage must be designed and installed;
- o Fuels and other chemicals must be stored securely within the site construction compound;
- o Appropriate wash-out facilities must be available for vehicles and machinery;
- o Trenches and excavations must be covered at the end of each working day.
- Abstractions and discharges are regulated by the Water Environment (Controlled Activities) (Scotland) Regulations 2011, more commonly known as the Controlled Activity Regulations (CAR) licence process. The applicant must apply for a CAR licence. Full details on how to apply for a CAR licence are located at: https://www.sepa.org.uk/regulations/water/.

SEPA will provide specific advice relating to the freshwater abstractions and discharges.

Existing Aquaculture and other users

• Dawnfresh Seafoods Ltd. operate two rainbow trout fin fish farms in Loch Awe. Existing hydro generation schemes may also be effected by the development. Depending on the volume of water abstracted over a 24 hour period, there may be an impact to Loch Awe ecology and its water



level. It will therefore be important for the applicant to consult with SEPA and other loch users prior to works commencing.

Chapter 12 – Flood Risk and Water Resources

• The applicant is to include a Flood Risk Assessment (FRA) within their EIAR. The FRA will comply with all related water policies as outlined under Local Development Plan (LDP) above.

Chapter 14 – Access Traffic and Transport

- Under Policy 42 Safeguarding Piers, Ports and Harbours; development proposals for a new temporary pier, port or harbour facilities will only be considered where it has been clearly demonstrated how the whole site including any related access and working areas can be restored to the satisfaction of the planning authority once the facilities are no longer required.
- The applicant must provide the proposed pier/jetty and wharf construction details within their CEMP and Method Statement together with their planning application. The proposal will need to consider cumulative infrastructure impacts during the works and to ensure continued safe access / egress during this time.

Chapter 15 – Noise and Vibration

- Mitigation measures to abate noise and vibration should be deployed during the construction and operational phase of the development. Predicted noise and vibration levels should be detailed within the CEMP and EIAR.
- As limited information is provided on the proposed impact piling works for the Marine Facility, the applicant/contractor is requested to submit a Noise Method Statement for the construction and operation that outlines timing, duration and expected noise levels. The Noise Method Statement should detail potential Likely Significant Effects (LSEs) and be agreed by the Planning Authority and NatureScot respectively prior to works being commenced.

Chapter 19 – Marine Physical Environment & Coastal Processes

Impacts on water quality (Loch Fyne)

- It is important to note that the Loch Fyne coastal strip is a shellfish growing water. Dredging impacts associated with the Marine Facility may have a Likely Significant Effect (LSE) to the 'Good' classification of the Upper Loch Fyne waterbody from siltation. If dredging and maintenance dredging is confirmed by the applicant, the use of a silt curtain boom is advised throughout all dredging periods to avoid siltation, sediment dispersion, and pollution events. It is further advised that the contractor consult with SEPA on this issue and follow appropriate dredging guidance located on the SEPA web link:
- o https://www.sepa.org.uk/regulations/water/guidance/#dredging.
- If dredging is a requirement of the Marine Facility, the applicant will need to apply for a Marine Licence to dredge from Marine Scotland Licensing and Operations Team (MS-LOT) and the Crown Estate (Scotland) respectively. All licensable marine work information is available on the following web links:
- o https://www.gov.scot/publications/marine-licensing-applications-and-guidance/
- o https://www.crownestatescotland.com/scotlands-property/coastal/marine-works.
- The proposed bathymetric survey, the detailed review of geotechnical information, and a sediment dispersion study around the marine facility area to understand potential coastal morphology and sediment transport at the site are required and must be detailed within the EIAR. As a matter of good practice, the effects of fine sediment dispersion due to maintenance dredging and disposal should not be scoped out of the EIAR. The applicant should explain

more thoroughly their reason for this.

- A sediment sampling analysis is further required and must also be detailed within the EIAR.
- A site walkover survey and development of a numerical hydrodynamic model are welcomed, and the results should be presented within the EIAR.
- The applicant is to note that the number of functioning sea outfalls identified in the Loch Fyne ICZM Plan may have changed since its publication in 2009. It is recommended that the applicant consult with SEPA and Scottish Water in the first instance to confirm existing and proposed sea outfalls in the vicinity of the proposed development.
- The monitoring of Total Suspended Solids (TSS) during the construction phase is welcomed, but if levels are exceeded, the applicant will need to address what appropriate action will be taken to ensure that adverse impacts are minimised and mitigated for.

Chapter 20 – Shipping and Navigation

• The applicant is advised to consult with Clydeport, Northern Lighthouse Board, Ministry of Defence, CalMAC, The Scottish Salmon Company, and the RYA to determine what would be the proposed affects to safe navigation and recreational boating during construction of the Marine Facility in Loch Fyne.

Chapter 21 – Commercial Fisheries

• The review of the commercial fleet and baseline assessment in Loch Fyne is welcomed. The applicant should provide a complete assessment of commercial fisheries to inform the EIAR and consult with the West Coast Regional Inshore Fisheries Group, and the Clyde Fishermen's Association in the first instance.

General comments

Interaction with other activities

- The Council is required to protect public access rights to and along the foreshore for all non-motorised users. Where there is a pier or breakwater structure that will obstruct access along a foreshore or loch side, a reasonable means of passing by the obstruction should be provided to allow the public to exercise their right of access along the shore, where appropriate.
- Any pier/jetty construction should be marked according to advice from the Northern Lighthouse Board.
- The proposal is a large engineering operation which is likely to have significant interaction with road transportation. However, the proposed development is considered to be consistent with the relevant policies of the Local Development Plan.

Pre-application discussion

• The applicant should undertake pre-application discussion with relevant stakeholders in addition to those previously discussed, including: SEPA, Scottish Water, NatureScot, AFT, ADSFB, ADRIA, Loch Fyne Oysters Ltd, and Dawnfresh Seafoods Ltd. in the first instance. Where appropriate, the applicant should provide a summary of pre-application discussion undertaken with key stakeholders in support of a full S36 application.



Biodiversity Officer Comments

No comments have been received at time of writing.

West of Scotland Archaeology Service Comments

I refer to the above scoping request. The scoping report cultural heritage section is quite general but I agree with the statements made and do not think that indirect/setting issues will form a major problem for the scheme. I agree there will be a major direct impact on undesignated sites and that a suite of mitigation will be required for dealing with this and the potential for buried remains in areas of proposed ground disturbance. I agree that walk over survey is required for areas of proposed ground disturbance and flooding and look forward to the EIA report in due course.

Area Roads Engineer Comments

These have not been received at time of writing. However the stated intention within the Scoping Report to discuss roads capacity/safety matters and potential cumulative impact issues with Transport Scotland and the Area Roads Manager prior to submission of the application is welcomed.

OVERALL CONCLUSIONS OF SCOPING REPORT

The Scoping Report at Table 3.2 summarises the matters to be evaluated within the proposed EIAR and also those matters which are proposed to be scoped out. This is set out below:

Table 3.2 Summary	, Proposed EIA Scope	
Environmental Topic	Proposed Scope of Assessment	Element Proposed to be Scoped Out
Landscape and Visual Assessment	Assessment of the effects on landscape character and visual amenity for construction, operation and decommissioning of the proposed Development.	Decommissioning
Terrestrial Ecology	Survey and assessment of:	Decommissioning
	 Habitats, including NVC; Protected mammals; Butterflies, dragonflies and damselflies; and Terrestrial and riparian invasive non-native species. 	
Aquatic Ecology	Survey and assessment of:	Decommissioning
	Habitats	
	• Fish	
	Aquatic macrophyte	
	Macroinvertebrate	
	 Freshwater invasive non-native species 	
Marine Ecology	Assessment of marine designated sites, benthic habitats and species, marine fish, elasmobranchs, marine mammals and marine invasive non-native species.	Decommissioning
Ornithology	Survey and assessment of habitats and breeding birds including raptor survey (including eagles), diver survey and moorland bird survey.	Decommissioning
Geology and Ground Conditions	Assessment of geology and hydrogeology including ground investigations and peat assessments.	Assessment of operational effects. Decommissioning
Water Environment	Assessment of water quality and water resource, hydrological assessment and a Water Framework Directive (WFD) assessment.	Decommissioning
Flood Risk and Water Resources	Production of Flood Risk Assessment and hydrological assessment	Breach analysis. Decommissioning
Cultural Heritage	Assessment of effects on cultural heritage assets and their setting that are within the zone of theoretical visibility up to up to 3km of the Development Site Boundary.	Decommissioning



Environmental Topic	Proposed Scope of Assessment	Element Proposed to be Scoped Out
Access, Traffic and Transport	Details of the proposed access route from the principal road network, the point(s) of access to the proposed Development Site and an indication of the likely number of vehicle movements and traffic management plans required during construction.	
Noise and Vibration	Assessment of construction and operation noise and vibration.	Baseline vibration survey. Decommissioning
Socio-economics, Recreation and Tourism	Assessment of the effects on the local community, local economy, recreation and tourism in the area.	Effects on business within the proposed Development Site. Population demographics. Decommissioning
Climate	Greenhouse Gas impact assessment.	Decommissioning
Arboricultural Impact Assessment	Identify trees to be removed and will consider any impacts to retained trees including how they can be protected.	Operation and Decommissioning
	Potential impacts of the proposed Marine Facility on physical marine and coastal processes.	Decommissioning
Shipping and Navigation	Potential impacts on current shipping and sea users from the movement of plant / material by sea and from construction of the marine facility.	Decommissioning
Commercial Fisheries	Potential impacts of the proposed Development on the receptor commercial fisheries.	Decommissioning

The matters identified for inclusion in the EIAR and also those matters identified to be scoped out as set out at table 3.2 are generally agreed by the Planning Authority. However it is considered that waste management should be specifically scoped into the EIAR to fully evaluate to what extent the objective of minimising importation of materials can actually be achieved. This can be included in the Access/Traffic and Transport section of the EIAR as it has direct relevance to the likely impact in respect of these matters, both in respect of this application, but also cumulative evaluation.

Given the amount of proposed S36, S37 and major application energy related infrastructure proposals either submitted or in the pipeline in the general North Argyll area the Planning Authority is becoming increasingly concerned about potential cumulative impacts and would request that the following matters are specifically scoped into the EIAR:

Cumulative Landscape Impacts

There is a considerable amount of major S36 and S37 energy related infrastructure applications either submitted or in the pipeline within the North Argyll Area. The Council is therefore concerned that cumulative impacts on landscape capacity to absorb all of this development is carefully evaluated as part of any EIAR submissions.

Cumulative Roads Impacts

It is noted that in this case the applicants seek to utilise a new pier and upgraded forest tracks to keep traffic off of the A819 in the proximity of Inveraray, and in transportation terms this would be welcomed if it is feasible to do so. However far greater detail on the actual engineering construction works is considered to be required as part of the EIAR in order to understand whether the importation of plant/materials and the handling or removal of any waste can realistically be undertaken with no material impacts on the road network or necessary upgrading works.

This is not considered a matter suitable for resolution through condition and should form part of the EIAR to provide confidence that promoted solutions are in fact deliverable.

A cumulative assessment in relation to other proposed major infrastructure projects in the area is also considered to be necessary at time of submission. The commitment to seek to agree these matters as set out at 14.3.1 of the Scoping Report is welcomed.

Cumulative Water Extraction and Discharge Impacts on Loch Awe

There is also a need to ensure that the cycles of water extraction to the main holding loch and that of the proposed Cruachan expansion from Loch Awe are fully considered as a potential cumulative extraction of waters to ensure that the marine environment is not adversely impacted through reduced water levels or any other related impacts.



Environmental Topic	Proposed Scope of Assessment	Element Proposed to be Scoped Out
Access, Traffic and Transport	Details of the proposed access route from the principal road network, the point(s) of access to the proposed Development Site and an indication of the likely number of vehicle movements and traffic management plans required during construction.	
Noise and Vibration	Assessment of construction and operation noise and vibration.	Baseline vibration survey. Decommissioning
Socio-economics, Recreation and Tourism	Assessment of the effects on the local community, local economy, recreation and tourism in the area.	Effects on business within the proposed Development Site. Population demographics. Decommissioning
Climate	Greenhouse Gas impact assessment.	Decommissioning
Arboricultural Impact Assessment	Identify trees to be removed and will consider any impacts to retained trees including how they can be protected.	Operation and Decommissioning
	Potential impacts of the proposed Marine Facility on physical marine and coastal processes.	Decommissioning
Shipping and Navigation	Potential impacts on current shipping and sea users from the movement of plant / material by sea and from construction of the marine facility.	Decommissioning
Commercial Fisheries	Potential impacts of the proposed Development on the receptor commercial fisheries.	Decommissioning

The matters identified for inclusion in the EIAR and also those matters identified to be scoped out as set out at table 3.2 are generally agreed by the Planning Authority. However it is considered that waste management should be specifically scoped into the EIAR to fully evaluate to what extent the objective of minimising importation of materials can actually be achieved. This can be included in the Access/Traffic and Transport section of the EIAR as it has direct relevance to the likely impact in respect of these matters, both in respect of this application, but also cumulative evaluation.

Given the amount of proposed S36, S37 and major application energy related infrastructure proposals either submitted or in the pipeline in the general North Argyll area the Planning Authority is becoming increasingly concerned about potential cumulative impacts and would request that the following matters are specifically scoped into the EIAR:

Cumulative Landscape Impacts

There is a considerable amount of major S36 and S37 energy related infrastructure applications either submitted or in the pipeline within the North Argyll Area. The Council is therefore concerned that cumulative impacts on landscape capacity to absorb all of this development is carefully evaluated as part of any EIAR submissions.

Cumulative Roads Impacts

It is noted that in this case the applicants seek to utilise a new pier and upgraded forest tracks to keep traffic off of the A819 in the proximity of Inveraray, and in transportation terms this would be welcomed if it is feasible to do so. However far greater detail on the actual engineering construction works is considered to be required as part of the EIAR in order to understand whether the importation of plant/materials and the handling or removal of any waste can realistically be undertaken with no material impacts on the road network or necessary upgrading works.

This is not considered a matter suitable for resolution through condition and should form part of the EIAR to provide confidence that promoted solutions are in fact deliverable.

A cumulative assessment in relation to other proposed major infrastructure projects in the area is also considered to be necessary at time of submission. The commitment to seek to agree these matters as set out at 14.3.1 of the Scoping Report is welcomed.

Cumulative Water Extraction and Discharge Impacts on Loch Awe

There is also a need to ensure that the cycles of water extraction to the main holding loch and that of the proposed Cruachan expansion from Loch Awe are fully considered as a potential cumulative extraction of waters to ensure that the marine environment is not adversely impacted through reduced water levels or any other related impacts.



The information contained at 12.3.1 is welcomed. However the EIAR should be required to specifically calculate maximum extraction for Balliemeanoch coinciding with maximum extraction from Loch Awe for the proposed Cruachan Extension. References to Market cycles being involved in defining such matters do not seem to clearly commit to undertaking this maximum extraction and discharge cumulative impact exercise.

I trust you find the above of assistance. Please do not hesitate to contact me if I can assist you further.

David Moore Major Applications Team 23 October 2017



Development Management and Strategic Road Safety **Roads Directorate**

Buchanan House, 58 Port Dundas Road, Glasgow G4 0HF Direct Line: 0141 272 7379, Fax: 0141 272 7350 gerard.mcphillips@transport.gov.scot



Energy Consents Unit The Scottish Government 5 Atlantic Quay 150 Broomielaw Glasgow G2 8LU Your ref: EC00003444

Our ref: GB01T19K05

Date:10/08/2022

Econsents_Admin@gov.scot

Dear Sirs,

ELECTRICITY ACT 1989

THE ELECTRICITY (APPLICATIONS FOR CONSENT) REGULATIONS 2017

REQUEST FOR SCOPING OPINION FOR PROPOSED SECTION 36 APPLICATION FOR BALLIEMEANOCH PUMPED STORAGE HYDRO SCHEME

With reference to your recent correspondence on the above development, we acknowledge receipt of the Scoping Report (SR) prepared by Aecom in support of the above development.

This information has been passed to SYSTRA Limited for review in their capacity as Term Consultants to Transport Scotland – Roads Directorate. Based on the review undertaken, we would provide the following comments.

Proposed Development

The proposed development comprises a Pumped Storage Hydro (PSH) scheme with a storage capacity of up to 45,000 MWh with up to 1,500 MW installed electrical generation capacity. The site is located approximately 4.4km to the south of Portsonachan and 9km north-west of Inveraray in Argyll and Bute. The nearest trunk road to the site is the A85(T) which lies approximately 8.6km to the north. The site will be accessed via the A819 local road. The SR states that in addition to the A85(T), the A83(T) would likely be used by a proportion of general construction traffic coming to the site from the east or south-west.

Assessment of Environmental Impacts

Chapter 14 of the SR presents the proposed assessment of the impacts associated with Access Traffic and Transport. We note that the thresholds as indicated within the Institute of Environmental Management and Assessment (IEMA) Guidelines for the Environmental Assessment of Road Traffic are to be used as a screening process for the assessment. Transport Scotland is in agreement with this approach.

The SR also indicates that potential trunk road related environmental impacts such as pedestrian delay, pedestrian amenity, accidents and safety etc will be considered and assessed where appropriate (i.e. where Institute of Environmental Management and Assessment Guidelines for further assessment are breached). These specify that road links should be taken forward for further detailed assessment if:

- Traffic flows will increase by more than 30%, or
- The number of HGVs will increase by more than 30%, or
- Traffic flows will increase by 10% or more in sensitive areas.

The SR indicates that the study area will include the A85(T), A83(T), A819, and the B840.

With regard to base traffic, the SR states that ATCs will be undertaken during a neutral month during 2022 which will provide two-way traffic flows and be classified by vehicle type, including HGVs. Figure 14.1 of the SR presents the proposed locations of these ATC counts. We note that in addition to A83(T) counts, only one count is proposed on the A85(T), located at Taynuilt – some 17km west of the junction of the A85(T) with the A819. Transport Scotland would state that base traffic in the vicinity of the A85(T)/ A819 junction should be used.

We note that it is proposed to establish design year traffic flows using "National Road Traffic Forecasts (Great Britain)," (NRTF) 'low' growth assumptions. Transport Scotland is satisfied with this approach.

We note that it is proposed that operational and decommissioning transport impacts will be scoped out of the EIAR. Transport Scotland considers this appropriate in this instance.

Abnormal Loads Assessment

We understand that development components will originate from the Inveraray Marine Facility. The SR states that it is not envisaged that abnormal load vehicles would use the A83(T); they will be transported to site via the A819 via an upgraded existing access track that runs to the north then east, from the A83(T), around the north of Inveraray. It also states that there are proposed upgrades to the existing unclassified road "Upper Avenue" at Inveraray and a new track linking this to the A83(T) at the proposed pier location.

Transport Scotland would state that any proposed changes to the trunk road network must be discussed and approved (via a technical approval process) by the appropriate Area Manager. At this stage, we would advise that 1:500 scale plans of any new or modified access from the trunk road should be submitted along with visibility splay plans. This will allow the standard of the junction to be assessed. It would be helpful to engage with the Area Manager for the A83(T) who is Neil McFarlane and who can be contacted at neil.macfarlane@transport.gov.scot.

Transport Scotland will require to be satisfied that any abnormal loads can negotiate the A83(T) junction, therefore, an Abnormal Loads Assessment and swept path analysis will be required.

I trust that the above is satisfactory and should you wish to discuss any issues raised in greater detail please do not hesitate to contact me or alternatively, Alan DeVenny at SYSTRA's Glasgow Office on 0141 343 9636.

Yours faithfully

Redacted

Gerard McPhillips


Transport Scotland Roads Directorate

cc Alan DeVenny – SYSTRA Ltd.

Annex B – Traffic Survey Data

		Virtual D	ay (7)																			Virtual Day	(7)																			
Time	Total						Classifi	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Speed B		· 1									
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5-	10 -	15 - 20			35 -	40 -	45 - 50	- 55 -	60 - 65	- 70 -	75 -	80 - 85	90 -	95 -	100 - 10	05 - 110			5 - 130 - 135 -	
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			10	15	20 2	5 30	30 - 33	40	45	50 55	60	65 70	75	80	85 90	95	100	105 1	10 115	120	125 130	0 135 140)
0000	13	0	9	0	2	0	1	0	0	0	1	0	0	0	3.3	0	0.0	0	0.0	49.3	55.6	0 0	0	0	0	0	0	2	5 3	2	0 0	0	0	0 0	0	0	0	0 0	0	0 0	0 0	7
0100	9	0	5	0	2	0	0	0	0	0	0	0	0	0	1.7	0	0.0	0	0.0	47	-	0 0	0	0	0	0	1	3	3 2	0	0 0	0	0	0 0	0	0	0	0 0	0	0 0	0 0	
0200	6	0	2	0	2	0	0	0	0	0	1	0	0	0	4.9	0	0.0	0	0.0	47.1	-	0 0	0	0	0	0	1	1	1 1	1	0 0	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
0300	5	0	2	0	1	0	0	0	0	0	0	0	0	0	5.9	0	0.0	0	0.0	48.2	-	0 0	0	0 (0	0	0	1	2 1	1	0 0	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
0400	15	0	7	0	5	0	0	0	0	1	2	0	0	1	7.7	0	2.9	0	0.0	47.8	57.2	0 0	0	0 (0	0	3	2	2 4	2	1 0	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
0500	31	0	18	0	8	1	0	0	1	2	1	0	0	2	7.4	0	0.9	0	0.0	49	57.8	0 0	0	0 (0	1	1	5	7 8	5	2 0	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
0600	73	0	48	2	12	1	3	0	1	2	4	0	0	6	8.1	0	0.4	0	0.0	49.5	56.8	0 0	0	0	0	1	5	12	19 20	10	4 2	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
0700	124	1	87	3	21	2	3	0	1	2	4	0	0	3	2.8	0	0.3	0	0.0	47.5	53.8	0 0	1	0	0	0	8	35	39 28	10	2 1	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
0800	187	2	133	3	33	3	6	1	1	1	3	0	0	4	1.9	0	0.2	0	0.1	46.5	52.8	0 0	1	0	1 1	4	14	51	64 37	10	3 1	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
0900	213	5	169	3	27	1	3	1	1	2	2	0	0	2	1.1	0	0.1	0	0.1	45.4	51.9	0 0	1	2	1 3	5	24	62	64 39	11	2 0	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
1000	265	9	200	5	38	2	2	1	2	2	2	0	0	4	1.5	0	0.1	0	0.0	44.8	50.6	0 0	1	2	1 1	8	32	90	84 34	9	3 1	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
1100	267	10	209	6	30	1	4	0	1	2	4	0	0	5	1.7	1	0.5	0	0.1	44.5	50.2	0 0	0	1	1 1	11	39	95	77 28	10	3 1	1	0	0 0	0	0	0	0 0	0	0 0	0 0	7
1200	291	11	228	8	34	0	2	0	2	2	3	0	0	5	1.8	1	0.2	0	0.0	44.3	50.4	0 0	3	2	1 2	9	42	101	85 33	9	4 1	0	0	0 0	0	0	0	0 0	0	0 0	0 0	7
1300	283	10	219	6	34	2	4	0	1	3	3	0	0	6	2.1	1	0.4	0	0.1	44	50.4	0 0	2	3	1 2	10	49	91	78 31	9	4 1	1	0	0 0	0	0	0	0 0	0	0 0	0 0	7
1400	274	9	218	5	32	2	2	1	1	1	3	0	0	4	1.6	1	0.4	0	0.1	44.9	51.1	0 0	1	2	1 0	7	41	85	83 37	12	3 1	0	0	0 0	0	0	0	0 0	0	0 0	0 0	
1500	275	9	222	3	29	1	3	0	1	1	6	0	0	6	2.1	1	0.4	1	0.2	45	51.3	0 0	2	2	1 2	7	34	88	85 36	12	4 1	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
1600	273	10	218	3	33	1	2	0	1	1	2	0	0	8	3.0	2	0.8	0	0.1	45.7	51.8	0 0	1	1	1 1	6	37	81	83 41	13	4 3	1	0	0 0	0	0	0	0 0	0	0 0	0 0	1
1700	241	4	203	2	22	1	2	0	1	1	4	0	0	7	2.9	1	0.2	0	0.0	46.2	52.9	0 0	1	1	1 1	7	26	61	76 42	16	5 2	0	0	0 0	0	0	0	0 0	0	0 0	0 0	
1800	186	2	161	2	16	0	2	0	0	1	1	0	0	6	3.3	1	0.8	1	0.3	47.9	54.1	0 0	1	0	0	2	13	43	64 40	17	4 1	1	0	0 0	0	0	0	0 0	0	0 0	0 0	1
1900	144	2	120	2	13	1	1	0	1	2	2	0	0	4	3.0	0	0.2	0	0.2	46.5	53	0 0	1	1	1 0	2	14	38	48 24	11	4 0	0	0	0 0	0	0	0	0 0	0	0 0	0 0	
2000	94	1	81	1	6	1	2	0	0	1	2	0	0	6	6.2	1	1.1	0	0.2	48.6	55.8	0 0	0	0 (0 0	1	6	21	29 20	11	4 2	1	0	0 0	0	0	0	0 0	0	0 0	0 0	1
2100	74	0	61	1	7	1	2	0	0	1	1	0	0	4	5.4	1	1.2	0	0.0	48.7	55.8	0 0	0	0	0 0	1	5	14	23 17	9	3 1	1	0	0 0	0	0	0	0 0	0	0 0	0 0	1
2200	37	0	31	0	3	0	2	0	0	0	1	0	0	1	2.3	0	0.8	0	0.0	47.3	54.5	0 0	0	0	0 0	1	2	8	12 8	4	0 0	0	0	0 0	0	0	0	0 0	0	0 0	0 0	1
2300	24	0	18	1	2	0	2	0	0	1	1	0	0	2	7.1	0	1.2	0	0.0	48.1	54.6	0 0	0	0	0 0	1	2	6	6 5	2	1 1	0	0	0 0	0	0	0	0 0	0	0 0	0 0	
07-19	2879	84	2268	50	349	16	36	5	13	19	37	1	1	60	2.1	11	0.4	2	0.1	45.4	51.7	0 2	15	17 1	0 14	75	360	883	881 42	5 138	39 14	5	2	1 0	0	0	0	0 0	0	0 0	0 0	1
06-22	3264	87	2579	56	386	21	44	5	16	25	44	1	1	80	2.5	13	0.4	3	0.1	45.7	52.2	0 2	16	19 1	1 14	79	389	966	1000 500	5 179	53 18	6	2	1 0	0	0	0	0 0	0	0 0	0 0	
06-00	3326	87	2628	57	391	21	48	5	16	25	46	1	1	83	2.5	14	0.4	3	0.1	45.7	52.3	0 2	17	20 1	2 14	81	393	981	1019 519	9 185	54 20	7	2	1 0	0	0	0	0 0	0	0 0	0 0	
00-00	3404	88	2670	58	412	22	49	5	18	29	51	1	1	88	2.6	15	0.4	3	0.1	45.8	52.4	0 2	17	20 1	2 15	82	401	995	1038 538	3 196	57 20	7	2	1 0	0	0	0	0 0	0	0 0	0 0	1
																																										_

		Virtual We	eek (1)																			Virtual	Week (1)																				
Time	Total						Classifi	cation]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Speed	l Bins (ı	mph)										
		1	2	3 4 5 6 7 8 9 10 11 12 60 60 68 68 75 75 85 6 5														5 - 10	- 15 -	20 - 25	5 -	35 -	40 -	45 - 50) - 55	- 60 -	65 - 1	70 - 7	5 - 80	- 85 -	90 -	95 -	100 - 1	105 - 11	0 - 115	- 120 -	125 -	130 - 135 -					
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5	10 15	20	25 3	0 30	- 35 40	45	50 5	5 60	65	70	75 8	80 85	90	95	100	105	110 11	15 120) 125	130	135 140
Mon	3361	68	2545	55	468	25	74	5	28	38	53	1	1	77	2.3	11	0.3	4	0.1	45.7	52.4	0	4 17	24	17 2	0 9	7 389	913	1035 5	8 21	55	14	4	3 1	0	0	0	0	0 () 0	0	0	0 0
Tue	3250	89	2427	62	451	24	61	3	22	31	77	3	0	68	2.1	10	0.3	3	0.1	45.4	52.2	0	0 19	21	16 1	8 6	9 434	953	975 4	31 19	5 48	12	5	2 1	0	0	0	0	0 (J 0	0	0	0 0
Wed	3079	53	2242	70	489	23	75	5	17	34	69	0	2	77	2.5	8	0.3	0	0.0	45.6	52.3	0	3 21	14	10 1	2 7	77 375	916	935 4	77 16	2 55	19	3	0 0	0	0	0	0	0 (J 0	0	0	0 0
Thu	3414	78	2574	78	460	27	58	9	22	43	62	1	2	109	3.2	14	0.4	4	0.1	46.1	53	0	1 20	17	10	7	74 398	990	998 5	8 22	74	28	3	3 1	0	0	0	0	0 (J 0	0	0	0 0
Fri	4149	91	3288	61	509	29	46	7	17	33	67	0	1	110	2.7	21	0.5	3	0.1	45.9	52.3	0	3 20	26	12 2	1 10	02 431	1214	1311 6	66 23	3 64	29	14	3 0	0	0	0	0	0 (J 0	0	0	0 0
Sat	3394	155	2876	36	275	8	6	2	8	15	12	1	0	107	3.2	23	0.7	4	0.1	45.4	52.1	0	3 15	17	12 1	1 9	93 466	1052	973 4	32 16	3 68	21	14	3 1	0	0	0	0	0 () 0	0	0	0 0
Sun	3178	79	2740	42	231	19	22	6	12	9	17	1	0	65	2.0	15	0.5	1	0.0	46.1	52.5	0	1 9	22	7 1	3 6	311	930	1037 5	33 18	9 38	19	7	1 0	0	0	0	0	0 () 0	0	0	0 0
5 Day Ave.	3451	76	2615	65	475	26	63	6	21	36	66	1	1	88	2.5	13	0.4	3	0.1	45.7	52.4	0	2 19	20	13 1	6 8	34 405	997	1051 5	50 20	4 59	20	6	2 1	0	0	0	0	0 (0	0	0	0 0
7 Day Ave.	3404	88	2670	58	412	22	49	5	18	29	51	1	1	88	2.6	15	0.4	3	0.1	45.8	52.4	0	2 17	20	12 1	5 8	32 401	995	1038 5	38 19	5 57	20	7	2 1	0	0	0	0	0 (0	0	0	0 0
	23825	613	18692	404	2883	155	342	37	126	203	357	7	6	613	2.6	102	0.4	19	0.1	45.8	52.4	0	15 12	141	84 1	04 5	73 2804	6968	7264 37	65 137	3 402	142	50	15 4	0	0	0	0	0 (0	0	0	0 0






3 approx 150m south of Inverary Parish Church	June 2021 A83 approx 150m south of Inverary Parish Church
orth South	Automatic Traffic Count North South
ual Day (5)	Virtual Day (5)

		Virtual Da	ay (5)																			Virtual D	ay (5)																					
Time	Total						Classif	fication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp											Speed Bi		- S										
		1	2	3	4	5	6	7	8	9	10	11	12	30	30	35	35	45	45		85) - 15 -		25 -		35 - 40		50 -	55 - 6	0 - 65	- 70 -	75 -	80 - 8	85 - 9	0 - 95	- 100					- 130 -	
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 3 1	10 15	5 20	25	30	30 - 33	40 45	50	55	60	55 70	75	80	85	90 9	95 10	00 105	5 110	115	120 1	125 130	135	140
0000	14	0	9	0	3	0	1	0	0	0	1	0	0	5	37.7	2	11.6	0	0.0	28.8	34.5	0 (0 0	0	2	6	4	1 0	0	0	0	0 0	0	0	0	0	0 0	. 0	0	0	0	0 0	0	0
0100	9	0	4	0	3	0	0	0	0	0	1	0	0	5	55.8	2	23.3	0	0.0	30.9	-	0	0 0	0	1	3	3	1 1	0	0	0	0 0	0	0	0	0	0 0	. 0	0	0	0	0 0	0	0
0200	8	0	4	0	2	0	0	0	0	0	1	0	0	3	38.1	1	9.5	0	0.0	28.1	-	0	0 0	0	2	3	2	1 0	0	0	0	0 0	0	0	0	0	0 0	. 0	0	0	0	0 0	0	0
0300	5	0	3	0	1	0	0	0	0	0	0	0	0	3	57.7	0	7.7	0	0.0	31.2	-	0	0 0	0	0	2	3	0 0	0	0	0	0 0	0	0	0	0	0 0	. 0	0	0	0	0 0	0	0
0400	16	0	7	0	6	1	0	0	0	1	2	0	0	8	46.3	3	15.9	1	3.7	30.3	35.6	0	0 0	0	1	7	5	2 0	0	0	0	0 0	0	0	0	0	0 0	. 0	0	0	0	0 0	0	0
0500	34	0	18	0	9	1	0	0	1	2	3	0	0	20	58.1	7	21.5	1	1.7	31.2	36.1	0	0 0	0	4	10	13	6 1	1	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
0600	82	0	53	2	14	2	3	0	1	3	5	0	0	40	49.4	13	15.9	1	0.7	30.4	35.3	0	0 0) 1	8	32	27	10 3	1	0	0	0 0	0	0	0	0	0 0	. 0	0	0	0	0 0	0	0
0700	153	0	114	2	22	2	5	0	1	2	5	0	0	47	30.5	12	7.7	1	0.5	28.3	32.7	0 (0 0) 5	27	74	35	9 2	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
0800	222	1	160	5	39	3	7	1	1	1	3	0	0	51	23.2	10	4.7	0	0.0	27.1	31.4	0 (0 1	12	53	104	41	9 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
0900	273	4	220	4	32	1	4	1	0	2	3	0	0	40	14.8	5	1.8	0	0.0	25.8	30	0 (0 1	24	84	123	36	4 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
1000	315	7	252	6	39	2	2	0	1	2	4	0	0	41	13.0	7	2.1	0	0.0	25.3	29.6	0	1 5	38	97	134	34	5 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
1100	308	7	247	7	33	2	5	1	1	2	4	0	0	34	11.2	6	2.1	0	0.1	24.8	29.2	0	0 6	38	114	115	28	5 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
1200	333	5	271	7	39	1	2	0	1	3	4	0	0	33	9.8	4	1.2	0	0.0	24.6	28.8	0	1 3	3 46	127	124	29	3 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
1300	327	4	268	6	36	2	3	0	1	2	3	0	0	29	8.9	5	1.5	0	0.0	24.1	28.5	0	2 8	48	131	108	24	4 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
1400	337	5	284	5	33	2	2	0	1	1	4	0	0	30	8.8	2	0.7	0	0.1	24.1	28.5	0	1 7	55	127	118	27	2 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
1500	330	6	277	5	30	1	4	0	1	1	5	0	0	38	11.5	6	1.9	1	0.2	24.8	29.2	0	1 6	42	117	127	32	5 1	0	1	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
1600	314	4	268	4	31	1	2	0	0	1	2	0	0	34	10.7	6	1.9	0	0.0	24.6	29	0 (0 7	44	110	119	28	5 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
1700	297	3	256	3	25	2	4	0	1	1	3	0	0	44	14.9	5	1.7	0	0.1	25.3	30	0 (0 7	32	97	118	39	5 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
1800	221	3	192	3	20	0	1	0	0	1	1	0	0	43	19.5	6	2.9	0	0.1	26.1	30.8	0	1 3	3 22	54	98	37	6 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
1900	177	2	155	2	12	1	0	0	1	1	2	0	0	34	19.4	6	3.2	0	0.1	26.1	31	0 (0 3	3 20	50	71	29	5 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
2000	107	1	95	0	6	1	1	0	0	1	2	0	0	27	25.5	8	7.1	1	0.6	27.3	32.8	0 (0 1	8	21	49	20	6 1	1	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
2100	84	0	72	1	7	1	1	0	0	0	1	0	0	25	30.3	4	4.3	0	0.0	27.3	32.2	0 (0 1	6	17	34	22	3 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
2200	44	0	38	0	3	0	1	0	0	0	1	0	0	12	26.1	2	3.6	0	0.5	27	32	0 (0 0) 2	14	16	10	1 1	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
2300	29	0	24	0	2	0	1	0	0	0	1	0	0	10	35.4	2	5.4	0	0.0	28.1	31.9	0 (0 0	0	5	13	9	2 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
07-19	3430	49	2808	56	378	21	41	6	10	20	40	1	1	464	13.5	75	2.2	3	0.1	25.2	29.7	0	6 55	5 405	1139	1362	389	63 10	2	1	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
06-22	3880	52	3183	61	417	26	46	6	12	25	49	1	1	591	15.2	105	2.7	4	0.1	25.4	30	0	7 59	9 439	1236	1548	487	85 15	3	1	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
06-00	3954	53	3245	62	422	26	49	6	12	26	51	1	1	613	15.5	108	2.7	4	0.1	25.5	30.1	0	7 60	0 441	1255	1578	505	88 16	3	1	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0
00-00	4041	53	3290	63	446	28	50	6	14	30	58	1	1	657	16.3	123	3.0	6	0.1	25.6	30.3	0	7 60	0 442	1265	1609	534	98 19	4	1	0	0 0	0	0	0	0	0 0	0	0	0	0	0 0	0	0

		Virtual We	eek (1)																			Virtual V	Veek (1)																					
Time	Total						Classif	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Sp	eed Bins	s (mph)											
		1	2	3 4 5 6 7 8 9 10 11 12 30 30 35 35 45 45 85														5 5	- 10 -	15 -	20 -	25 -	35 -	40 -	45 -	50 -	55 - 60	- 65 -	70 -	75 -	80 -	35 - 90	- 95	- 100	- 105 -	110 - /	115 - 1	120 - 125	- 130 - 1	135 -				
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 1	0 15	20	25	30 30 -	35 40	45	50	55	60 65	70	75	80	85	90 9	100 د	0 105	110	115	120	125 130	135	140
Mon	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	-	-	0	0 0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 (. 0	0	0	0	0	0 0	0	0
Tue	4066	102	3181	65	492	28	61	5	17	34	79	0	2	563	13.9	100	2.5	4	0.1	25.5	29.8	0	6 51	421	1301	1724 46	3 81	15	3	0	0 1	0	0	0	0	0 (0	0	0	0	0	0 0	0	0
Wed	3775	62	2900	73	507	26	82	5	13	31	73	1	2	682	18.1	119	3.2	10	0.3	26.1	30.5	1	4 53	355	1029	1651 56	3 91	18	5	5	0 0	0	0	0	0	0 (. 0	0	0	0	0	0 0	0	0
Thu	4094	44	3238	79	492	35	59	12	22	43	69	0	1	698	17.1	130	3.2	5	0.1	25.8	30.4	1	7 56	411	1248	1673 56	8 104	21	4	1	0 0	0	0	0	0	0 (. 0	0	0	0	0	0 0	0	0
Fri	4654	38	3884	65	478	35	46	6	12	29	58	3	0	803	17.3	160	3.4	5	0.1	25.6	30.5	0	5 64	529	1507	1746 64	3 129	26	4	1	0 0	0	0	0	0	0 (. 0	0	0	0	0	0 0	0	0
Sat	3614	17	3248	33	263	15	4	2	5	14	12	1	0	540	14.9	105	2.9	4	0.1	25	30	0 1	12 77	494	1242	1249 43	5 86	15	4	0	0 0	0	0	0	0	0 (. 0	0	0	0	0	0 0	0	0
Sun	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	-	-	0	0 0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0 (0	0	0	0	0	0 0	0	0
5 Day Ave.	4147	62	3301	71	492	31	62	7	16	34	70	1	1	687	16.6	127	3.1	6	0.1	25.8	30.3	1	6 56	429	1271	1699 55	9 101	20	4	2	0 0	0	0	0	0	0 (0	0	0	0	0	0 0	0	0
7 Day Ave.	4041	53	3290	63	446	28	50	6	14	30	58	1	1	657	16.3	123	3.0	6	0.1	25.6	30.3	0	7 60	442	1265	1609 53	4 98	19	4	1	0 0	0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
	20203	263	16451	315	2232	139	252	30	69	151	291	5	5	3286	16.3	614	3.0	28	0.1	25.6	30.3	2 3	301	2210	6327	8043 267	72 491	95	20	7	0 1	0	0	0	0	0 (0	0	0	0	0	0 0	0	0





| | | | | | | |

 |

 |
 | | |

 | |

 | | | | | | | Virtual Da | ay (1)
 | | | | | | | | |
 | | | | | | | | |
 | | | | | |
 | |
|-------|--|--|---|---|--|--
--
--
--
--

--
--
--
--
---|--|---|---
--
--
--
---|--
--
--
--
--|--|--|--|---|---|--|----------------------------
--|--|--|--|---
---|---------------------------|----------------------------|----------------------|--|---|---
---	---------	---	---	--
Iotal				

 |

 |
 | | |

 |]PSL |]PSL%

 |]SL1 |]SL1% |]SL2 |]SL2% | Mean | Vpp | | |
 | | | | |
 | | | | Speed | Bins (m | ph) | | |
 | | | | | |
 | |
| | 1 | 2 | 3 | 4 | 5 | 6 | 7

 | 8

 | 9
 | 10 | 11 | 12

 | 40 | 40

 | 46 | 46 | 55 | 55 | | 85 | |
 | | | | 20 25 | 35 - 40 -
 | | | 55 - | 60 - 6 | 5 - 70 | - 75 - | 80 - | 85 - | 90 - 9
 | /5 - 100 | J - 105 - | | | |
 | |
| | MCL | SV | SVT | TB2 | TB3 | T4 | ART3

 | ART4

 | ART5
 | ART6 | BD | DRT

 | |

 | ACPO | ACPO | DfT | DfT | | | 0 - 5 | 0 1
 | 5 20 | 25 | 30 | 30 - 35 | 40 45
 | 50 | 55 | 60 | 65 | 70 75 | 80 | 85 | 90 | 95 1
 | 00 10 | 5 110 | 115 | 120 | 125 13 | 0 135
 | 140 |
| 5 | 0 | 4 | 0 | 1 | 0 | 0 | 0

 | 0

 | 0
 | 0 | 0 | 0

 | 2 | 29.0

 | 1 | 15.8 | 1 | 13.2 | 40.8 | - | 0 0 | 0
 | 0 0 | 0 | 0 | 1 | 2 1
 | 0 | 0 | 0 | 0 | 1 0 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 4 | 0 | 2 | 0 | 1 | 0 | 1 | 0

 | 0

 | 0
 | 0 | 0 | 0

 | 2 | 42.9

 | 1 | 25.0 | 0 | 10.7 | 41.5 | - | 0 0 | 0
 | 0 0 | 0 | 0 | 1 | 2 1
 | 0 | 0 | 0 | 0 | 0 0 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 3 | 0 | 2 | 0 | 1 | 0 | 0 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 1 | 30.4

 | 1 | 21.7 | 0 | 8.7 | 41 | - | 0 0 |) 0
 | 0 0 | 0 | 0 | 1 | 2 0
 | 0 | 0 | 0 | 0 | 0 0 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 2 | 0 | 1 | 0 | 1 | 0 | 0 | 0

 | 0

 | 0
 | 0 | 0 | 0

 | 1 | 43.8

 | 1 | 43.8 | 1 | 25.0 | 44.7 | - | 0 0 |) 0
 | 0 0 | 0 | 0 | 0 | 1 0
 | 0 | 0 | 0 | 0 | 1 0 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 5 | 0 | 3 | 0 | 1 | 0 | 0 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 3 | 68.6

 | 2 | 40.0 | 1 | 14.3 | 45.5 | - | 0 0 | 0
 | 0 0 | 0 | 0 | 1 | 1 1
 | 1 | 0 | 0 | 0 | 0 0 | 0 | 0 | 0 | 0
 | 0 0 |) 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 12 | 0 | 7 | 0 | 2 | 0 | 0 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 6 | 53.7

 | 4 | 32.9 | 3 | 23.2 | 50.3 | 81.5 | 0 0 | 0
 | 0 0 | 0 | 0 | 1 | 4 2
 | 1 | 0 | 0 | 0 | 0 0 | 0 | 1 | 0 | 1
 | 0 0 |) 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 30 | 0 | 21 | 1 | 5 | 0 | 1 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 18 | 59.4

 | 8 | 28.0 | 6 | 18.8 | 47.3 | 77.4 | 0 0 | 0
 | 0 0 | 0 | 1 | 2 | 9 8
 | 3 | 1 | 0 | 0 | 0 0 | 5 | 0 | 0 | 0
 | 0 0 |) 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 64 | 1 | 48 | 1 | 9 | 0 | 2 | 0

 | 1

 | 2
 | 1 | 0 | 0

 | 26 | 41.0

 | 13 | 20.5 | 11 | 16.9 | 43.7 | 58.7 | 0 0 | 0
 | 0 0 | 0 | 3 | 13 | 22 11
 | 4 | 0 | 1 | 0 | 0 0 | 9 | 0 | 0 | 0
 | 0 0 |) 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 72 | 1 | 50 | 2 | 15 | 1 | 1 | 0

 | 0

 | 1
 | 0 | 0 | 0

 | 24 | 34.0

 | 13 | 17.9 | 9 | 12.5 | 39.9 | 49.3 | 0 0 | 0
 |) 1 | 1 | 4 | 17 | 26 11
 | 3 | 2 | 5 | 1 | 3 0 | 0 | 0 | 0 | 0
 | 0 0 |) 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 98 | 6 | 75 | 1 | 14 | 0 | 1 | 0

 | 0

 | 0
 | 0 | 0 | 0

 | 26 | 26.4

 | 13 | 13.4 | 10 | 9.8 | 38.7 | 44.2 | 0 0 |) 0
 | 0 0 | 2 | 10 | 27 | 32 12
 | 3 | 2 | 0 | 1 | 7 1 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 154 | 13 | 116 | 2 | 19 | 2 | 2 | 0

 | 0

 | 0
 | 0 | 0 | 0

 | 38 | 24.7

 | 19 | 12.5 | 16 | 10.3 | 37.8 | 43.3 | 0 0 |) 0
 |) 1 | 4 | 19 | 41 | 52 18
 | 3 | 1 | 8 | 4 | 3 0 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 153 | 10 | 114 | 3 | 21 | 1 | 1 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 41 | 26.6

 | 19 | 12.7 | 13 | 8.2 | 37.4 | 44.1 | 0 0 |) 0
 |) 1 | 4 | 19 | 44 | 44 19
 | 7 | 2 | 5 | 5 | 2 0 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 159 | 15 | 113 | 3 | 24 | 1 | 2 | 0

 | 0

 | 1
 | 1 | 0 | 0

 | 42 | 26.8

 | 20 | 12.7 | 16 | 10.0 | 38 | 44.3 | 0 0 | 0
 | 0 0 | 3 | 16 | 45 | 51 20
 | 5 | 1 | 11 | 3 | 0 1 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 151 | 13 | 109 | 3 | 20 | 2 | 1 | 1

 | 1

 | 0
 | 1 | 0 | 0

 | 37 | 24.7

 | 17 | 11.5 | 13 | 8.7 | 37.6 | 43.1 | 0 0 | 0
 |) 1 | 6 | 15 | 43 | 48 19
 | 4 | 1 | 6 | 4 | 2 1 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 149 | 14 | 106 | 2 | 21 | 2 | 1 | 0

 | 0

 | 1
 | 1 | 0 | 0

 | 49 | 32.7

 | 26 | 17.3 | 15 | 10.1 | 39.1 | 48.8 | 0 0 | 0
 | 0 0 | 3 | 15 | 41 | 42 20
 | 7 | 6 | 4 | 7 | 3 1 | 0 | 0 | 0 | 0
 | 0 0 |) 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 158 | 11 | 118 | 2 | 20 | 1 | 2 | 1

 | 1

 | 0
 | 3 | 0 | 0

 | 48 | 30.5

 | 28 | 17.7 | 19 | 11.9 | 39.5 | 48.1 | 0 0 | 0
 | 0 0 | 5 | 15 | 41 | 48 17
 | 9 | 4 | 3 | 3 | 9 3 | 0 | 0 | 0 | 0
 | 0 0 |) 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 155 | 11 | 121 | 1 | 18 | 1 | 1 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 48 | 31.0

 | 23 | 14.8 | 17 | 11.3 | 39.4 | 45.8 | 0 0 |) 0
 |) 1 | 2 | 13 | 39 | 52 22
 | 7 | 1 | 5 | 6 | 6 1 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 131 | 6 | 104 | 2 | 16 | 1 | 1 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 47 | 35.8

 | 20 | 15.2 | 12 | 9.5 | 40.4 | 46.2 | 0 0 |) 0
 | 0 0 | 2 | 7 | 29 | 45 25
 | 7 | 2 | 1 | 4 | 1 3 | 3 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 95 | 3 | 78 | 1 | 11 | 0 | 1 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 36 | 38.1

 | 14 | 14.7 | 10 | 10.2 | 41.4 | 45.9 | 0 0 |) 0
 | 0 0 | 1 | 4 | 18 | 35 21
 | 4 | 1 | 0 | 0 | 0 5 | 1 | 2 | 1 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 70 | 2 | 58 | 1 | 7 | 1 | 1 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 27 | 38.5

 | 13 | 18.9 | 8 | 11.3 | 42.8 | 48.4 | 0 0 |) 0
 | 0 0 | 1 | 3 | 12 | 27 13
 | 4 | 2 | 0 | 0 | 0 2 | 1 | 2 | 2 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 47 | 3 | 36 | 0 | 6 | 1 | 0 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 24 | 51.7

 | 14 | 29.7 | 10 | 22.3 | 45.6 | 65.8 | 0 0 |) 0
 | 0 0 | 0 | 2 | 7 | 13 10
 | 2 | 2 | 1 | 1 | 5 3 | 0 | 1 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 33 | 1 | 26 | 0 | 4 | 0 | 0 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 14 | 42.5

 | 6 | 18.0 | 4 | 11.8 | 41.4 | 48.6 | 0 0 |) 0
 | 0 0 | 0 | 2 | 5 | 12 7
 | 3 | 1 | 0 | 3 | 0 0 | 0 | 0 | 0 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 20 | 0 | 16 | 0 | 2 | 0 | 0 | 0

 | 0

 | 1
 | 1 | 0 | 0

 | 9 | 43.8

 | 5 | 24.8 | 4 | 19.0 | 43.3 | 65.3 | 0 0 | 0
 | 0 0 | 0 | 1 | 4 | 6 4
 | 1 | 1 | 0 | 1 | 2 1 | 0 | 0 | 0 | 0
 | 0 C | 0 (| 0 | 0 | 0 0 | 0
 | 0 |
| 13 | 0 | 10 | 0 | 1 | 0 | 0 | 0

 | 0

 | 0
 | 1 | 0 | 0

 | 5 | 41.1

 | 3 | 24.4 | 2 | 13.3 | 41.5 | 51.9 | 0 0 | 0
 | 0 0 | 0 | 1 | 3 | 4 2
 | 1 | 1 | 0 | 2 | 0 0 | 0 | 0 | 0 | 0
 | 0 0 | 0 (| 0 | 0 | 0 0 | 0
 | 0 |
| 1539 | 102 | 1153 | 21 | 209 | 12 | 15 | 2

 | 5

 | 6
 | 13 | 1 | 0

 | 463 | 30.1

 | 226 | 14.7 | 160 | 10.4 | 39.1 | 45.8 | 0 1 | 1 0
 | 7 | 33 | 140 | 398 | 497 217
 | 61 | 25 | 50 | 39 | 35 17 | 7 13 | 3 | 2 | 0
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 1718 | 108 | 1294 | 24 | 231 | 13 | 16 | 2

 | 5

 | 7
 | 17 | 1 | 0

 | 546 | 31.8

 | 267 | 15.6 | 188 | 10.9 | 39.6 | 46.5 | 0 1 | 1 1
 | 1 7 | 35 | 148 | 424 | 558 255
 | 73 | 30 | 51 | 43 | 40 22 | 2 19 | 7 | 4 | 1
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 1750 | 108 | 1320 | 24 | 234 | 14 | 16 | 2

 | 5

 | 8
 | 18 | 1 | 0

 | 559 | 32.0

 | 275 | 15.7 | 193 | 11.1 | 39.6 | 46.8 | 0 1 | 1 1
 | 1 7 | 35 | 149 | 430 | 568 260
 | 75 | 31 | 51 | 45 | 42 23 | 3 20 | 7 | 4 | 1
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| 1782 | 108 | 1339 | 24 | 240 | 14 | 17 | 3


 | 6

 | 9
 | 21 | 1 | 0

 | 574 | 32.2

 | 285 | 16.0 | 199 | 11.2 | 39.8 | 47 | 0 1 | 1 1
 | 1 7 | 35 | 151 | 435 |
 | | 32 | 52 | 46 | 44 23 | 3 20 | 7 | 4 | 2
 | 0 0 | 0 | 0 | 0 | 0 0 | 0
 | 0 |
| | 30
64
72
98
154
153
159
151
149
158
155
131
95
70
47
33
20
13
1539
1718 | 5 0
4 0
3 0
2 0
5 0
12 0
30 0
64 1
72 1
98 6
154 13
153 10
159 15
151 13
149 14
158 11
155 11
131 6
95 3
70 2
47 3
33 1
20 0
13 0
1539 102
1718 108
1750 108 | 5 0 4 4 0 2 3 0 2 2 0 1 5 0 3 12 0 7 30 0 21 64 1 48 72 1 50 98 6 75 154 13 116 153 10 114 159 15 113 151 13 109 149 14 106 158 11 118 155 11 121 131 6 104 95 3 78 70 2 58 47 3 36 33 1 26 20 0 16 13 0 10 1539 102 1153 1718 108 1294 | 5 0 4 0 4 0 2 0 3 0 2 0 2 0 1 0 5 0 3 0 12 0 7 0 30 0 21 1 64 1 48 1 72 1 50 2 98 6 75 1 154 13 116 2 153 10 114 3 159 15 113 3 151 13 109 3 149 14 106 2 158 11 118 2 155 11 121 1 131 6 104 2 95 3 78 1 70 2 58 1 47 3 36 0 < | 5 0 4 0 1 4 0 2 0 1 3 0 2 0 1 2 0 1 0 1 5 0 3 0 1 12 0 7 0 2 30 0 21 1 5 64 1 48 1 9 72 1 50 2 15 98 6 75 1 14 154 13 116 2 19 153 10 114 3 21 159 15 113 3 24 151 13 109 3 20 149 14 106 2 21 158 11 118 2 20 155 11 121 1 18 131 6 | 5 0 4 0 1 0 4 0 2 0 1 0 3 0 2 0 1 0 2 0 1 0 1 0 5 0 3 0 1 0 12 0 7 0 2 0 30 0 21 1 5 0 64 1 48 1 9 0 72 1 50 2 15 1 98 6 75 1 14 0 154 13 116 2 19 2 153 10 114 3 21 1 159 15 113 3 24 1 159 15 113 3 24 1 159 15 113 3 24 1 | 5 0 4 0 1 0 0 4 0 2 0 1 0 1 3 0 2 0 1 0 0 2 0 1 0 0 0 5 0 3 0 1 0 0 12 0 7 0 2 0 0 30 0 21 1 5 0 1 64 1 48 1 9 0 2 72 1 50 2 15 1 1 98 6 75 1 14 0 1 1 154 13 116 2 19 2 2 1 153 10 114 3 21 1 1 1 1 1 1 1 1 1 1 1 1 <td>5 0 4 0 1 0 0 0 4 0 2 0 1 0 1 0 3 0 2 0 1 0 0 0 2 0 1 0 0 0 0 5 0 3 0 1 0 0 0 12 0 7 0 2 0 0 0 30 0 21 1 5 0 1 0 64 1 48 1 9 0 2 0 72 1 50 2 15 1 1 0 98 6 75 1 14 0 1 0 154 13 116 2 19 2 2 0 153 10 114 3 21 1 1 0<td>5 0 4 0 1 0 0 0 0 4 0 2 0 1 0 1 0 0 3 0 2 0 1 0 0 0 0 2 0 1 0 1 0 0 0 0 5 0 3 0 1 0 0 0 0 12 0 7 0 2 0 0 0 0 30 0 21 1 5 0 1 0 0 64 1 48 1 9 0 2 0 1 72 1 50 2 15 1 1 0 0 98 6 75 1 14 0 1 0 0 153 10 114 3 21 1</td><td>5 0 4 0 1 0 0 0 0 0 4 0 2 0 1 0 1 0 0 0 3 0 2 0 1 0 0 0 0 0 2 0 1 0</td><td>MCL SV SVT IB2 IB3 T4 ART3 ART4 ART5 ART6 5 0 4 0 1 0 0 0 0 0 0 0 0 4 0 2 0 1 0 1 0 0 0 0 0 0 3 0 2 0 1 0 1 1 0 0 0 1 1 0 0 0 1 1 0 0 0 1 1 0 0 0 0 1 1 1 0</td><td>MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD 5 0 4 0 1 0<td> MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT </td><td>MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT 5 0 4 0 1 0 0 0 0 0 0 0 0 2 4 0 2 0 1 0 1 0 0 0 0 0 0 2 3 0 2 0 1 0<!--</td--><td>MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT Company 5 0 4 0 1 0 0 0 0 0 0 0 2 290 4 0 2 0 1 0 1 0</td><td> MCL SV SVI TB2 TB3 T4 ARI3 ARI4 ARI5 ARI6 BD DRI </td><td> MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT </td><td> MCL SV SVI TB2 TB3 T4 ARI3 ARI4 ARI5 ARI6 BD DRI CF ACPO ACPO DTI S</td><td> MCL SV SVI 1B2 1B3 T4 AR13 AR14 AR15 AR16 BD DR1 CV CV ACPO DR1 DR1 </td><td>MCL SV SVI 182 183 14 ARIS ARIS ARIS BD DRI CP ACPO DIT DIT OIT ARIS ARIS ARIS BD DRI CP ACPO DIT DIT CHOS 5 0 4 0 1 0 0 0 0 0 2 29.0 1 158.0 1 13.2 40.8 4 0 1 15.0 1 0 0 1 4.7 4.7 4 3.2 0 1 4.7 4 4.1 4.8 1 4.2 2.0 4 1 3.0 2.0 1</td><td> MCL MCL SV SVI IB2</td><td> MCL SV SVI 182 183 14 AR13 AR14 AR15 AR16 BD DR1 SV CV ACPO DCT DCT DCT SV SVI T82 T83 T4 AR15 AR16 BD DR1 SV SVI T82 T83 T4 AR15 AR16 BD DR1 SV SVI T82 T83 T</td><td> MCL SV SVI 182 183 14 ARI3 ARI4 ARI5 ARI6 8D ORI C C C C C ORI ORI C C C C C C C C C </td><td> MCL SV SVI 182 183 14 AR13 AR14 AR15 AR16 R16 R16 R16 R16 R16 R16 R16 R16 R17 R17 R18 R17 R18 R1</td><td> MC MC SV SV </td><td> Mole Mole </td><td> Math Math </td><td> MCL SV SV IB2 IB3</td><td> MCL SV SVT 182 183</td><td> MC SV SV N20</td><td> MCL SV SV R8 R8 R8 R4 AR18 AR18 </td><td> Mart Mart </td><td> Mart Mart </td><td> Mart Mart </td><td> Martine</td><td> Mart Mart </td><td> Mart Mart </td><td> Martia M</td><td>. Mart No. 1. Mart</td><td></td><td> Mart Mart </td><td> Mart Mart </td><td> Mart Mart </td></td></td></td> | 5 0 4 0 1 0 0 0 4 0 2 0 1 0 1 0 3 0 2 0 1 0 0 0 2 0 1 0 0 0 0 5 0 3 0 1 0 0 0 12 0 7 0 2 0 0 0 30 0 21 1 5 0 1 0 64 1 48 1 9 0 2 0 72 1 50 2 15 1 1 0 98 6 75 1 14 0 1 0 154 13 116 2 19 2 2 0 153 10 114 3 21 1 1 0 <td>5 0 4 0 1 0 0 0 0 4 0 2 0 1 0 1 0 0 3 0 2 0 1 0 0 0 0 2 0 1 0 1 0 0 0 0 5 0 3 0 1 0 0 0 0 12 0 7 0 2 0 0 0 0 30 0 21 1 5 0 1 0 0 64 1 48 1 9 0 2 0 1 72 1 50 2 15 1 1 0 0 98 6 75 1 14 0 1 0 0 153 10 114 3 21 1</td> <td>5 0 4 0 1 0 0 0 0 0 4 0 2 0 1 0 1 0 0 0 3 0 2 0 1 0 0 0 0 0 2 0 1 0</td> <td>MCL SV SVT IB2 IB3 T4 ART3 ART4 ART5 ART6 5 0 4 0 1 0 0 0 0 0 0 0 0 4 0 2 0 1 0 1 0 0 0 0 0 0 3 0 2 0 1 0 1 1 0 0 0 1 1 0 0 0 1 1 0 0 0 1 1 0 0 0 0 1 1 1 0</td> <td>MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD 5 0 4 0 1 0<td> MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT </td><td>MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT 5 0 4 0 1 0 0 0 0 0 0 0 0 2 4 0 2 0 1 0 1 0 0 0 0 0 0 2 3 0 2 0 1 0<!--</td--><td>MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT Company 5 0 4 0 1 0 0 0 0 0 0 0 2 290 4 0 2 0 1 0 1 0</td><td> MCL SV SVI TB2 TB3 T4 ARI3 ARI4 ARI5 ARI6 BD DRI </td><td> MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT </td><td> MCL SV SVI TB2 TB3 T4 ARI3 ARI4 ARI5 ARI6 BD DRI CF ACPO ACPO DTI S</td><td> MCL SV SVI 1B2 1B3 T4 AR13 AR14 AR15 AR16 BD DR1 CV CV ACPO DR1 DR1 </td><td>MCL SV SVI 182 183 14 ARIS ARIS ARIS BD DRI CP ACPO DIT DIT OIT ARIS ARIS ARIS BD DRI CP ACPO DIT DIT CHOS 5 0 4 0 1 0 0 0 0 0 2 29.0 1 158.0 1 13.2 40.8 4 0 1 15.0 1 0 0 1 4.7 4.7 4 3.2 0 1 4.7 4 4.1 4.8 1 4.2 2.0 4 1 3.0 2.0 1</td><td> MCL MCL SV SVI IB2</td><td> MCL SV SVI 182 183 14 AR13 AR14 AR15 AR16 BD DR1 SV CV ACPO DCT DCT DCT SV SVI T82 T83 T4 AR15 AR16 BD DR1 SV SVI T82 T83 T4 AR15 AR16 BD DR1 SV SVI T82 T83 T</td><td> MCL SV SVI 182 183 14 ARI3 ARI4 ARI5 ARI6 8D ORI C C C C C ORI ORI C C C C C C C C C </td><td> MCL SV SVI 182 183 14 AR13 AR14 AR15 AR16 R16 R16 R16 R16 R16 R16 R16 R16 R17 R17 R18 R17 R18 R1</td><td> MC MC SV SV </td><td> Mole Mole </td><td> Math Math </td><td> MCL SV SV IB2 IB3</td><td> MCL SV SVT 182 183</td><td> MC SV SV N20</td><td> MCL SV SV R8 R8 R8 R4 AR18 AR18 </td><td> Mart Mart </td><td> Mart Mart </td><td> Mart Mart </td><td> Martine</td><td> Mart Mart </td><td> Mart Mart </td><td> Martia M</td><td>. Mart No. 1. Mart</td><td></td><td> Mart Mart </td><td> Mart Mart </td><td> Mart Mart </td></td></td> | 5 0 4 0 1 0 0 0 0 4 0 2 0 1 0 1 0 0 3 0 2 0 1 0 0 0 0 2 0 1 0 1 0 0 0 0 5 0 3 0 1 0 0 0 0 12 0 7 0 2 0 0 0 0 30 0 21 1 5 0 1 0 0 64 1 48 1 9 0 2 0 1 72 1 50 2 15 1 1 0 0 98 6 75 1 14 0 1 0 0 153 10 114 3 21 1 | 5 0 4 0 1 0 0 0 0 0 4 0 2 0 1 0 1 0 0 0 3 0 2 0 1 0 0 0 0 0 2 0 1 0 | MCL SV SVT IB2 IB3 T4 ART3 ART4 ART5 ART6 5 0 4 0 1 0 0 0 0 0 0 0 0 4 0 2 0 1 0 1 0 0 0 0 0 0 3 0 2 0 1 0 1 1 0 0 0 1 1 0 0 0 1 1 0 0 0 1 1 0 0 0 0 1 1 1 0 | MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD 5 0 4 0 1 0 <td> MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT </td> <td>MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT 5 0 4 0 1 0 0 0 0 0 0 0 0 2 4 0 2 0 1 0 1 0 0 0 0 0 0 2 3 0 2 0 1 0<!--</td--><td>MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT Company 5 0 4 0 1 0 0 0 0 0 0 0 2 290 4 0 2 0 1 0 1 0</td><td> MCL SV SVI TB2 TB3 T4 ARI3 ARI4 ARI5 ARI6 BD DRI </td><td> MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT </td><td> MCL SV SVI TB2 TB3 T4 ARI3 ARI4 ARI5 ARI6 BD DRI CF ACPO ACPO DTI S</td><td> MCL SV SVI 1B2 1B3 T4 AR13 AR14 AR15 AR16 BD DR1 CV CV ACPO DR1 DR1 </td><td>MCL SV SVI 182 183 14 ARIS ARIS ARIS BD DRI CP ACPO DIT DIT OIT ARIS ARIS ARIS BD DRI CP ACPO DIT DIT CHOS 5 0 4 0 1 0 0 0 0 0 2 29.0 1 158.0 1 13.2 40.8 4 0 1 15.0 1 0 0 1 4.7 4.7 4 3.2 0 1 4.7 4 4.1 4.8 1 4.2 2.0 4 1 3.0 2.0 1</td><td> MCL MCL SV SVI IB2</td><td> MCL SV SVI 182 183 14 AR13 AR14 AR15 AR16 BD DR1 SV CV ACPO DCT DCT DCT SV SVI T82 T83 T4 AR15 AR16 BD DR1 SV SVI T82 T83 T4 AR15 AR16 BD DR1 SV SVI T82 T83 T</td><td> MCL SV SVI 182 183 14 ARI3 ARI4 ARI5 ARI6 8D ORI C C C C C ORI ORI C C C C C C C C C </td><td> MCL SV SVI 182 183 14 AR13 AR14 AR15 AR16 R16 R16 R16 R16 R16 R16 R16 R16 R17 R17 R18 R17 R18 R1</td><td> MC MC SV SV </td><td> Mole Mole </td><td> Math Math </td><td> MCL SV SV IB2 IB3</td><td> MCL SV SVT 182 183</td><td> MC SV SV N20</td><td> MCL SV SV R8 R8 R8 R4 AR18 AR18 </td><td> Mart Mart </td><td> Mart Mart </td><td> Mart Mart </td><td> Martine</td><td> Mart Mart </td><td> Mart Mart </td><td> Martia M</td><td>. Mart No. 1. Mart</td><td></td><td> Mart Mart </td><td> Mart Mart </td><td> Mart Mart </td></td> | MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT | MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT 5 0 4 0 1 0 0 0 0 0 0 0 0 2 4 0 2 0 1 0 1 0 0 0 0 0 0 2 3 0 2 0 1 0 </td <td>MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT Company 5 0 4 0 1 0 0 0 0 0 0 0 2 290 4 0 2 0 1 0 1 0</td> <td> MCL SV SVI TB2 TB3 T4 ARI3 ARI4 ARI5 ARI6 BD DRI </td> <td> MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT </td> <td> MCL SV SVI TB2 TB3 T4 ARI3 ARI4 ARI5 ARI6 BD DRI CF ACPO ACPO DTI S</td> <td> MCL SV SVI 1B2 1B3 T4 AR13 AR14 AR15 AR16 BD DR1 CV CV ACPO DR1 DR1 </td> <td>MCL SV SVI 182 183 14 ARIS ARIS ARIS BD DRI CP ACPO DIT DIT OIT ARIS ARIS ARIS BD DRI CP ACPO DIT DIT CHOS 5 0 4 0 1 0 0 0 0 0 2 29.0 1 158.0 1 13.2 40.8 4 0 1 15.0 1 0 0 1 4.7 4.7 4 3.2 0 1 4.7 4 4.1 4.8 1 4.2 2.0 4 1 3.0 2.0 1</td> <td> MCL MCL SV SVI IB2</td> <td> MCL SV SVI 182 183 14 AR13 AR14 AR15 AR16 BD DR1 SV CV ACPO DCT DCT DCT SV SVI T82 T83 T4 AR15 AR16 BD DR1 SV SVI T82 T83 T4 AR15 AR16 BD DR1 SV SVI T82 T83 T</td> <td> MCL SV SVI 182 183 14 ARI3 ARI4 ARI5 ARI6 8D ORI C C C C C ORI ORI C C C C C C C C C </td> <td> MCL SV SVI 182 183 14 AR13 AR14 AR15 AR16 R16 R16 R16 R16 R16 R16 R16 R16 R17 R17 R18 R17 R18 R1</td> <td> MC MC SV SV </td> <td> Mole Mole </td> <td> Math Math </td> <td> MCL SV SV IB2 IB3</td> <td> MCL SV SVT 182 183</td> <td> MC SV SV N20</td> <td> MCL SV SV R8 R8 R8 R4 AR18 AR18 </td> <td> Mart Mart </td> <td> Mart Mart </td> <td> Mart Mart </td> <td> Martine</td> <td> Mart Mart </td> <td> Mart Mart </td> <td> Martia M</td> <td>. Mart No. 1. Mart</td> <td></td> <td> Mart Mart </td> <td> Mart Mart </td> <td> Mart Mart </td> | MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT Company 5 0 4 0 1 0 0 0 0 0 0 0 2 290 4 0 2 0 1 0 1 0 | MCL SV SVI TB2 TB3 T4 ARI3 ARI4 ARI5 ARI6 BD DRI | MCL SV SVI TB2 TB3 T4 ART3 ART4 ART5 ART6 BD DRT | MCL SV SVI TB2 TB3 T4 ARI3 ARI4 ARI5 ARI6 BD DRI CF ACPO ACPO DTI S | MCL SV SVI 1B2 1B3 T4 AR13 AR14 AR15 AR16 BD DR1 CV CV ACPO DR1 DR1 | MCL SV SVI 182 183 14 ARIS ARIS ARIS BD DRI CP ACPO DIT DIT OIT ARIS ARIS ARIS BD DRI CP ACPO DIT DIT CHOS 5 0 4 0 1 0 0 0 0 0 2 29.0 1 158.0 1 13.2 40.8 4 0 1 15.0 1 0 0 1 4.7 4.7 4 3.2 0 1 4.7 4 4.1 4.8 1 4.2 2.0 4 1 3.0 2.0 1 | MCL MCL SV SVI IB2 | MCL SV SVI 182 183 14 AR13 AR14 AR15 AR16 BD DR1 SV CV ACPO DCT DCT DCT SV SVI T82 T83 T4 AR15 AR16 BD DR1 SV SVI T82 T83 T4 AR15 AR16 BD DR1 SV SVI T82 T83 T | MCL SV SVI 182 183 14 ARI3 ARI4 ARI5 ARI6 8D ORI C C C C C ORI ORI C C C C C C C C C | MCL SV SVI 182 183 14 AR13 AR14 AR15 AR16 R16 R16 R16 R16 R16 R16 R16 R16 R17 R17 R18 R17 R18 R1 | MC MC SV SV | Mole Mole | Math Math | MCL SV SV IB2 IB3 | MCL SV SVT 182 183 | MC SV SV N20 | MCL SV SV R8 R8 R8 R4 AR18 AR18 | Mart Mart | Mart Mart | Mart Mart | Martine | Mart Mart | Mart Mart | Martia M | . Mart No. 1. Mart | | Mart Mart | Mart Mart | Mart Mart |


		Virtual We	eek (1)																			Virtual W	eek (1)																					
Time	Total						Classifi	cation]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Sp	eed Bins	(mph)											1
		1	2	3	3 4 5 6 7 8 9 10 11 12 40 40 46 46 55 55 85 85 0.5 5 - 10 - 15 - 20 - 25 - 30.35 35 - 40 - 45 - 50 - 55															5 - 60 -	65 -	70 -	75 -	80 - 8	35 - 90) - 95	- 100	- 105 -	110 -	115 - 1	20 - 125	- 130 - 135 -	4											
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 10	15	20	25	30 30 -	³⁵ 40	45	50	55	65 65	70	75	80	85	90 9!	5 10	0 105	110	115	120	125 130	135 140	1
Mon	2173	14	1680	11	399	28	4	6	9	8	9	3	2	1817	83.6	1487	68.4	1283	59.0	56.5	71	0 1	0	1	11	35 90	218	290	138	106	32 297	287	133	134	51	29 1	3 2	3	2	0	0	0 0	0 0	Ī
Tue	1602	82	1169	31	231	14	25	0	7	11	32	0	0	250	15.6	40	2.5	3	0.2	35.1	40.3	0 0	4	13	48	177 514	4 596	191	47	9	2 0	0	1	0	0	0 (0	0	0	0	0	0 0	0 0	1
Wed	1827	102	1331	34	253	14	24	3	7	14	44	1	0	346	18.9	61	3.3	7	0.4	35.6	40.9	0 0	0	10	49	198 53	0 694	273	48	18	3 3	0	1	0	0	0 (0	0	0	0	0	0 0	0 0	1
Thu	1800	110	1312	31	255	13	37	1	5	13	23	0	0	379	21.1	63	3.5	4	0.2	36	41.1	0 1	0	4	34	184 52	7 671	291	64	20	2 0	1	1	0	0	0 (0	0	0	0	0	0 0	0 0	1
Fri	1878	117	1413	21	254	17	17	4	7	8	20	0	0	446	23.8	98	5.2	7	0.4	36.5	41.9	0 2	0	9	36	163 498	8 724	318	92	29	4 1	2	0	0	0	0 (0	0	0	0	0	0 0	0 0	1
Sat	1742	228	1321	13	145	9	9	1	2	4	9	1	0	367	21.1	87	5.0	12	0.7	36.1	41.4	0 0	0	7	44	176 50	2 646	255	82	18	10 2	0	0	0	0	0 (0	0	0	0	0	0 0	0 0	1
Sun	1451	101	1150	27	145	3	6	3	2	3	9	1	1	416	28.7	156	10.8	76	5.2	38.2	43.6	0 2	0	4	23	121 38	1 504	237	76	27	9 17	17	28	4	1	0 (0	0	0	0	0	0 0	0 0	1
5 Day Ave.	1856	85	1381	26	278	17	21	3	7	11	26	1	0	648	34.9	350	18.9	261	14.1	39.9	47.0	0 1	1	7	36	151 433	2 581	273	78	36	69 60	58	27	27	10	6 :	3 0	1	0	0	0	0 0	0 0	I
7 Day Ave.	1782	108	1339	24	240	14	17	3	6	9	21	1	0	574	32.2	285	16.0	199	11.2	39.8	47.0	0 1	1	7	35	151 43	5 579	265	78	32	52 46	44	23	20	7	4 2	2 0	0	0	0	0	0 0	0 0	1
	12473	754	9376	168	1682	98	122	18	39	61	146	6	3	4021	32.2	1992	16.0	1392	11.2	39.8	47.0	0 6	4	48	245	1054 304	2 4053	1855	547	227	320	307	164	138	52	29 1:	3 2	3	2	0	0	0 0	0 0	1





		Virtual Da	ay (7)																			Virtual D	Day (7)																			
Time	Total						Classifi	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Speed B	ins (mp	h)									
		1	2	3	4	5	6	7	8	9	10	11	12	40	40	46	46	55	55		85		5 - 10 -	15 -	20 - 25	- 00 05	35 -	40 -	45 - 50	- 55 -	60 - 65	- 70 -	75 -	80 -	85 - 90	- 95 -	100 - 1	105 - 110	0 - 115 -	120 - 11	25 - 130	- 135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 1	10 15	20	25 30) 30 - 35	40	45	50 55	60	65 70	75	80	85	90 95	100	105	110 11	5 120	125 1	30 135	5 140
0000	13	0	8	0	2	0	1	0	0	0	1	0	0	4	33.0	2	12.5	0	2.3	38.5	45.4	0	0 0	0	0 1	3	5	2	1 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
0100	12	0	6	0	3	0	1	0	0	1	1	0	0	3	27.7	1	12.1	0	0.0	37.5	44.8	0	0 0	0	0 2	2	5	2	1 0	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
0200	10	0	5	0	3	0	0	0	0	0	1	0	0	3	29.9	1	7.5	0	1.5	36.2	-	0	0 0	0	0 1	3	2	2	0 0	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
0300	6	0	3	0	2	0	0	0	0	1	0	0	0	2	29.6	0	4.5	0	0.0	37.1	-	0	0 0	0	0 1	2	2	2	0 0	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
0400	15	0	7	0	5	0	0	0	0	1	1	0	0	6	39.8	2	13.9	0	0.9	38.1	45.7	0	0 0	0	0 2	3	4	3	2 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
0500	39	0	21	0	11	1	0	0	1	2	2	0	0	18	46.7	6	14.4	1	3.3	39.9	45.9	0	0 0	0	0 2	6	12	11	5 1	1	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
0600	70	0	43	2	15	2	1	0	1	2	4	0	0	27	38.4	9	12.8	0	0.6	39.2	45.1	0	0 0	0	0 2	12	29	16	9 2	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
0700	134	1	95	2	26	2	1	0	1	3	3	0	0	35	26.0	6	4.6	0	0.1	37	42.1	0	0 0	0	0 8	38	52	26	7 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
0800	192	4	133	4	38	1	5	1	1	2	3	0	0	38	19.9	4	2.0	0	0.1	36	40.9	0	0 0	2	2 1	59	75	32	5 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
0900	247	7	185	4	40	1	2	0	1	2	3	0	0	28	11.5	5	2.0	1	0.2	34.7	39.3	0	0 0	0	4 3	94	88	23	4 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
1000	328	15	250	4	45	3	3	1	1	2	3	0	0	27	8.3	4	1.2	1	0.2	33	37.7	0	0 1	2	11 7	141	74	22	4 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
1100	349	20	268	7	41	2	4	0	1	2	3	0	0	20	5.7	4	1.0	1	0.2	32.5	37.1	0	0 0	1	16 93	148	71	15	3 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
1200	372	18	293	7	42	1	2	0	2	3	4	0	0	25	6.6	4	1.1	1	0.2	32.4	37.4	0	0 1	3	18 93	157	77	20	3 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
1300	389	23	298	6	47	2	5	1	1	3	4	0	0	23	6.0	5	1.3	0	0.1	32.1	36.7	0	1 2	3	18 10	0 167	75	17	5 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
1400	364	20	284	4	44	2	3	0	1	2	3	0	0	23	6.3	4	1.2	1	0.2	32.5	37.1	0	0 0	3	23 8	151	83	17	5 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
1500	362	18	289	4	38	1	4	1	2	1	5	0	0	24	6.7	5	1.5	1	0.4	32.5	37.2	0	0 1	2	19 9	147	77	18	4 1	1	1 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
1600	336	15	273	3	38	1	1	0	1	1	3	0	0	31	9.2	5	1.6	1	0.2	33.1	38.1	0	0 0	2	15 6	145	77	24	4 2	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
1700	279	11	230	2	27	1	2	0	1	1	3	0	0	32	11.5	6	2.0	0	0.2	34.2	39.1	0	0 1	1	9 4	110	86	24	7 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
1800	224	8	186	3	22	0	2	1	0	1	1	0	0	38	17.1	8	3.8	1	0.4	35.5	40.6	0	0 0	1	5 2	72	83	28	8 2	1	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
1900	175	5	145	2	15	2	2	0	1	2	2	0	0	28	15.7	6	3.3	1	0.7	35.5	40.2	0	0 0	1	3 1	58	67	21	4 2	1	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
2000	102	5	83	1	9	1	2	0	1	0	1	0	0	25	24.4	4	4.3	1	0.6	36.9	42	0	0 0	0	1 7	27	42	19	4 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
2100	76	0	62	0	9	1	2	0	0	1	1	0	0	18	23.6	4	4.9	0	0.4	36.5	42.1	0	0 0	0	1 6	21	29	14	4 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
2200	42	0	34	0	5	0	1	0	0	1	0	0	0	10	23.6	3	6.5	0	0.7	36.4	42.2	0	0 0	0	1 6	9	16	6	2 1	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
2300	27	0	21	0	2	0	2	0	0	0	1	0	0	8	30.0	2	6.3	0	0.5	37.8	43.3	0	0 0	0	0 2	6	11	6	2 0	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0 0	0
07-19	3577	159	2784	51	449	20	33	6	14	23	37	1	1	345	9.7	61	1.7	7	0.2	33.4	38.4	0	2 7	21	140 71	2 1431	919	265	58 15	5 4	2 1	0	0	0	0 0	0	0	0 0	0	0	0 0	0
06-22	4000	169	3116	56	497	24	39	6	17	29	44	1	1	443	11.1	84	2.1	10	0.2	33.7	38.9	0	2 7	22	145 74	7 1549	1086	334	79 20) 6	2 1	0	0	0	0 0	0	0	0 0	0	0	0 0	0
06-00	4069	169	3171	57	505	25	43	6	17	30	45	1	1	461	11.3	88	2.2	10	0.3	33.8	39	0	2 7	22	145 75	5 1564	1114	346	83 21	1 7	2 1	0	0	0	0 0	0	0	0 0	0	0	0 0	0
00-00	4163	169	3221	58	530	27	45	7	19	35	52	1	1	497	11.9	100	2.4	12	0.3	33.9	39.1	0	2 7	22	146 76	4 1583	1144	368	93 24	1 8	3 1	0	0	0	0 0	0	0	0 0	0	0	0 0	0

		Virtual We	eek (1)																			Virtual V	leek (1)																				
Time	Total						Classifi	cation]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spe	eed Bins	(mph)										
		1	2	3	4	5	6	7	8	9	10	11	12	40	40	46	46	55	55		85	5	- 10 -	15 -	20 -	25 - 20	35 -	40 -	45 -	50 - 5	5 - 60 -	65 -	70 -	75 - 80) - 85	- 90 -	95 -	100 - 10	5 - 110	J - 115 ·	120 -	125 - 130	0 - 135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 1	0 15	20	25	30	40	45	50	55 6	0 65	70	75	80 8	5 90	95	100	105 11	10 11!	5 120	125	130 13	5 140
Mon	3964	109	2986	51	601	30	50	5	29	44	57	1	1	474	12.0	100	2.5	11	0.3	34.1	39.1	0	3 7	18	141	616 15	19 1186	353	93	17	8 2	0	1	0 () 0	0	0	0 (0	0	0	0 0	0
Tue	3977	137	2926	68	622	27	37	6	21	42	87	1	3	472	11.9	87	2.2	8	0.2	33.7	39.1	0	0 10	31	129	805 15	36 994	357	77	30	5 1	1	1	0 () 0	0	0	0 (0	0	0	0 0) 0
Wed	3829	128	2762	54	637	31	68	8	21	36	80	3	1	436	11.4	104	2.7	13	0.3	33.7	39.3	0	4 9	35	176	734 13	64 1071	301	98	24	4 7	2	0	0 () 0	0	0	0 (o 0	0	0	0 0	0
Thu	4062	147	3006	71	584	33	67	6	21	57	67	1	2	533	13.1	104	2.6	9	0.2	34.1	39.4	0	1 10	20	138	695 15	76 1089	401	98	25	B 1	0	0	0 () 0	0	0	0 (o 0	0	0	0 0	0
Fri	4973	196	3910	68	609	33	41	9	17	38	50	1	1	589	11.8	113	2.3	12	0.2	34	39.1	1 :	3 7	27	154	867 19	05 1420	436	121	20 1	1 1	0	0	0 () 0	0	0	0 (J 0	0	0	0 0	0
Sat	4316	307	3537	47	354	15	22	2	8	13	10	1	0	541	12.5	97	2.2	16	0.4	33.8	39.3	0 (0 3	13	157	869 16	24 1109	418	81	26	7 6	2	1	0 () 0	0	0	0 (o 0	0	0	0 0	0
Sun	4023	159	3422	46	301	17	30	11	14	13	10	0	0	434	10.8	94	2.3	16	0.4	34	39	0 (0 2	11	125	759 15	56 1136	308	86	24 1	0 2	0	0	1 () 3	0	0	0 (o 0	0	0	0 0	0
5 Day Ave.	4161	143	3118	62	611	31	53	7	22	43	68	1	2	501	12.0	102	2.5	11	0.3	33.9	39.2	0	2 9	26	148	743 15	30 1152	370	97	23	7 2	1	0	0 (0	0	0	0 (0	0	0	0 0	0
7 Day Ave.	4163	169	3221	58	530	27	45	7	19	35	52	1	1	497	11.9	100	2.4	12	0.3	33.9	39.1	0	2 7	22	146	764 15	3 1144	368	93	24	8 3	1	0	0 (0	0	0	0 (0	0	0	0 0	0
	29144	1183	22549	405	3708	186	315	47	131	243	361	8	8	3479	11.9	699	2.4	85	0.3	33.9	39.1	1 1	1 48	155	1020	5345 110	80 8005	2574	654	166 5	3 20	5	3	1 () 3	0	0	0 (5 0	0	0	0 0	0






June 2021	A83 approx 350m south of Garron Bridge
Automatic Traffic Count	North South

		Virtual Da	y (7)																			Virtual Da	y (7)																				
Time	Total						Classi	fication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spe	eed Bins	(mph)										
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5 -	10 -	15 -	20 -	25 -	35	- 40 -	45 -	50 - 55	- 60 -	65 -	70 -	75 - 80 -	85 -	90 -	95 -	100 - 10!	5 - 110	- 115 -	120 - 12	25 - 130 - 1	35 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 10	15	20	25	30 30 -	35 40	45	50	55 6) 65	70	75	80 85	90	95	100	105 11	0 115	120	125 1	30 135	140
0000	14	0	10	0	2	0	1	0	0	0	0	0	0	3	22.9	1	4.2	0	0.0	55	62.2	0 0	0	0	0	0 (0	1	3	4 3	2	0	1	0 0	0	0	0	0 0	0	0	0	0 0	0
0100	12	0	7	0	3	0	1	0	0	0	1	0	0	2	12.9	0	2.4	0	1.2	52.7	59.5	0 0	0	0	0	0 0	0	1	2	4 2	1	0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0200	11	0	6	0	2	0	0	0	0	1	1	0	0	0	1.3	0	0.0	0	0.0	46.9	54.2	0 0	0	0	0	0 1	1	3	2	3 1	0	0	0	0 0	0	0	0	0 0	0 (0	0	0 0	0
0300	7	0	4	0	1	0	0	0	0	0	1	0	0	1	7.8	0	0.0	0	0.0	50.3	-	0 0	0	0	0	0 0	0	1	2	1 1	0	0	0	0 0	0	0	0	0 0	0 (0	0	0 0	0
0400	16	0	9	0	5	0	0	0	0	1	1	0	0	3	17.7	1	7.1	0	2.7	53.2	61.3	0 0	0	0	0	0 0) 1	2	1	4 5	1	1	0	0 0	0	0	0	0 0	0 (0	0	0 0	0
0500	39	0	23	1	10	1	1	0	1	1	2	0	0	8	21.3	3	6.6	1	2.6	55.1	63.6	0 0	0	0	0	0 0) 0	3	8	10 9	3	3	1	1 0	0	0	0	0 0	0 (0	0	0 0	0
0600	70	0	46	2	13	1	1	0	1	2	4	0	0	20	28.7	3	4.5	0	0.6	55	63.5	0 0	0	0	0	0 1	1	8	8	13 1	3 12	6	1	0 0	0	0	0	0 0	0	0	0	0 0	0
0700	130	1	90	2	24	3	3	0	1	2	3	0	0	18	14.2	3	2.2	1	0.4	51.9	59.7	0 0	0	0	0	0 1	4	21	25	35 2	12	5	1	0 0	0	0	0	0 0) 0	0	0	0 0	0
0800	190	4	135	3	36	2	4	1	1	1	3	0	0	17	8.9	3	1.7	1	0.3	50.8	57.9	0 0	0	1	0	0 2	2 8	27	47	55 3	3 10	5	1	1 0	0	0	0	0 0) 0	0	0	0 0	0
0900	237	7	182	4	35	2	2	0	1	2	3	0	0	16	6.7	2	1.0	0	0.2	49.3	56.5	0 0	0	1	0	0 3	3 16	48	64	57 3	3 11	4	1	0 0	0	0	0	0 0	0 0	0	0	0 0	0
1000	330	21	250	4	42	4	2	1	1	2	3	0	0	17	5.2	5	1.4	2	0.6	47.9	54.1	0 0	0	0	0	1 3	3 29	86	98	71 2	5 11	3	2	1 0	0	0	0	0 0	0 0	0	0	0 0	0
1100	335	22	256	8	39	2	2	0	1	1	4	0	0	16	4.7	5	1.4	3	0.9	47.2	53.7	0 0	0	0	1	1 3	35	95	104	54 2	1 9	3	1	1 1	1	0	0	0 0	0	0	0	0 0	0
1200	363	22	284	9	38	1	2	0	1	2	4	0	0	12	3.4	3	0.8	2	0.5	46.3	52.7	0 0	0	0	0	2 1	1 45	107	101	60 2	6	3	1	1 0	0	0	0	0 0	0	0	0	0 0	0
1300	384	25	295	8	43	2	4	1	1	2	4	0	0	15	3.9	5	1.2	2	0.6	45.7	52.7	0 0	1	1	2	6 1	3 50	105	111	57 2	9	3	1	1 1	0	0	0	0 0	0	0	0	0 0	0
1400	354	23	277	5	39	3	2	0	1	1	3	0	0	16	4.5	6	1.6	4	1.1	47.1	53.5	0 0	0	1	2	3 5	35	97	106	66 2	8	3	1	1 1	1	0	0	0 0) 0	0	0	0 0	0
1500	351	22	274	5	40	1	2	1	1	0	4	0	0	21	5.9	6	1.7	3	0.9	48.2	54.6	0 0	0	1	0	0 3	3 25	96	107	70 2	11	5	1	1 1	0	0	0	0 0	0	0	0	0 0	0
1600	328	16	262	4	38	2	1	0	1	1	3	0	0	23	6.9	7	2.1	2	0.6	48.7	55.3	0 0	0	0	0	1 5	5 22	74	106	69 2	12	6	3	1 1	0	0	0	0 0) 0	0	0	0 0	0
1700	271	13	225	2	23	1	1	0	1	1	3	0	0	20	7.4	5	1.9	1	0.5	50.1	56.7	0 0	0	1	0	0 2	2 11	50	87	65 3	10	6	2	1 0	0	0	0	0 0) 0	0	0	0 0	0
1800	219	6	182	3	21	1	1	1	0	1	1	0	0	26	11.7	7	3.1	3	1.3	51.5	58.7	0 0	0	0	0	0 3	9	29	56	60 3	7 16	4	3	2 1	0	0	0	0 0) 0	0	0	0 0	0
1900	169	5	139	2	14	2	2	0	1	1	1	0	0	20	12.0	6	3.7	2	1.1	51.6	58.8	0 0	0	0	0	0 2	2 6	21	49	44 2	7 11	5	3	1 1	0	0	0	0 0) 0	0	0	0 0	0
2000	98	4	81	1	8	1	1	0	0	0	1	0	0	23	23.1	8	7.7	3	3.3	55.3	62.6	0 0	0	0	0	0 () 2	7	17	26 2	3 12	5	2	1 1	0	0	1	0 0) 0	0	0	0 0	0
2100	73	1	58	0	8	1	2	0	0	1	1	0	0	14	19.2	2	3.3	1	1.0	54	61.6	0 0	0	0	0	0 () 1	6	14	21 1	8	4	1	0 0	0	0	0	0 0) 0	0	0	J 0	0
2200	39	0	31	0	5	0	1	0	0	1	1	0	0	8	20.2	2	4.4	0	1.1	52.9	61.8	0 0	0	0	0	0 () 1	4	8	11 7	5	2	1	0 0	0	0	0	0 0) 0	0	0	J 0	0
2300	26	0	20	0	2	0	2	0	0	0	1	0	0	5	17.5	1	3.3	0	1.1	53	60.6	0 0	0	0	0	0 () 1	3	6	7 5	3	1	0	0 0	0	0	0	0 0) 0	0	0	0 0	0
07-19	3491	182	2711	57	418	24	26	6	11	18	38	1	1	217	6.2	55	1.6	24	0.7	48.2	55.3	0 1	2	6	6	14 5	6 289	832	1013	717 33	9 125	49	19	10 6	4	2	1	0 0	0	0	0	0	0
06-22	3902	193	3036	62	461	29	32	6	13	23	45	1	1	294	7.5	75	1.9	30	0.8	48.8	56.2	0 1	2	6	6	14 5	9 301	875	1100	821 42	4 168	70	25	13 8	5	2	2	1 0	0	0	0	0 0	0
06-00	3967	194	3087	63	468	29	35	6	13	24	46	1	1	306	7.7	77	2.0	31	0.8	48.9	56.3	0 1	2	6	6	14 5	9 303	882	1114	839 43	6 177	72	26	14 8	5	2	2	1 0	0	0	0	0 0	0
00-00	4066	194	3145	64	492	31	38	7	15	27	52	1	1	323	7.9	82	2.0	33	0.8	49	56.4	0 1	2	6	6	14 6	0 306	893	1134	865 45	8 185	77	28	15 9	5	2	2	1 0	0	0	0	0 0	0


																								-												4					4		
		Virtual We	eek (1)																			Virtual We	ek (1)																				
Time	Total						Classifi	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spe	ed Bins ((mph)										
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5 -	10 -	15 -	20 -	25 -	35 -	40 -	45 - 5	0 - 55 -	60 -	65 -	70 -	75 - 80	- 85 -	90 -	95 - 1	100 - 105	5 - 110	- 115 -	120 - 1	125 - 13	0 - 135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 10	15	20	25	30 30 - 3	40	45	50	55 60	65	70	75	80 8!	5 90	95	100	105 11	115	120	125 1	130 13	35 140
Mon	3844	121	2886	59	557	35	49	2	26	43	64	1	1	290	7.5	69	1.8	20	0.5	47.1	56	0 5	10	18	33	78 162	458	807	879 7	25 379	166	78	26	12 2	0	1	4	1 0	0	0	0	0 () 0
Tue	3870	149	2878	79	563	29	30	6	15	29	90	1	1	284	7.3	63	1.6	18	0.5	49	56.2	0 1	3	7	1	0 35	257	884	1123 8	323 452	174	70	22	6 7	3	1	1	0 0	0	0	0	0 () 0
Wed	3759	149	2733	61	584	32	69	11	12	32	72	2	2	291	7.7	60	1.6	26	0.7	49	56.5	0 0	1	5	0	3 39	285	868	1075	50 440	175	65	25	12 6	, 3	2	3	0 0	0	0	0	0 2	2 0
Thu	4005	162	3006	75	548	39	48	7	18	34	65	1	2	325	8.1	90	2.2	38	0.9	49.6	56.7	0 0	0	1	2	4 31	243	906	1108	10 475	182	81	24	15 1:	3 5	2	2	1 0	0	0	0	0 () 0
Fri	4839	221	3792	73	572	40	38	9	12	30	50	1	1	363	7.5	90	1.9	34	0.7	49	56.1	0 0	2	5	2	7 74	317	1076	1423 1	043 527	201	96	32	19 1	1 0	3	1	0 0	0	0	0	0 () 0
Sat	4216	362	3412	56	326	22	8	2	7	11	10	0	0	359	8.5	102	2.4	34	0.8	48.9	56.1	0 0	0	1	0	3 52	371	955	1220 8	350 405	200	78	47	15 7	8	2	0	2 0	0	0	0	0 () 0
Sun	3930	194	3311	45	291	22	23	9	13	9	13	0	0	347	8.8	100	2.5	58	1.5	50.2	57.2	0 1	1	4	2	0 27	208	752	1107	525	194	74	21	24 1	5 13	6	0	0 0	0	0	0	0 () 0
5 Day Ave.	4063	160	3059	69	565	35	47	7	17	34	68	1	1	311	7.7	74	1.8	27	0.7	48.7	56.3	0 1	3	7	8	18 68	312	908	1122 8	350 455	180	78	26	13 8	2	2	2	0 0	0	0	0	0 () 0
7 Day Ave.	4066	194	3145	64	492	31	38	7	15	27	52	1	1	323	7.9	82	2.0	33	0.8	49.0	56.4	0 1	2	6	6	14 60	306	893	1134 8	865 458	185	77	28	15 9	5	2	2	1 0	0	0	0	0 () 0
	28463	1358	22018	448	3441	219	265	46	103	188	364	6	7	2259	7.9	574	2.0	228	0.8	49.0	56.4	0 7	17	41	40	95 420	2139	6248	7935 6	057 3203	1292	542	197	103 6	1 32	17	11	4 0	0	0	0	0 1	2 0





		Virtual D	ay (7)																			Virtual Da	y (7)																				
Time	Total						Classi	fication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spe	ed Bins (
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5-	10 -		20 -	25 - 20	35 -	40 -	45 -	50 - 55 -	60 -	65 -	70 -	75 - 80 -	85 -	90 -						25 - 130 -	
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			10	15	20	25	30	40	45	50	55 60	65	70	75	80 85	90	95	100	105 1	10 11	5 120	125 1	130 135	140
0000	5	0	3	0	1	0	0	0	0	0	0	0	0	0	8.6	0	5.7	0	5.7	53.5	-	0 0	0	0	0	0 0	0	0	1	2 1	0	0	0	0 0	0	0	0	0 /	0 0	0	0	0 0	0
0100	4	0	2	0	1	0	1	0	0	0	0	0	0	1	37.0	0	11.1	0	3.7	57.9	-	0 0	0	0	0	0 0	0	0	1	1 1	1	0	0	0 0	0	0	0	0	0 0	0	0	0 0	0
0200	2	0	1	0	1	0	0	0	0	0	1	0	0	0	17.7	0	11.8	0	11.8	52.1	-	0 0	0	0	0	0 0	0	1	1	0 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0 0	0
0300	2	0	1	0	1	0	0	0	0	0	0	0	0	0	13.3	0	13.3	0	6.7	52.9	-	0 0	0	0	0	0 0	0	0	0	1 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0 0	0
0400	5	0	4	0	1	0	0	0	0	0	0	0	0	2	37.8	1	21.6	0	5.4	58.8	-	0 0	0	0	0	0 0	0	0	1	1 1	0	1	0	0 0	0	0	0	0	0 0	0	0	0 0	0
0500	11	0	7	0	2	0	1	0	0	0	1	0	0	5	48.1	2	19.5	1	5.2	60.2	71.8	0 0	0	0	0	0 0	0	0	2	2 2	2	2	1	0 0	0	0	0	0	0 0	0	0	0 0	0
0600	27	0	18	1	5	0	1	0	0	1	1	0	0	9	34.0	3	11.7	0	1.6	57.4	67	0 0	0	0	0	0 0	0	1	3	6 8	4	3	2	0 0	0	0	0	0	0 0	0	0	0 0	0
0700	55	1	38	1	8	0	3	0	1	1	2	0	0	18	32.4	5	9.8	2	2.9	56.7	65.4	0 0	0	0	0	0 0	1	3	8	12 13	9	5	3	1 0	0	0	0	0	0 0	0	0	0 0	0
0800	69	1	49	2	13	1	2	0	0	1	0	0	0	21	31.0	7	10.6	3	4.0	56.5	65.6	0 0	0	0	0	0 0	1	4	11	18 14	10	6	3	2 1	0	0	0	0	0 0	0	0	0 0	0
0900	93	7	69	1	13	0	1	0	0	0	1	0	0	22	23.8	7	7.4	2	2.6	54.8	63.7	0 0	0	0	0	0 0	3	5	18	23 20	11	6	3	1 1	1	0	0	0	0 0	0	0	0 0	0
1000	142	11	106	2	18	2	2	0	0	0	1	0	0	30	21.3	11	8.1	4	3.0	53.8	62.9	0 0	0	0	0	1 1	4	12	31	39 22	13	8	5	2 1	0	0	0	0 (0 0	0	0	0 0	0
1100	142	12	104	3	20	0	2	0	0	0	1	0	0	28	20.0	10	7.0	5	3.5	54.4	62.9	0 0	0	0	0	0 0	3	12	34	34 30	13	7	4	2 1	1	0	0	0	0 0	0	0	0 0	0
1200	148	17	106	3	18	1	1	0	0	0	1	0	0	30	20.6	10	6.8	3	2.0	54.4	61.9	0 0	0	0	0	0 1	2	11	30	38 34	16	7	4	1 1	0	0	0	0	0 0	0	0	0 0	0
1300	139	14	98	3	19	1	1	0	0	1	1	0	0	31	22.5	11	8.1	4	3.0	54.7	62.7	0 0	0	0	0	0 1	3	10	27	36 31	17	5	5	2 1	1	0	0	0 (0 0	0	0	0 0	0
1400	137	14	97	2	19	2	1	0	0	1	2	0	0	32	23.0	14	9.9	5	3.5	55.1	64.2	0 0	0	0	0	1 1	3	12	26	30 33	13	9	5	2 1	1	0	1	0 (0 0	0	0	0 0	0
1500	145	15	103	3	17	1	1	0	1	1	3	0	0	34	23.2	16	10.8	8	5.6	54.7	63.6	0 0	0	0	0	0 1	4	14	33	35 24	13	8	4	3 3	1	0	0	1 '	0 0	0	0	0 0	0
1600	143	12	109	1	16	1	1	0	0	0	2	0	0	36	25.3	12	8.7	5	3.8	55.3	63.5	0 0	0	0	0	0 1	4	10	23	40 29	19	7	4	2 1	1	1	0	0 (0 0	0	0	0 0	0
1700	127	6	103	2	12	1	2	0	0	1	1	0	0	33	26.2	12	9.3	5	4.2	56.2	65	0 0	0	0	0	0 1	1	6	21	36 29	14	10	4	3 0	1	0	0	0 /	0 0	0	0	0 0	0
1800	85	3	70	1	10	0	1	0	0	0	1	0	0	29	33.4	10	11.4	4	4.7	57.3	65.9	0 0	0	0	0	0 0	1	5	11	18 21	14	6	4	2 1	1	0	0	0 /	0 0	0	0	0 0	0
1900	60	2	49	1	5	1	1	0	0	0	0	0	0	18	30.7	6	10.0	3	5.5	56.6	64.6	0 0	0	0	0	1 0	0	3	8	15 14	10	4	1	1 1	0	0	0	0 /	0 0	0	0	0 0	0
2000	41	2	32	0	5	1	0	0	0	0	1	0	0	14	33.2	6	14.2	2	5.9	57.6	67.1	0 0	0	0	0	0 0	1	2	5	9 10	7	3	2	1 1	0	0	0	0	0 0	0	0	0 0	0
2100	30	1	24	0	4	0	0	0	0	0	1	0	0	12	40.9	4	13.5	1	4.8	58	67.2	0 0	0	0	0	0 0	1	1	3	6 6	6	3	2	1 0	0	0	0	0	0 0	0	0	0 0	0
2200	18	0	14	0	2	0	0	0	0	1	1	0	0	6	34.2	1	7.3	0	2.4	55.3	65.1	0 0	0	0	0	0 0	0	2	2	4 3	3	2	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
2300	11	0	8	0	1	0	0	0	0	0	1	0	0	3	32.0	2	17.3	1	6.7	58.6	70	0 0	0	0	0	0 0	0	1	1	3 3	1	1	1	0 0	0	0	0	0	0 0	0	0	0 0	0
07-19	1425	113	1053	25	183	9	16	3	3	6	15	0	0	345	24.2	125	8.8	51	3.6	55.1	63.6	0 0	1	2	0	3 8	29	104	273	361 300	164	84	46	23 11	8	4	2	1	2 0	0	0	0 0	0
06-22	1583	118	1176	28	201	11	18	3	3	7	18	0	0	398	25.2	144	9.1	58	3.7	55.3	64	0 0	1	2	1	4 9	31	111	292	396 338	191	97	52	26 14	8	4	2	1	2 0	0	0	0 0	0
06-00	1611	118	1198	28	204	11	18	3	3	8	20	0	0	408	25.3	148	9.2	60	3.7	55.4	64	0 0	1	2	1	4 9	31	114	295	403 343	195	99	54	27 14	8	4	2	1	2 0	0	0	0 0	0
00-00	1641	118	1216	28	210	11	20	3	3	9	22	0	0	418	25.4	152	9.3	61	3.7	55.4	64.1	0 0	1	2	1	4 9	32	115	301	410 349	198	103	55	28 15	9	4	2	1	2 0	0	0	0 0	0
		Virtual W	(1, (d)																			Virtual We	1 (4)																			$\overline{}$	


		Virtual We	eek (1)																			Virtual We	eek (1)																					
Time	Total						Classif	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Sp	eed Bin	s (mph)	1										
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5	10 -	15 -	20 -	25 - 20	35 -	40 -	45 -	50 - 55	- 60 -	65 -	70 -	75 -	80 - 85	- 90 -	95 -	100 - 1	105 - 11	0 - 115	- 120	- 125 -	130 - 13	35 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			10 - 5	15	20	25	30	40	45	50	55 6	0 65	70	75	80	85 90	95	100	105	110 1	15 120	J 125	130	135 1	40
Mon	1534	75	1111	25	253	13	18	2	2	11	22	1	1	344	22.4	112	7.3	44	2.9	54.6	63.1	0 2	0	1	0	2 9	34	127	302	396 3	7 170	82	48	20	9 5	7	1	0	2 (0 0	0	0	0	0
Tue	1550	79	1113	40	225	10	32	2	4	10	35	0	0	373	24.1	132	8.5	50	3.2	54.6	64.1	0 0	4	0	1	4 10	40	125	321	387 2	5 167	104	52	22	14 9	5	0	0	0 (0 0	0	0	0	0
Wed	1756	104	1266	31	248	10	34	7	4	14	38	0	0	431	24.5	164	9.3	64	3.6	55.1	63.9	0 0	1	2	0	6 16	37	120	329	454 3	0 197	117	53	34	16 7	4	2	0	0	1 0	0	0	0	0
Thu	1769	114	1284	33	247	13	33	1	5	16	23	0	0	447	25.3	160	9.0	60	3.4	55.2	64	0 0	0	4	2	5 12	36	132	300	477 3	4 219	106	62	30	12 9	4	4	1	0 (0 0	0	0	0	0
Fri	1817	117	1360	25	241	18	16	6	6	8	20	0	0	487	26.8	160	8.8	60	3.3	55.8	64.1	0 0	2	3	1	1 7	26	110	315	414 4	1 249	116	62	32	17 6	2	2	0	1 (0 0	0	0	0	0
Sat	1686	231	1276	15	138	9	2	2	2	2	9	0	0	478	28.4	204	12.1	94	5.6	56.6	65.5	0 0	0	1	0	4 8	23	88	295	420 3	9 212	101	71	32	24 20	6	4	3	5 (0 0	0	0	0	0
Sun	1376	105	1105	27	115	5	3	3	1	2	10	0	0	363	26.4	133	9.7	57	4.1	55.7	64.1	0 0	1	1	0	3 4	25	104	245	321 3	9 175	92	39	25	10 7	3	4	4	4 (0 0	0	0	0	0
5 Day Ave.	1685	98	1227	31	243	13	27	4	4	12	28	0	0	416	24.7	146	8.7	56	3.3	55.1	63.8	0 0	1	2	1	4 11	35	123	313	426 3	3 200	105	55	28	14 7	4	2	0	1 (0 0	0	0	0	0
7 Day Ave.	1641	118	1216	28	210	11	20	3	3	9	22	0	0	418	25.4	152	9.3	61	3.7	55.4	64.1	0 0	1	2	1	4 9	32	115	301	410 3	9 198	103	55	28	15 9	4	2	1	2 (0 0	0	0	0	0
	11488	825	8515	196	1467	78	138	23	24	63	157	1	1	2923	25.4	1065	9.3	429	3.7	55.4	64.1	0 2	8	12	4	25 66	221	806	2107	2869 24	45 1389	718	387	195	102 63	31	17	8	12	1 0	0	0	0	0





		Virtual Day	y (7)																			Virtual D	ay (7)																				
Time	Total						Classifi	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spee	d Bins (r	mph)										
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5	- 10 -	15 -	20 - 2	5 - 20 .	35 -	40 -	45 - 5	0 - 55	- 60 -	65 - 7	70 - 7	75 - 80) - 85 -	90 -	95 -	100 - 105	5 - 110			25 - 130 -	135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 1	0 15	20	25	30 30	40	45	50	55 60	65	70	75	80 8!	5 90	95	100	105 11	0 115	120	125 13	30 135	140
0000	5	0	3	0	1	0	0	0	0	0	0	0	0	0	8.6	0	2.9	0	0.0	50.9	-	0	0 0	0	0	0 0	0	1	1	2 1	0	0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0100	4	0	3	0	1	0	0	0	0	0	0	0	0	1	13.8	0	6.9	0	0.0	54.6	-	0 (0 0	0	0	0 0	0	0	1	1 1	0	0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0200	2	0	1	0	0	0	0	0	0	0	1	0	0	0	17.7	0	11.8	0	0.0	50.2	-	0 (0 0	0	0	0 0	0	1	1	0 0	0	0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0300	2	0	0	0	1	0	0	0	0	0	0	0	0	0	16.7	0	8.3	0	0.0	50.8	-	0 (0 0	0	0	0 0	0	0	1	0 0	0	0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0400	5	0	4	0	0	0	0	0	0	0	1	0	0	2	33.3	1	11.1	0	0.0	55	-	0 (0 0	0	0	0 0	0	1	1	1 1	1	1	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0500	11	0	7	0	1	0	1	0	0	0	1	0	0	3	26.9	1	10.3	0	0.0	55.8	67	0 (0 0	0	0	0 0	0	1	2	2 3	1	1	1	0 0	0	0	0	0 0	0	0	0	0 0	0
0600	27	0	18	1	5	0	1	0	0	1	1	0	0	6	22.8	1	4.8	0	1.1	54.7	62.9	0 (0 0	0	0	0 0	0	2	4	8 6	4	2	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0700	56	1	41	1	8	0	2	0	0	1	2	0	0	10	17.6	2	3.1	0	0.0	53.9	61.5	0 (0 0	0	0	0 0	1	4	10	17 13	6	3	1	0 0	0	0	0	0 0	0	0	0	0 0	0
0800	69	1	50	2	12	1	1	0	0	1	0	0	0	14	20.0	4	5.4	1	1.5	53.7	61.5	0 (0 0	0	0	0 0	2	6	15	19 13	8	3	2	1 0	0	0	0	0 0	0	0	0	0 0	0
0900	92	7	69	1	12	1	1	0	0	0	1	0	0	13	14.0	3	3.4	1	0.8	52	59.5	0 (0 0	0	0	1 1	2	11	23	26 15	8	3	2	1 0	0	0	0	0 0	0	0	0	0 0	0
1000	138	11	104	2	17	2	2	0	0	0	1	0	0	16	11.6	3	2.0	1	0.5	51	58.3	0 (0 0	0	0	0 1	6	18	40	37 21	11	3	1	0 0	0	0	0	0 0	0	0	0	0 0	0
1100	143	12	105	3	20	1	1	0	0	0	1	0	0	17	12.0	3	2.4	1	1.0	51.3	58.6	0 (0 0	0	0	0 0	4	22	42	37 21	11	4	1	1 0	0	0	0	0 0	0	0	0	0 0	0
1200	147	17	105	4	17	1	1	0	0	0	1	0	0	15	10.5	3	1.8	1	0.5	51.3	58	0 (0 0	0	0	0 0	5	17	44	42 23	10	3	2	0 0	0	0	0	0 0	0	0	0	0 0	0
1300	139	14	97	4	18	2	1	0	0	1	1	0	0	15	10.7	4	2.9	1	0.9	51.3	58.4	0 (0 0	0	0	0 1	6	18	37	40 22	8	4	1	1 0	0	0	0	0 0	0	0	0	0 0	0
1400	139	15	99	2	18	2	1	0	0	1	2	0	0	18	12.6	6	4.0	2	1.5	51.6	58.9	0 (0 0	0	0	0 1	6	19	36	35 24	9	5	2	1 1	0	0	0	0 0	0	0	0	0 0	0
1500	146	16	106	3	15	1	2	0	1	0	2	0	0	17	11.3	7	4.5	1	1.0	50.7	58.2	0 (0 0	0	0	0 0	7	26	44	31 20	7	5	3	1 0	0	0	0	0 0	0	0	0	0 0	0
1600	142	11	109	1	15	1	2	0	0	0	2	0	0	20	13.8	5	3.3	1	0.9	51.9	59.6	0 (0 0	0	0	0 1	6	16	38	37 24	11	4	3	1 0	0	0	0	0 0	0	0	0	0 0	0
1700	125	6	101	2	12	1	1	0	0	1	1	0	0	21	16.7	5	3.8	2	1.5	52.9	60.6	0	0 0	0	0	0 1	3	12	33	33 23	13	5	1	1 0	0	0	0	0 0	0	0	0	0 0	0
1800	85	3	70	1	9	0	1	0	0	0	0	0	0	15	17.7	4	4.5	1	1.2	53.8	61.1	0	0 0	0	0	0 0	2	7	17	25 19	9	4	2	1 0	0	0	0	0 0	0	0	0	0 0	0
1900	59	2	49	1	4	1	1	0	0	0	0	0	0	11	19.4	3	4.8	1	1.7	54.2	61.4	0	0 0	0	0	0 0	0	5	12	17 13	6	3	1	0 0	0	0	0	0 0	0	0	0	0 0	0
2000	41	2	32	0	4	1	0	0	0	0	1	0	0	8	20.7	3	6.7	1	1.8	54.3	61.5	0 (0 0	0	0	0 0	1	3	7	11 9	4	2	1	0 0	0	0	0	0 0	0	0	0	0 0	0
2100	29	1	24	0	3	0	0	0	0	0	1	0	0	7	24.6	1	3.4	0	1.5	55.2	63	0 (0 0	0	0	0 0	1	2	5	6 8	5	2	0	0 0	0	0	0	0 0	0	0	0	0 0	0
2200	17	0	14	0	2	0	0	0	0	1	1	0	0	3	15.6	0	2.5	0	0.0	51.8	60.7	0 (0 0	0	0	0 0	1	3	3	5 3	2	1	0	0 0	0	0	0	0 0	0	0	0	0 0	0
2300	11	0	8	0	1	0	0	0	0	0	1	0	0	2	19.7	1	6.6	0	2.6	54	62	0 (0 0	0	0	0 0	0	1	2	3 2	1	0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
07-19	1422	114	1055	26	171	14	16	2	3	5	14	0	0	190	13.3	47	3.3	14	1.0	51.9	59.3	0	1 0	1	1	2 6	49	175	380 3	379 23	110	46	20	8 3	3 2	1	0	0 0	0	0	0	0 0	0
06-22	1578	119	1177	28	188	16	19	2	3	7	17	0	0	223	14.1	55	3.5	16	1.0	52.1	59.6	0	1 0	1	1	2 7	52	188	408	21 27	130	55	22	9 4	1 2	1	0	0 0	0	0	0	0 0	0
06-00	1606	119	1199	29	191	16	19	2	3	7	19	0	0	228	14.2	56	3.5	16	1.0	52.1	59.6	0	1 0	1	1	2 7	53	192	412	29 28	133	56	23	9 4	1 2	1	0	0 0	0	0	0	0 0	0
00-00	1636	119	1218	29	195	17	20	3	4	9	22	0	0	234	14.3	58	3.6	16	1.0	52.2	59.7	0	1 0	1	1	2 7	53	195	418 4	36 28	135	58	24	9 4	1 2	1	0	0 0	0	0	0	0 0	0

		Virtual We	eek (1)																			Virtual V	Veek (1)																				
Time	Total						Classif	cation]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spe	ed Bins	(mph)										
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	[5	5 - 10 -	15 -	20 -	25 - 25 .	35 -	40 -	45 -	50 -	55 - 60 -	65 -	70 -	5 - 8	0 - 85	5 - 90 -	95 -	100 - 1	105 - 11	10 - 11	15 - 12	0 - 125 -	130 - 135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5	10 15	20	25	30 30	40	45	50	55	60 65	70	75	80 8	35 9	0 95	100	105	110 1	115 1	20 12	25 130	135 140
Mon	1548	72	1138	28	239	15	22	1	2	11	20	0	0	197	12.7	43	2.8	10	0.6	51.6	59.2	0	1 0	3	0	3 10	54	193	403	426	258 118	54	15	7	2 1	0	0	0	0	0	0 () 0	0 0
Tue	1535	77	1109	36	215	15	29	3	4	13	34	0	0	215	14.0	50	3.3	13	0.8	51.7	59.5	0	2 0	0	1	4 7	58	199	410	399	240 133	44	25	7	4 0) 2	0	0	0	0	0 () 0	0 0
Wed	1748	106	1265	32	234	16	33	4	7	13	38	0	0	225	12.9	66	3.8	16	0.9	52	59.1	0	0 0	1	0	4 10	49	212	484	445	318 117	70	22	10	2 1	1 2	1	0	0	0	0 (0	0 0
Thu	1759	111	1293	36	223	20	30	1	6	13	25	1	0	245	13.9	49	2.8	14	0.8	52	59.3	0	0 1	0	3	4 4	60	217	436	482	307 154	52	25	7	6 1	0	0	0	0	0	0 (0	0 0
Fri	1813	123	1372	25	215	25	15	5	4	9	19	1	0	276	15.2	64	3.5	11	0.6	52.6	60.1	0	1 1	3	1	0 6	56	196	405	533	335 162	72	31	6	3 1	1 1	0	0	0	0	0 () 0	0 0
Sat	1686	238	1274	14	125	17	5	2	1	2	8	0	0	269	16.0	83	4.9	29	1.7	52.9	60.3	0	0 0	0	0	0 4	50	181	436	427	319 138	71	31	17	5 6	5 1	0	0	0	0	0 () 0	0 0
Sun	1360	109	1074	30	115	9	6	3	1	2	11	0	0	211	15.5	54	4.0	21	1.5	52.3	60.2	0	1 0	1	1	0 8	47	167	354	341	229 124	44	22	11	5 4	1 1	0	0	0	0	0 () 0	0 0
5 Day Ave.	1681	98	1235	31	225	18	26	3	5	12	27	0	0	232	13.8	54	3.2	13	0.8	52.0	59.4	0	1 0	1	1	3 7	55	203	428	457	292 137	58	24	7	3 1	1 1	0	0	0	0	0 (0	0 0
7 Day Ave.	1636	119	1218	29	195	17	20	3	4	9	22	0	0	234	14.3	58	3.6	16	1.0	52.2	59.7	0	1 0	1	1	2 7	53	195	418	436	287 135	58	24	9	4 2	2 1	0	0	0	0	0 (0	0 0
	11449	836	8525	201	1366	117	140	19	25	63	155	2	0	1638	14.3	409	3.6	114	1.0	52.2	59.7	0	5 2	8	6	15 49	374	1365	2928	3053	2006 946	407	171	65 2	27 1	4 7	1	0	0	0	0 (0	0 0






June 2021	A819 approx 100m north of access track
Automatic Traffic Count	North South

		Virtual Da	ay (7)																			Virtual Da	y (7)																					
Time	Total						Classif	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spee	ed Bins (n	mph)											
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5 -	10 -	15 -	20 - 25 -	.	35 -	40 - 4	15 - 50	0 - 55 -	60 -	65 - 7	70 -	75 - 80 -	85 -	90 -	95 - 1	100 - 1	05 - 11	0 - 115	- 120 -	125 - 1	30 - 13	5 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 10	15	20	25 30	30 - 35	40	45	50 5	5 60	65	70	75	80 85	90	95	100	105 1	110 1	15 120	125	130	135 1/	40
0000	5	0	4	0	1	0	0	0	0	0	0	0	0	0	2.9	0	2.9	0	0.0	47.1	-	0 0	0	0	0 0	0	0	2	2 1	1 0	0	0	0	0 0	0	0	0	0	0 (0 0	0	0	0	0
0100	4	0	2	0	1	0	1	0	0	0	0	0	0	0	11.1	0	0.0	0	0.0	49.8	-	0 0	0	0	0 0	0	0	1	1 1	1 0	0	0	0	0 0	0	0	0	0	0 (0 0	0	0	0	0
0200	2	0	1	0	0	0	0	0	0	0	1	0	0	0	0.0	0	0.0	0	0.0	45.1	-	0 0	0	0	0 0	0	0	0	0 1	1 0	0	0	0	0 0	0	0	0	0	0 (0 0	0	0	0	٥
0300	2	0	1	0	1	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	49.8	-	0 0	0	0	0 0	0	0	0	0 1	1 0	0	0	0	0 0	0	0	0	0	0 (0 0	0	0	0 0	0
0400	5	0	3	0	1	0	0	0	0	0	0	0	0	1	16.7	0	0.0	0	0.0	51.2	-	0 0	0	0	0 0	0	0	1	1 1	1 1	1	0	0	0 0	0	0	0	0	0 (0 0	0	0	0 /	٥
0500	10	0	6	0	2	0	1	0	0	0	1	0	0	1	14.3	0	2.9	0	0.0	51.4	-	0 0	0	0	0 0	0	1	1	3 2	2 2	1	0	0	0 0	0	0	0	0	0 (0 0	0	0	0 /	٥
0600	24	0	13	1	5	0	1	0	0	2	1	0	0	2	9.6	0	1.8	0	0.0	51.2	58.4	0 0	0	0	0 0	0	2	3	5 7	7 5	2	0	0	0 0	0	0	0	0	0 (0 0	0	0	0 (٥
0700	49	1	34	1	8	0	2	0	1	1	2	0	0	5	9.4	1	1.5	0	0.3	51	58.1	0 0	0	0	0 0	1	2	5	12 1	6 8	3	1	0	0 0	0	0	0	0	0 (0 0	0	0	0 /	o .
0800	65	1	46	2	12	0	2	0	0	0	0	0	0	5	8.2	1	1.5	0	0.7	50.3	57.7	0 0	0	0	0 1	1	4	7	18 2	20 9	4	1	0	0 0	0	0	0	0	0 (0 0	0	0	0 (0
0900	88	6	65	1	12	1	1	0	0	0	1	0	0	5	5.5	1	1.0	0	0.0	49	56.2	0 0	0	0	0 1	1	5	16	26 2	12	3	1	1	0 0	0	0	0	0	0 (0 0	0	0	0 (3
1000	138	12	101	2	17	2	2	0	0	0	1	0	0	8	5.7	2	1.5	1	0.4	48.6	55.3	0 0	0	0	0 0	3	7	30	47 2	9 14	5	2	1	0 0	0	0	0	0	0 (0 0	0	0	0 /	3
1100	137	14	96	3	20	0	1	0	0	0	1	0	0	11	7.7	3	2.0	1	0.9	48.6	55.8	0 0	0	0	0 1	2	12	31	40 2	7 14	6	2	1	0 0	0	0	0	0	0 (0 0	0	0	0 /	J
1200	141	15	99	4	19	1	1	0	0	0	1	0	0	8	5.6	2	1.1	0	0.3	47.8	54.9	0 0	0	0	0 2	2	12	33	43 2	9 13	5	2	0	0 0	0	0	0	0	0 (0 0	0	0	0 /	J
1300	135	14	94	3	19	1	1	0	0	1	1	0	0	8	5.9	1	1.1	1	0.5	48.7	55.3	0 0	0	0	0 1	1	9	28	44 3	13	5	2	0	0 0	0	0	0	0	0 (0 0	0	0	0 (J
1400	137	16	98	2	17	1	1	0	0	1	2	0	0	12	8.7	5	3.3	2	1.4	49.3	56.8	0 0	0	0	0 0	2	10	28	39 3	15	6	2	2	1 1	0	0	0	0	0 (0 0	0	0	0 (0
1500	141	16	101	2	16	0	1	0	1	0	2	0	0	10	7.0	3	2.4	1	0.8	48.5	55.4	0 0	0	0	0 1	3	9	33	42 3	13	5	3	1	1 0	0	0	0	0	0 (0 0	0	0	0 /	J
1600	140	11	106	1	16	1	2	0	1	0	2	0	0	13	9.5	4	2.6	2	1.2	49.7	57.1	0 0	1	0	0 0	3	6	25	39 3	15	8	2	1	1 1	0	0	0	0	0 (0 0	0	0	0 /	J
1700	127	7	100	2	14	1	1	0	0	0	1	0	0	9	7.4	3	2.1	1	0.6	50	56.2	0 0	0	0	0 0	2	5	21	39 3	3 17	5	2	2	0 0	0	0	0	0	0 (0 0	0	0	0 /	J
1800	81	3	65	1	9	0	1	0	0	0	0	0	0	7	8.9	1	1.6	0	0.2	51	57.8	0 0	0	0	0 0	1	2	10	23 2	7 11	5	2	1	0 0	0	0	0	0	0 (0 0	0	0	0 /	J
1900	55	3	46	1	4	1	1	0	0	0	1	0	0	7	13.4	2	3.6	1	1.0	51.2	59.1	0 0	0	0	0 0	1	3	7	15 1	3 9	4	2	1	0 0	0	0	0	0	0 (0 0	0	0	0 0	0
2000	41	3	31	0	4	1	0	0	0	0	1	0	0	4	9.8	1	3.1	1	1.7	51.6	57.5	0 0	0	0	0 0	1	1	5	9 1	4 7	2	1	0	0 0	0	0	0	0	0 (0 0	0	0	0 0	J
2100	30	1	23	0	5	0	0	0	0	0	1	0	0	3	10.9	0	0.5	0	0.0	52	58.6	0 0	0	0	0 0	0	1	2	8 9	9 6	3	1	0	0 0	0	0	0	0	0 (0 0	0	0	0 /	J
2200	17	0	13	0	2	0	0	0	0	1	1	0	0	2	10.3	0	0.0	0	0.0	49.6	58.8	0 0	0	0	0 0	1	1	2	4 5	5 2	1	1	0	0 0	0	0	0	0	0 (0 0	0	0	0 (J
2300	11	0	8	0	1	0	0	0	0	0	1	0	0	0	2.6	0	1.3	0	0.0	48.3	55	0 0	0	0	0 0	0	1	2	2	4 1	0	0	0	0 0	0	0	0	0	0 (0 0	0	0	0 (J
07-19	1376	117	1004	24	180	9	16	1	4	6	15	0	0	101	7.3	26	1.9	9	0.7	49.1	56	0 0	1	1	2 9	21	82	268	413 32	26 153	59	22	11	5 3	1	0	0	0	0 (0 0	0	0	0 (٥
06-22	1527	123	1118	27	197	11	18	1	4	8	18	0	0	118	7.7	30	1.9	10	0.7	49.4	56.5	0 0	1	1	2 9	23	88	285	450 36	68 180	69	25	12	5 3	1	1	0	0	0 (0 0	0	0	0 (0
06-00	1554	123	1140	27	201	11	18	1	4	9	20	0	0	120	7.7	30	1.9	10	0.7	49.4	56.5	0 0	1	1	2 10	24	90	290	456 37	77 183	71	26	12	5 3	1	1	0	0	0 (0 0	0	0	0 /	5
00-00	1582	123	1156	27	206	12	20	2	5	10	23	0	0	122	7.7	30	1.9	10	0.7	49.4	56.5	0 0	1	1	2 10	24	92	294	463 38	84 187	73	27	13	5 3	1	1	0	0	0 (0 0	0	0	0 /	٥

		Virtual We	eek (1)																			Virtual W	eek (1)																				
Time	Total						Classifi	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spee	d Bins (mph)										
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5	- 10 -	15 -	20 -	25 - 20 2	_ 35 -	40 -	45 - 5	0 - 5!	5 - 60 -	65 -	70 - 75	5 - 80	- 85	- 90 -	95 -	100 - 1	105 - 11	10 - 11	5 - 12/	0 - 125 -	130 - 135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 1	0 15	20	25	30 - 3	40	45	50	55 6	0 65	70	75 8	0 85	5 90	95	100	105 1	110 1	15 12	20 12	25 130	135 140
Mon	1476	71	1065	28	241	13	18	0	4	13	23	0	0	80	5.4	15	1.0	4	0.3	48.5	55.6	0 (0	1	3	11 32	84	328	418 3	57 1	52 56	13	7	3 0) 1	0	0	0	0	0 (0 () 0	0 0
Tue	1467	83	1027	32	221	14	31	0	7	13	39	0	0	99	6.7	10	0.7	1	0.1	48.7	55.6	0 0) 1	2	4	9 25	104	287	440 3	45 1	51 73	19	6 (0 1	0	0	0	0	0	0 (0 () 0	0 0
Wed	1670	104	1183	34	245	9	33	3	8	14	37	0	0	117	7.0	27	1.6	6	0.4	48.9	56	0 1	9	0	1	17 25	116	295	512 3	81 1	96 75	25	11 2	2 2	1	1	0	0	0	0 (0 () 0	0 0
Thu	1695	117	1214	30	240	14	34	1	3	18	24	0	0	114	6.7	24	1.4	6	0.4	49	56.1	0 1	0	0	6	16 31	103	299	497	26 2	02 68	30	10	3 1	1	1	0	0	0	0 (0 () 0	0 0
Fri	1758	124	1309	25	230	19	13	3	6	8	20	0	1	154	8.8	40	2.3	13	0.7	50	57.2	0 (0	2	1	7 22	98	301	487 4	62 2	24 91	35	15	4 5	1	2	0	1	0	0 (0 () 0	0 0
Sat	1659	241	1233	18	136	9	7	1	3	2	9	0	0	191	11.5	61	3.7	22	1.3	50.4	58	0 (0	0	1	8 23	71	305	476 3	95 1	39 96	43	30 1	3 8	0	1	0	0	0	0 (0 () 0	0 0
Sun	1352	118	1060	25	126	4	2	3	1	3	10	0	0	102	7.5	35	2.6	21	1.6	50	56.7	0 (0	0	1	4 13	71	245	408 3	22 1	36 49	22	10 1	0 5	6	0	0	0	0	0 (0 () 0	0 0
5 Day Ave.	1613	100	1160	30	235	14	26	1	6	13	29	0	0	113	7.0	23	1.4	6	0.4	49.0	56.1	0 () 2	1	3	12 27	101	302	471 3	94 1	37 73	24	10	2 2	1	1	0	0	0	0 (0 (0	0 0
7 Day Ave.	1582	123	1156	27	206	12	20	2	5	10	23	0	0	122	7.7	30	1.9	10	0.7	49.4	56.5	0 () 1	1	2	10 24	92	294	463 3	84 1	37 73	27	13 !	5 3	1	1	0	0	0	0 (0 (0	0 0
	11077	858	8091	192	1439	82	138	11	32	71	162	0	1	857	7.7	212	1.9	73	0.7	49.4	56.5	0 2	10	5	17	72 171	647	2060	3238 2	688 13	10 508	187	89 3	5 22	2 10	5	0	1	0	0 (0 (0	0 0






		7																		14133 / 1	nverary	7										
		B840 ap North Sc)m west o	of A819/ I	B840 jund	ction												Automa		ne 2021 c Count				0m we	est of A	A819/ E	3840 jur	nction			
	,	Virtual Day	y (7)																			Virtua	al Day	(7)								
Г	Total						Classif	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp											
Ш		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	0 5	5 -	10 -	15 -	20 -	25 -	20 25	35 -	40 -	45 -	50
Ш		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5	10	15	20	25	30	30 - 35	40	45	50	55
110	1	0	1	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	24.8	-	0	0	0	0	1	0	0	0	0	0	0

Time Total	1	2			Classific		ISL1	JL 170	SL2	SL2%	Mean	Vpp										Speed	l Bins (m	IDII)																	
			3	4	5	6	7	8	9	10	l 11 l	12	60	60	68	68	75	75		85	1 1	5 - 10 -	15 -	20 - 25	- 1	35 -	40 -	45 - 50) - 55 -	60-16	65 - T70) - 75	- 80 -	85 -	90 - 95	- 1100	- 105 - 11	0 - 115 -	120 - 1	125 - 1	30 - 135 -
0000 1	MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT				ACPO		DfT				10 15		25 30	130 - 3	40	45	50 5!		65	70 75	5 80	85	90	95 10						135 140
0000	0	1	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	24.8	-	0	0 0	0	1 0	0	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
0100 0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	31.8	-	0	0 0	0	0 0	0	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
0200 0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.5	-	0	0 0	0	0 0	0	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
0300 1	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	19.6	-	0	0 0	0	0 0	0	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
0400 1	0	1	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	22.9	-	0	0 0	0	0 0	0	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
0500 2	0	1	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	25.2	-	0	0 0	0	1 1	0	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
0600 3	0	2	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	26.2	-	0	0 0	0	1 1	0	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
0700 8	0	7	0	1	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	25.6	-	0	0 0	0	3 4	1	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
0800 18	0	15	0	2	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	24.5	29.2	0	0 0	2	8 6	2	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
0900 29	1	25	0	2	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.3	26.8	0	0 1	4	14 8	2	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
1000 35	3	28	0	4	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.4	27.6	0	0 1	5	17 10	0 1	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
1100 35	2	28	0	2	0	1	0	0	0	1	0	0	0	0.0	0	0.0	0	0.0	23.6	27.6	0	0 0	5	17 13	2 1	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
1200 28	1	23	0	3	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.9	27.8	0	0 0	3	12 1	1 1	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
1300 23	2	17	1	4	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.2	28	0	1 0	4	11 6	2	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
1400 26	1	21	0	3	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.9	28.1	0	0 0	5	11 8	2	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
1500 26	1	20	0	3	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.8	27.8	0	0 0	4	13 8	1	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
1600 27	1	24	0	1	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.5	27.1	0	0 1	3	14 8	1	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
1700 22	1	18	0	3	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.9	28.6	0	0 0	3	11 7	1	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
1800 23	1	20	0	2	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.2	27.9	0	0 2	4	9 7	1	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
1900 12	0	10	0	1	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	24.6	28.3	0	0 0	1	4 5	1	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
2000 10	0	9	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	23.5	27.2	0	0 0	1	5 3	0	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
2100 10	1	8	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	24.3	-	0	0 0	2	3 4	1	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
2200 4	0	3	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	25.8	-	0	0 0	0	1 2	0	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
2300 2	0	2	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	22.8	-	0	0 0	0	1 1	0	0	0	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
07-19 300	15	245	3	31	2	2	1	0	0	2	0	0	0	0.0	0	0.0	0	0.0	23.7	27.9	0	2 6	41	138 9	5 16	0	1	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
06-22 334	16	275	4	33	2	2	1	0	1	2	0	0	0	0.0	0	0.0	0	0.0	23.7	27.9	0	2 7	45	152 10	9 18	0	1	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
06-00 340	16	280	4	33	2	2	1	0	1	2	0	0	0	0.0	0	0.0	0	0.0	23.8	27.9	0	2 7	46	154 11	1 18	0	1	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0
00-00 344	16	283	4	34	2	2	1	0	1	2	0	0	0	0.0	0	0.0	0	0.0	23.8	27.9	0	2 7	46	156 11	3 18	0	1	0 0	0	0	0 0	0 0	0	0	0 0	0	0	0 0	0	0	0 0


00 00			200			_			-				_	,	0.0				0.0									-		0 0		_			Ů	-						قعله	0 0
		Virtual W	eek (1)																			Virtual W	/eek (1)																				
Time	Total						Classifi	cation]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp											Spe	ed Bins (mph)									
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5	- 10-	- 15 -	20 -	25 -	ا م	85 - 4	10 - 4	5 - 50	- 55 -	60 -	65 -	70 - 75	- 80 -	85 - 9	0 - 95	- 100	- 105 -	110 -	115 - 12	0 - 125	5 - 130 - 135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 1	0 15	20	25	30	30 - 35	40	45 5	50 55	60	65	70	75 80	85	90	95 10	0 105	5 110	115	120 12	25 130	0 135 140
Mon	292	20	243	3	19	2	0	2	2	0	1	0	0	0	0.0	0	0.0	0	0.0	24.2	28.7	0	1 5	39	127	101	19	0	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0	0 (0	0 0
Tue	337	14	268	5	43	3	3	0	0	1	0	0	0	0	0.0	0	0.0	0	0.0	23.8	28	0	4 6	47	140	121	19	0	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0	0 (0 (0 0
Wed	436	20	339	8	61	2	2	0	0	1	3	0	0	0	0.0	0	0.0	0	0.0	23.3	27.8	0	4 18	63	187	146	16	0	2	0 0	0	0	0	0 0	0	0	0 0	0	0	0	0 (0 (0 0
Thu	341	17	278	5	31	3	3	1	0	0	3	0	0	0	0.0	0	0.0	0	0.0	23.5	27.5	1	1 5	46	170	104	12	2	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0	0 (0 ر	0 0
Fri	351	10	295	5	36	1	0	1	0	2	1	0	0	0	0.0	0	0.0	0	0.0	23.8	27.7	0	1 6	45	163	120	16	0	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0	0 () 0	0 0
Sat	343	15	298	3	25	1	0	0	0	0	1	0	0	0	0.0	0	0.0	0	0.0	24.4	28.7	1	1 2	35	156	114	32	1	1	0 0	0	0	0	0 0	0	0	0 0	0	0	0	0 () 0	0 0
Sun	306	15	263	0	22	0	3	0	1	0	2	0	0	0	0.0	0	0.0	0	0.0	23.4	27.3	0 -	4 5	48	148	84	15	0	2	0 0	0	0	0	0 0	0	0	0 0	0	0	0	0 () 0	0 0
5 Day Ave.	351	16	285	5	38	2	2	1	0	1	2	0	0	0	0.0	0	0.0	0	0.0	23.7	27.9	0	2 8	48	157	118	16	0	0	0 0	0	0	0	0 0	0	0	0 0	0	0	0	0 (0	0 0
7 Day Ave.	344	16	283	4	34	2	2	1	0	1	2	0	0	0	0.0	0	0.0	0	0.0	23.8	27.9	0	2 7	46	156	113	18	0	1	0 0	0	0	0	0 0	0	0	0 0	0	0	0	0 (0	0 0
	2406	111	1984	29	237	12	11	4	3	4	11	0	0	0	0.0	0	0.0	0	0.0	23.8	27.9	2 1	6 47	323	1091	790	129	3	5	0 0	0	0	0	0 0	0	0	0 0	0	0	0	0 (0	0 0





Direction		Last We	531																Automic	ilic iraiii	C Couri	L LCIST VI	/C3l																	,	Automic	ilic irai	iiic Courit
		Virtual Da	ay (7)																			Virtual E	Day (7)																				
Time	Total						Classit	ication]PSL	1PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Sr	peed Bins	(mph)										
		1	2	3	4	1 5	6	1 7	1 8	9	10	1 11	12	60	60	68	68	75	75		85	1 1	5 - I 10	- 15 -	20 -	25 -	35 -	40 -	45 -	50 - 59	5 - 60	- 65 -	70 - 1	75 - 8	80 - 85	- 90 -	95.	100 - 1	105 - 111	0. 1115.	120-	125 - 1	130 - 135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5		BD	DRT			ACPO			DfT				10 15			30 30 -	35 40		50		0 65		75		85 90			105 1					135 140
				371	102		14	ANIS	AR14	ANIS	AKIO							DII					10 13	20	23	30	40	43	30	33 (70	73	00 (00 70	73	100	103	110 11	13 120		130	133 140
0000	14	0	9	0	2	0	0	0	0	1	0	0	0	1	4.2	0	1.0	0	1.0	46.3	54.3	0	0 0	0	0	0 1	2	2	3	3	1 0	0	0	0	0 0	0	0	0	0 (0 0	0	0	0 0
0100	9	0	4	0	1	0	0	0	0	1	2	0	0	1	6.5	0	1.6	0	0.0	46.7	-	1	0 0		0	0 0) 1	1	3	1	1 0	0	0	0	0 0	0	0	0	0 (0 0	Ů	-	0 0
0200	7	0	3	0	2	0	0	0	0	1	1	0	0	0	5.9	0	5.9	0	0.0	47.7	-	-	0 0	0	0	0 1	1	1	1	2	1 0	0	0	0	0 0	0	0	0	0 (0 0	0	0	0 0
0300	9	0	4	0	2	0	0	0	1	0	1	0	0	0	1.6	0	0.0	0	0.0	46.7	-	0	0 0	0	0	0 1	1	2	3	2	1 0	0	0	0	0 0	0	0	0	0 (0 0	0	0	0 0
0400	18	0	11	1	3	0	0	0	0	2	1	0	0	1	6.3	0	0.8	0	0.0	47.9	56.2	0	0 0	0	0	0 1	2	3	5	4	2 1	0	0	0	0 0	0	0	0	0 (0 0	0	0	0 0
0500	36	0	19	1	9	1	0	0	1	2	3	0	0	3	9.5	1	3.6	0	0.4	49.6	57.3	0	0 0	0	1	1 1	1	7	8	9	5 1	1	1	0	0 0	0	0	0	0 (0 0	0	0	0 0
0600	60	0	40	1	11	0	0	0	1	2	4	0	0	5	9.1	1	1.7	0	0.2	48.1	56.3	0	0 0	0	1	1 1	7	12	14	12	6 4	1	1	0	0 0	0	0	0	0 (0 0	0	0	0 0
0700	124	1	87	3	24	1	1	0	1	1	4	0	0	7	5.5	2	1.4	0	0.1	47	54.9	0	0 0	0	2	1 7	15	22	32	27 1	1 4	2	1	0	0 0	0	0	0	0 (0 0	0	0	0 0
0800	178	2	138	3	28	2	1	1	1	1	2	0	0	4	2.2	1	0.3	0	0.0	45.5	53	0	0 0	0	1	3 9	26	42	52	28 1	2 3	1	0	0	0 0	0	0	0	0 (0 0	0	0	0 0
0900	238	11	180	4	34	2	1	0	1	2	3	0	0	3	1.3	1	0.3	0	0.1	43.6	50.4	0	0 0	0	2	4 16	6 47	77	54	28	7 2	0	1	0	0 0	0	0	0	0 (0 0	0	0	0 0
1000	336	15	262	7	42	3	1	1	1	2	3	0	0	2	0.6	0	0.1	0	0.0	41.7	48.1	0	0 0	0	2	8 38	8 87	104	67	22	7 1	1	0	0	0 0	0	0	0	0 /	0 0	0	0	0 0
1100	333	14	257	10	43	1	1	1	1	2	2	0	0	5	1.4	1	0.4	1	0.2	41.5	47.8	0	0 0	0	2	9 38	8 87	107	60	21	4 3	1	0	0	0 0	0	0	0	0 /	0 0	0	0	0 0
1200	346	18	264	12	43	2	1	1	1	1	3	0	0	6	1.7	2	0.5	1	0.2	42	47.9	0	0 0	0	1	7 35	5 91	116	63	21	6 4	0	1	1	0 0	0	0	0	0 /	0 0	0	0	0 0
1300	321	16	248	8	39	3	1	1	1	2	3	0	0	6	1.8	1	0.3	0	0.1	42.1	48.5	0	0 0	0	1	7 33	3 85	99	62	23	6 4	1	0	0	0 0	0	0	0	0 (0 0	0	0	0 0
1400	328	19	251	8	41	2	1	0	1	1	3	0	0	2	0.7	0	0.1	0	0.0	42.2	48.5	0	0 0	0	1	4 31	1 86	104	66	25	7 2	0	0	0	0 0	0	0	0	0 (0 0	0	0	0 0
1500	330	17	259	4	39	1	2	1	1	1	4	0	0	5	1.5	1	0.2	0	0.1	42	48.7	0	0 0	0	1	8 38	8 87	96	60	26	B 4	1	0	0	0 0	0	0	0	0 (0 0	0	0	0 0
1600	289	14	231	4	32	1	1	0	0	1	3	0	0	5	1.8	1	0.3	0	0.1	43.1	49.9	0	0 0	0	1	6 26	6 60	94	60	26 1	1 3	1	0	0	0 0	0	0	0	0 (0 0	0	0	0 0
1700	254	8	211	3	26	1	1	1	0	1	2	0	0	6	2.3	1	0.5	0	0.1	43.8	51.4	0	0 0	0	2	8 24	4 43	67	59	33 1	2 4	1	1	0	0 0	0	0	0	0 /	0 0	0	0	0 0
1800	199	4	167	3	19	1	0	0	0	1	3	0	0	6	3.2	1	0.6	0	0.1	45.6	53.1	0	0 0	0	1	3 9	27	55	54	29 1	3 3	2	1	0	0 0	0	0	0	0 (0 0	0	0	0 0
1900	145	5	120	2	13	1	0	0	1	1	2	0	0	6	4.4	1	0.7	0	0.0	46	53.9	0	0 0	0	1	3 8	19	38	34	26 1	0 4	2	1	0	0 0	0	0	0	0 /	0 0	0	0	0 0
2000	115	3	97	1	10	2	0	0	0	0	1	0	0	5	4.3	1	0.9	0	0.2	45.9	54.5	0	0 0	0	1	1 7	16	30	28	17 1	1 3	1	0	0	0 0	0	0	0	0 0	0 0	0	0	0 0
2100	86	0	72	2	7	0	0	0	1	1	2	0	0	4	4.1	0	0.5	0	0.3	45.6	53.7	0	0 0	0	1	2 6	11	18	23	14	7 3	1	0	0	0 0	0	0	0	0 0	0 0	0	0	0 0
2200	44	0	35	1	5	0	0	0	0	1	1	0	0	3	6.5	1	1.9	0	0.3	46.2	54.1	0	0 0	0	0	0 2	10	9	9	8	3 1	1	0	0	0 0	0	0	0	0 /	0 0	0	0	0 0
2300	26	0	19	0	5	0	0	0	0	1	0	0	0	1	4.9	0	1.1	0	0.0	44.8	53.9	0	0 0	0	0	1 2	6	5	5	4	2 1	0	0	0	0 0	0	0	0	0 (0 0	0	0	0 0
07-19	3276	137	2555	70	410	20	14	6	10	16	36	0	1	57	1.7	12	0.4	3	0.1	42.9	49.8	0	0 0	2	15	68 30	3 741	983	690	309 1	07 37	7 12	4	2	1 0	0	0	0	0	0 0	0	0	0 0
06-22	3682	145	2884	76	451	24	15	7	13	21	44	0	1	77	2.1	15	0.4	4	0.1	43.3	50.4	0	0 0	2	18	74 32	6 795	1080	789	379 1	40 50	17	6	2	1 0	0	0	0	0	0 0	0	0	0 0
06-00	3752	146	2939	78	461	24	15	7	13	24	45	1	1	81	2.2	17	0.4	4	0.1	43.3	50.5	0	0 0	2	19	75 33	0 811	1095	804	390 1	45 52	2 18	6	2	1 0	0	0	0	0	0 0	0	0	0 0
	0015			0.4	101								_					-	-		50.7			_		77 00	_		007	410 1	_	- 04	-			_							

00-00	3845	146	2990	81	481	25	16	7	14	30	54	1	1	88	2.3	19	0.5	5	0.1	43.4	50.7	0	0 0	2	20	77 3	834 818	1111	827	412	156 5	5 21	7	3	1	0 0	0	0	0	0 (0 0	0	0	0
		Virtual W	leek (1)																			Virtual \	Week (1)																					
Time	Total						Classifi	cation]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										S	peed Bin	s (mph))										
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	0 5 !	5 - 10 -	15 -	20 - 2		35 -	40 -	45 -	50 -	55 - 60	0 - 65 -	70 -	75 -	80 -	85 - 90	- 95 -				15 - 120 -			
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0-5	10 15	20	25	30	40	45	50	55	60 6	5 70	75	80	85	90 95	100	105	110 1	115 12	20 125	130	135	140
Mon	3657	87	2762	98	543	25	18	5	22	25	71	1	0	79	2.2	17	0.5	1	0.0	43.7	51.2	1	0 0	3	31	72 3	715	1022	840	412	182 4	7 22	9	1	0	0 0	0	0	0	0 (0 0	0	0	0
Tue	3349	95	2506	67	519	21	13	5	16	41	66	0	0	65	1.9	10	0.3	3	0.1	43.4	51	1	0 0	0	24	45 3	329 684	987	681	384	149 4	7 11	4	1	2	0 0	0	0	0	0 (0 0	0	0	0
Wed	3673	148	2674	73	573	24	23	10	18	45	81	1	3	78	2.1	13	0.4	0	0.0	42.9	50.5	1	0 0	5	36	93 3	857 821	1024	731	396	131 5	4 16	8	0	0	0 0	0	0	0	0 (0 0	0	0	0
Thu	3636	113	2730	92	515	32	27	6	17	42	59	1	2	71	2.0	11	0.3	2	0.1	43.2	50.8	0	0 0	1	18	83 3	815 809	1063	728	396	152 4	7 20	2	1	1	0 0	0	0	0	0 (0 0	0	0	0
Fri	4530	143	3573	86	558	29	13	12	16	40	59	1	0	103	2.3	24	0.5	8	0.2	43.3	50.3	0	0 0	3	15	70 4	113 1022	1315	974	431	184 6	1 25	9	3	3	1 1	0	0	0	0 (0 0	0	0	0
Sat	4463	281	3708	69	332	24	11	6	5	11	15	1	0	121	2.7	39	0.9	10	0.2	43.7	50.3	0	1 0	0	10	94 3	806 915	1374	1051	436	155 6	3 33	15	7	1	1 1	0	0	0	0 (0 0	0	0	0
Sun	3609	153	2979	80	325	19	4	7	7	9	25	0	1	96	2.7	17	0.5	8	0.2	43.6	51.1	0	0 0	1	8	81 3	317 762	992	787	427	138 6	6 18	4	5	3	0 0	0	0	0	0 (0 0	0	0	0
5 Day Ave.	3769	117	2849	83	542	26	19	8	18	39	67	1	1	79	2.1	15	0.4	3	0.1	43.3	50.8	1	0 0	2	25	73 3	843 810	1082	791	404	160 5	1 19	6	1	1	0 0	0	0	0	0 (0 0	0	0	0
7 Day Ave.	3845	146	2990	81	481	25	16	7	14	30	54	1	1	88	2.3	19	0.5	5	0.1	43.4	50.7	0	0 0	2	20	77 3	334 818	1111	827	412	156 5	5 21	7	3	1	0 0	0	0	0	0 (0 0	0	0	0
	26917	1020	20932	565	3365	174	109	51	101	213	376	5	6	613	2.3	131	0.5	32	0.1	43.4	50.7	3	1 0	13	142 5	38 2	337 5728	7777	5792	2882	1091 38	85 145	51	18	10	2 2	0	0	0	0 (0 0	0	0	0






June 202	1 A85 approx 150m west of the A85/ A819 junction
Automatic Traffic Coun	t North South

		Virtual Da	ay (7)																			Virtual Day	y (7)																					
Time	Total						Classif	fication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spee	ed Bins (n	nph)											
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5 -	10 -	15 -	20 - 25 -	20 25	35 -	40 - 4	5 - 50	0 - 55 -	60 -	65 - 7	0 - 7	5 - 80 -	85 -	90 -	95 - 1	100 - 10	05 - 110) - 115 - ·	120 - 1	25 - 13	30 - 135	5 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 10	15	20	25 30	30 - 35	40	45 5	50 5	5 60	65	70 7	75 8	85	90	95	100	105 1°	110 115	5 120	125 1	130 1/	35 14	10
0000	13	0	8	1	2	0	0	0	0	1	0	0	0	2	11.8	0	3.2	0	1.1	49.9	58.3	0 0	0	0	0 0	0	1	2	3	3 2	1	0	0 (0 0	0	0	0	0	0 0	0	0	0 /	0 0	ر
0100	10	0	5	0	1	0	0	0	0	1	2	0	0	1	9.9	0	1.4	0	0.0	49.4	56.5	0 0	0	0	0 0	0	1	1	3	3 1	1	0	0 (0 0	0	0	0	0	0 0	0	0	0 /	0 0	<u> </u>
0200	8	0	4	0	2	0	1	0	0	1	2	0	0	1	8.5	0	3.4	0	0.0	49	-	0 0	0	0	0 0	0	1	2	1	1 2	0	0	0 (0 0	0	0	0	0	0 0	0	0	0	0 0)
0300	10	0	5	0	2	0	0	0	1	1	1	0	0	1	10.3	0	2.9	0	1.5	49.3	-	0 0	0	0	0 0	0	1	2	2	2 1	1	0	0 (0 0	0	0	0	0	0 0	0	0	0 /	0 0)
0400	18	0	11	1	3	0	0	0	0	2	2	0	0	2	11.1	0	2.4	0	0.0	50.1	57.9	0 0	0	0	0 0	0	2	2	6	4 2	1	0	0 (0 0	0	0	0	0	0 0	0	0	0 /	0 0)
0500	39	0	22	0	10	1	1	0	1	2	2	0	0	6	15.7	2	4.4	0	1.1	52.5	60.3	0 0	0	0	0 0	0	1	4	10 1	11 7	4	1	1 (0 0	0	0	0	0	0 0	0	0	0 (0 0)
0600	70	1	46	1	15	0	1	0	1	3	3	0	0	7	9.6	1	1.2	0	0.2	50.2	58.3	0 0	0	0	0 0	1	6	11 1	16 1	15 13	5	1	0 (0 0	0	0	0	0	0 0	0	0	0 (0 0	J
0700	140	1	99	2	28	2	2	0	1	2	3	0	0	13	9.0	2	1.2	0	0.3	50	57.1	0 0	0	0	0 0	2	9	22 3	35 3	39 19	8	3	1 (0 0	0	0	0	0	0 0	0	0	0 (0 0	J
0800	199	2	154	4	31	1	2	0	1	2	2	0	0	8	4.2	1	0.6	0	0.1	48.7	55.1	0 0	0	0	0 0	4	14	36 6	62 5	52 22	6	2	0 (0 0	0	0	0	0	0 0	0	0	0 (0 0	J
0900	277	11	211	5	39	2	2	1	2	2	3	0	0	6	2.3	2	0.7	1	0.2	45.9	52.3	0 0	0	1	1 2	10	32	74	90 4	16 15	4	1	1 (0 0	0	0	0	0	0 0	0	0	0 (0 0)
1000	389	16	303	8	49	3	3	1	1	2	3	0	0	3	0.9	1	0.1	0	0.0	44.1	50.3	0 0	0	1	2 5	24	64	117 1	113 4	15 13	2	1	1 (0 0	0	0	0	0	0 0	0	0	0 (0 0	j
1100	388	17	302	9	53	1	1	0	1	2	2	0	0	8	2.1	3	0.7	1	0.4	44.5	50.4	0 0	0	1	1 5	21	61	122 1	110 4	15 13	4	1	1	1 0	0	0	0	0	0 0	0	0	0 (0 0	j
1200	397	17	308	10	53	2	1	1	1	1	3	0	0	9	2.4	3	0.8	1	0.2	45.3	51	0 0	0	0	0 4	17	52	120 1	28 5	16	5	2	1 (0 0	0	0	0	0	0 0	0	0	0 (0 0	j
1300	348	15	271	9	45	2	2	1	1	2	2	0	0	9	2.5	2	0.6	1	0.2	45.3	51.7	0 0	0	0	1 5	12	47	106 1	100 5	0 16	4	3	1	1 0	0	0	0	0	0 0	0	0	0 (0 0	j
1400	363	17	280	6	51	2	1	1	1	1	2	0	0	9	2.4	1	0.3	0	0.0	45.2	51.8	0 0	0	0	1 4	19	49	107 1	105 5	18	6	3	0 (0 0	0	0	0	0	0 0	0	0	0 (0 0)
1500	374	20	297	5	45	1	2	1	1	1	1	0	0	11	2.8	4	1.0	1	0.4	45.8	52.6	0 0	0	0	0 2	16	53	109 1	106 5	55 23	6	2	1	1 0	0	0	0	0	0 0	0	0	0 (0 0)
1600	330	17	267	4	36	2	1	0	1	1	1	0	0	14	4.3	4	1.2	1	0.4	46.9	53.7	0 0	0	1	0 2	12	37	81 9	96 6	55 23	8	3	1	1 1	0	0	0	0	0 0	0	0	0 (0 0	J
1700	295	9	244	4	32	1	2	0	1	1	1	0	0	16	5.4	4	1.3	1	0.2	47.5	54.6	0 0	0	0	1 2	10	31	66	79 6	55 26	10	3	1	1 0	0	0	0	0	0 0	0	0	0 (0 0	j
1800	224	5	189	2	22	1	2	0	0	1	2	0	0	15	6.6	3	1.4	0	0.2	49.1	56.3	0 0	0	1	0 1	3	13	41 6	69 5	55 26	9	4	2 (0 0	0	0	0	0	0 0	0	0	0 (0 0	j
1900	153	4	128	2	14	1	1	0	1	1	1	0	0	13	8.6	4	2.3	1	0.9	50	57.2	0 0	0	0	0 1	2	10	22	43 3	38 22	8	2	2	1 0	0	0	0	0	0 0	0	0	0 (0 0	J
2000	120	2	101	1	12	1	0	0	0	0	1	0	0	10	8.4	2	1.4	1	0.7	49.8	57.2	0 0	0	0	0 1	3	7	19 3	35 2	28 17	5	3	1 (0 0	1	0	0	0	0 0	0	0	0 (0 0	J
2100	82	1	69	2	8	0	0	0	0	1	1	0	0	8	9.9	1	1.6	0	0.5	49.8	58.3	0 0	0	0	0 1	2	7	12 1	18 2	22 11	6	2	1 (0 0	0	0	0	0	0 0	0	0	0 (0 0	J
2200	46	0	36	1	6	0	0	0	0	2	0	0	0	4	8.1	2	3.4	0	0.6	49.2	57.1	0 0	0	0	0 0	2	4	9 1	10	9 8	2	1	1 (0 0	0	0	0	0	0 0	0	0	0 (0 0	j
2300	26	0	18	0	6	0	0	0	0	1	1	0	0	3	9.8	1	2.7	0	0.0	47.8	56.8	0 0	0	0	0 0	1	3	5	5	6 2	1	1	0 (0 0	0	0	0	0	0 0	0	0	0 (0 0	j
07-19	3726	145	2924	68	485	21	23	6	12	17	26	0	0	121	3.3	29	0.8	8	0.2	46.1	52.8	0 0	2	6	8 32	151	461	1001 10	093 6	20 231	73	29	12	5 1	1	1	0	0	0 0	0	0	0 (0 0	j
06-22	4151	152	3268	74	535	23	26	6	14	22	32	0	0	159	3.8	36	0.9	11	0.3	46.5	53.5	0 0	2	6	9 34	159	491	1066 12	206 7.	24 295	96	37	15	6 2	2	1	0	0	0 0	0	0	0	0 0	,
06-00	4223	152	3322	75	547	24	26	6	14	24	33	0	0	165	3.9	39	0.9	11	0.3	46.5	53.5	0 0	2	6	9 35	162	499	1080 12	222 7	38 305	99	39	16	7 2	2	1	0	0	0 0	0	0	0	0 0	,
00-00	4322	152	3377	78	567	25	27	7	15	31	42	1	0	178	4.1	42	1.0	12	0.3	46.6	53.7	0 0	2	6	9 35	163	507	1092 12	247 7	62 321	107	42	18	7 2	2	1	0	0	0 0	0	0	0 (0 0	,

				-																																					4		
	<u> </u>	Virtual We	eek (1)		<u> </u>								<u> </u>			<u> </u>				<u> </u>	·	Virtual V	Veek (1)													·							
Time	Total						Classifi	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Speed	d Bins (r	nph)										
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	1 1 5	- 10-	15 -	20 - 1	25 -	35 -	40 -	45 - 5	0 - 55	- 60 - 1		70 - 75	- 80	- 85 -	90 -	95 -	100 - 105	5 - 110	- 115 -	120 - 1	125 - 130	- 135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5	0 15	20	25	30 30 -	40	45	50	55 6	0 65	70	75 80	0 85	90	95		105 110	0 115	120	125	130 135	140
Mon	4205	104	3180	97	657	27	22	3	26	32	57	0	0	150	3.6	39	0.9	9	0.2	46.3	53.5	0	0 2	4	6	40 196	518	1050	1183	51 30)5 93	28	20 2	1	5	1	0	0 0	0	0	0	0 0	0
Tue	4011	101	3017	62	656	23	37	4	18	38	52	2	1	169	4.2	35	0.9	8	0.2	46.7	54.1	0	0 2	4	3	26 173	478	975	1140	10 3	31 95	51	15 7	1	0	0	0	0 0	0	0	0	0 0	0
Wed	4249	156	3139	67	683	30	44	11	18	45	56	0	0	179	4.2	42	1.0	10	0.2	46.5	53.6	0	0 3	11	11	36 148	505	1092	1230 7	19 3	5 110	46	13 5	2	2	1	0	0 0	0	0	0	0 0	0
Thu	4063	113	3076	88	585	29	54	6	15	42	53	1	1	169	4.2	30	0.7	5	0.1	46.5	53.9	0	0 2	4	14	34 158	464	1063	1168 6	67 32	20 113	37	14 2	! 1	2	0	0	0 0	0	0	0	0 0	0
Fri	4986	168	3928	80	642	30	23	12	17	37	48	1	0	187	3.8	38	0.8	12	0.2	46.5	53.5	0	0 2	9	6	56 178	570	1303	1439 8	364 3	2 124	33	18 8	4	0	0	0	0 0	0	0	0	0 0	0
Sat	4795	254	4060	65	364	20	1	4	8	11	7	0	1	215	4.5	68	1.4	22	0.5	47	53.4	0	0 2	7	13	27 150	475	1251	1445	07 30	3 115	49	29 12	2 3	3	2	1	0 1	0	0	0	0 0	0
Sun	3945	167	3238	84	382	16	11	6	6	13	22	0	0	176	4.5	41	1.0	16	0.4	46.7	54	0	0 2	5	9	29 138	536	912	1121 7	19 29	97	47	16 12	2 2	2	0	0	0 0	0	0	0	0 0	0
5 Day Ave.	4303	128	3268	79	645	28	36	7	19	39	53	1	0	171	4.0	37	0.9	9	0.2	46.5	53.7	0	0 2	6	8	38 171	507	1097	1232	42 32	9 107	39	16 5	2	2	0	0	0 0	0	0	0	0 0	0
7 Day Ave.	4322	152	3377	78	567	25	27	7	15	31	42	1	0	178	4.1	42	1.0	12	0.3	46.6	53.7	0	0 2	6	9	35 163	507	1092	1247	62 32	107	42	18 7	2	2	1	0	0 0	0	0	0	0 0	0
	30254	1063	23638	543	3969	175	192	46	108	218	295	4	3	1245	4.1	293	1.0	82	0.3	46.6	53.7	0	0 15	44	62	248 114	1 3546	7646	8726 5	337 22	44 747	291 1	125 48	8 14	14	4	1	0 1	1 0	0	0	0 0	0






June 2021	A815 approx 100m north of the A815/ A886 junction
Automatic Traffic Count	North South

		Virtual Da	ay (7)																			Virtual Da	ay (7)																				
Time	Total						Classif	cation]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp											ed Bins	(mph)	1									
		1	2	3	4	5	6	7	8	9	10	11	12	40	40	46	46	55	55		85	IO EI	- 10 -			25 - 20	35 -	40 -	45 -	50 - 55	- 60 -	65 -	70 -	75 - 8	0 - 85	- 90 -	95 -					25 - 130 -	
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			10 10) 15	20	25	30	40	45	50	55 60	65	70	75	80 8	35 90	95	100	105 1	110 11	5 120	125 1	130 135	140
0000	9	0	7	0	1	0	0	0	0	0	0	0	0	4	48.3	2	25.0	0	3.3	41.6	-	0 0	0	0	0	0 1	3	2	1	1 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
0100	3	0	2	0	0	0	0	0	0	1	0	0	0	2	60.9	1	34.8	0	13.0	42.7	-	0 0	0	0	0	0 1	1	1	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
0200	5	0	3	0	1	0	0	0	0	1	0	0	0	4	73.5	2	41.2	0	2.9	44	-	0 0	0	0	0	0 0	1	1	2	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
0300	6	0	3	0	1	0	0	0	0	0	0	0	0	3	57.5	1	17.5	0	2.5	41.3	-	0 0	0	0	0	0 1	2	2	1	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
0400	9	0	5	0	2	0	0	0	0	1	1	0	0	7	71.2	3	31.8	0	3.0	43.4	-	0 0	0	0	0	0 1	2	3	3	1 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
0500	22	0	15	1	4	0	0	0	0	0	2	0	0	12	54.3	5	23.5	1	5.9	42.2	50.1	0 0	0	0	0	0 2	8	6	3	2 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
0600	54	0	32	3	15	1	0	0	0	1	2	0	0	27	49.6	10	17.9	1	1.8	40.7	47	0 0	0	0	0	1 6	20	15	9	3 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
0700	99	0	70	3	21	1	1	0	0	1	1	0	0	39	39.2	10	10.0	0	0.4	39.1	44.3	0 0	0	0	0	2 2	39	26	10	2 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
0800	135	1	97	4	24	1	1	1	1	1	4	0	0	49	36.2	12	8.6	1	0.7	38.9	44	0 0	0	0	0	2 2	3 60	34	11	3 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
0900	155	2	118	3	23	2	2	0	0	1	3	0	0	49	31.6	10	6.7	1	0.5	38.1	42.9	0 0	0	0	1	5 3	4 67	35	12	2 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
1000	181	6	139	4	23	3	2	0	2	1	2	0	0	51	28.2	9	5.1	0	0.2	37.6	42.6	0 0	0	0	2	8 4	79	39	10	2 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
1100	195	9	151	5	23	2	2	0	0	0	3	0	0	49	25.2	9	4.7	1	0.3	37.2	41.9	0 0	0	1	2	7 5	4 82	36	10	2 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
1200	183	8	143	3	22	1	2	0	1	1	1	0	0	62	33.6	12	6.7	1	0.5	38.3	43.3	0 0	0	1	1	8 3) 81	44	13	3 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
1300	163	5	127	2	20	1	2	0	1	1	2	0	0	58	35.8	14	8.4	1	0.9	38.8	43.5	0 0	0	0	1	5 3) 68	42	11	4 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
1400	187	8	142	5	24	1	2	0	1	1	2	0	0	62	33.2	16	8.6	2	1.1	38.5	43.8	0 0	0	0	1	4 3	8 81	42	14	4 2	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
1500	194	9	154	5	20	1	3	0	0	1	1	0	0	71	36.8	18	9.1	2	0.8	39	43.7	0 0	0	0	0	4 3	4 84	50	16	4 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
1600	198	7	162	3	22	1	1	0	0	1	2	0	0	79	39.8	18	8.9	2	0.9	39.1	44.1	0 0	1	0	0	5 2	9 83	55	18	3 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
1700	171	4	145	3	16	1	0	0	0	1	2	0	0	68	40.0	17	9.7	1	0.6	39.2	44.1	0 0	0	0	1	2 2	5 73	47	16	4 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
1800	109	2	93	1	10	0	1	0	0	1	3	0	0	49	45.2	15	13.9	1	1.3	40.1	45.7	0 0	0	0	0	1 1	5 43	30	14	4 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
1900	74	2	63	1	5	0	0	0	0	1	1	0	0	35	48.0	10	13.8	1	1.9	39.9	45.5	0 0	0	0	0	1 9	27	23	9	2 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
2000	52	3	42	1	5	0	0	0	0	0	0	0	0	25	49.3	8	15.2	1	1.7	40.1	46	0 0	0	0	1	2 4	19	15	7	2 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
2100	37	1	31	0	3	0	0	0	1	0	0	0	0	17	47.5	5	12.8	1	1.9	40.1	45.7	0 0	0	0	0	1 5	13	10	5	2 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
2200	22	0	18	0	2	0	0	0	0	0	0	0	0	7	34.2	3	13.2	0	2.0	38.2	44.9	0 0	0	0	0	1 4	8	4	2	1 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
2300	16	1	14	0	1	0	0	0	0	0	0	0	0	8	49.1	3	20.5	0	2.7	40.1	47.4	0 0	0	0	0	1 3	4	4	3	1 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0 0	0
07-19	1969	62	1539	40	249	14	18	2	7	12	25	0	0	686	34.9	159	8.1	13	0.7	38.6	43.5	0 0	2	3	9	54 37	5 840	480	156	37 9	3	1	1	0	0 0	0	0	0	0 0	0	0	0 0	0
06-22	2185	68	1708	46	276	15	19	2	9	13	28	0	0	791	36.2	192	8.8	17	0.8	38.7	43.8	0 1	2	4	10	59 40	0 918	543	186	46 1	3	2	1	0	0 0	0	0	0	0 0	0	0	0 0	0
06-00	2223	69	1741	47	279	15	19	3	9	14	28	0	0	806	36.3	198	8.9	18	0.8	38.7	43.8	0 1	2	4	10	61 40	7 931	551	190	47 1:	3	2	1	0	0 0	0	0	0	0 0	0	0	0 0	0
00-00	2276	69	1775	48	288	16	19	3	10	18	31	0	0	838	36.8	212	9.3	21	0.9	38.8	44	0 1	2	4	11	62 41	2 947	565	200	52 1	4	2	1	0	0 0	0	0	0	0 0	0	0	0 0	0


		Virtual We	eek (1)																			Virtual We	ek (1)																				
Time	Total						Classifi	cation]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spe	eed Bins	(mph)										
		1	2	3	4	5	6	7	8	9	10	11	12	40	40	46	46	55	55		85	5 -	10 -	15 -	20 - 2	5 -	35 -	40 -	45 - !	60 - 55	- 60 -	65 -	70 - 75	- 80 -	- 85 -	90 -	95 - 1	00 - 105	- 110 -	115 - 11	20 - 125	5 - 130 -	135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 10	15	20	25	30 30 - 3	40	45	50	55 60	65	70	75 8	85	90	95	100	105 110	115	120 1	25 13	30 135	140
Mon	2293	48	1697	65	362	14	9	5	11	23	59	0	0	834	36.4	213	9.3	13	0.6	38.8	44	0 0	2	2	13	62 404	976	553	223	45 12	1	0	0 0	0	0	0	0	0 0	0	0	0 0) 0	0
Tue	2154	47	1575	65	331	17	30	3	16	22	47	0	1	842	39.1	228	10.6	27	1.3	39.5	44.5	0 0	0	2	3	32 298	977	550	208	57 21	5	1	0 0	0	0	0	0	0 0	0	0	0 0	0	0
Wed	2444	95	1791	50	363	25	30	1	13	22	54	0	0	655	26.8	146	6.0	11	0.5	37.4	42.6	0 2	3	4	13 1	07 656	1004	459	147	38 8	1	1	1 (0	0	0	0	0 0	0	0	0 0	0	0
Thu	2420	74	1818	52	371	21	21	1	12	23	26	0	1	766	31.7	183	7.6	15	0.6	37.8	42.9	0 3	6	3	17 1	18 526	981	542	165	44 11	3	1	0 0	0	0	0	0	0 0	0	0	0 0	0 (0
Fri	2699	71	2127	51	329	25	38	4	9	21	23	1	0	1050	38.9	262	9.7	26	1.0	39	44.2	0 1	1	12	16	61 462	1096	708	256	60 19	6	1	0 0	0	0	0	0	0 0	0	0	0 0	0 (0
Sat	1969	75	1696	31	142	6	2	2	4	6	5	0	0	837	42.5	220	11.2	27	1.4	39.8	44.9	0 0	5	3	8	20 286	810	555	195	60 13	3	4	5 2	. 0	0	0	0	0 0	0	0	0 0) 0	0
Sun	1955	70	1722	20	120	2	3	3	5	6	4	0	0	882	45.1	234	12.0	27	1.4	40	45.1	0 0	0	1	4	32 250	786	587	206	62 14	8	4	1 (0	0	0	0	0 0	0	0	0 0) 0	0
5 Day Ave.	2402	67	1802	57	351	20	26	3	12	22	42	0	0	829	34.5	206	8.6	18	0.7	38.5	43.6	0 1	2	5	12	76 469	1007	562	200	49 14	3	1	0 0	0	0	0	0	0 0	0	0	0 0	0	0
7 Day Ave.	2276	69	1775	48	288	16	19	3	10	18	31	0	0	838	36.8	212	9.3	21	0.9	38.8	44.0	0 1	2	4	11	62 412	947	565	200	52 14	4	2	1 (0	0	0	0	0 0	0	0	0 0	0	0
	15934	480	12426	334	2018	110	133	19	70	123	218	1	2	5866	36.8	1486	9.3	146	0.9	38.8	44.0	0 6	17	27	74	32 2882	6630	3954	1400	366 98	3 27	12	7 2	. 0	0	0	0	0 0	0	0	0 0) 0	0





		Virtual Da	ay (7)																			Virtual	Day (7)																					
Time	Total						Classif	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp											Speed Bin	s (mph))										
		1	2	3	4	5	6	7	8	9	10	11	12	30	30	35	35	45	45		85	ا م	5 - 10	- 15 -	20 -	25 -	35	- 40 -	45 -	50 -	55 - 6	0 - 65 -	70 -	75 -	80 -	85 - 90	- 95	- 100 -	105 -	110 - 1	115 - 12	20 - 125	- 130 -	135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5	10 15	20	25	30	40	45	50	55	60	55 70	75	80	85	90 95	100	0 105	110	115	120 1	25 130	135	140
0000	1	0	1	0	0	0	0	0	0	0	0	0	0	0	20.0	0	20.0	0	0.0	29.1	-	0	0 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
0100	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	-	-	0	0 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
0200	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100.0	0	100.0	0	0.0	36.3	-	0	0 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
0300	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	-	-	0	0 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
0400	1	0	0	0	0	0	0	0	0	0	0	0	0	0	50.0	0	50.0	0	0.0	34.1	-	0	0 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
0500	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	16.7	-	0	0 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
0600	1	0	1	0	0	0	0	0	0	0	0	0	0	0	10.0	0	0.0	0	0.0	22.8	-	0	0 0	0	1	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
0700	4	0	4	0	0	0	0	0	0	0	0	0	0	1	32.3	0	6.5	0	0.0	28.1	-	0	0 0	0	1	2	1 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
0800	7	0	6	0	1	0	0	0	0	0	0	0	0	1	13.5	0	0.0	0	0.0	22.8	-	0	1 1	0	1	3	1 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
0900	10	1	8	0	1	0	0	0	0	0	0	0	0	2	18.1	1	5.6	0	0.0	22.8	30.9	0	1 2	1	1	4	1 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
1000	14	3	9	0	1	0	0	0	0	0	0	0	0	2	13.7	0	0.0	0	0.0	22.6	29.8	0	1 2	1	4	4	2 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
1100	13	1	10	0	2	0	0	0	0	0	0	0	0	2	16.1	1	7.5	0	0.0	24.8	30.9	0	0 1	1	4	5	1 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
1200	15	2	10	0	3	0	0	0	0	0	0	0	0	2	11.4	1	3.8	0	0.0	24.5	29.5	0	1 1	1	3	7	1 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
1300	10	2	6	0	2	0	0	0	0	0	0	0	0	3	26.8	0	1.4	0	0.0	26.1	32.3	0	0 0	1	2	4	3 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
1400	15	1	12	0	3	0	0	0	0	0	0	0	0	4	26.9	0	1.9	0	0.0	26.1	32.1	0	0 0	1	3	6	4 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
1500	17	2	12	0	2	0	0	0	0	0	0	0	0	5	26.9	1	7.6	0	0.0	25	32	0	0 2	2	4	5	3 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
1600	20	3	14	1	3	0	0	0	0	0	0	0	0	9	45.0	2	12.1	0	0.0	28.4	34.9	0	0 1	1	3	6	7 2	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
1700	16	0	13	0	2	0	0	0	0	0	0	0	0	4	22.5	1	5.4	0	1.8	25.6	31.6	0	0 2	1	4	6	3 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
1800	12	0	10	0	2	0	0	0	0	0	0	0	0	3	25.0	1	4.8	0	0.0	25.8	31.4	0	0 1	0	3	4	2 1	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
1900	5	0	4	0	1	0	0	0	0	0	0	0	0	1	11.8	0	2.9	0	0.0	23.4	-	0	0 1	0	1	2	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
2000	2	0	2	0	0	0	0	0	0	0	0	0	0	0	20.0	0	6.7	0	0.0	23.9	-	0	0 0	0	1	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
2100	2	0	2	0	0	0	0	0	0	0	0	0	0	1	26.7	0	0.0	0	0.0	23	-	0	0 1	0	0	0	1 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
2200	1	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0	0.0	0	0.0	19.7	-	0	0 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
2300	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100.0	0	0.0	0	0.0	30.2	-	0	0 0	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
07-19	154	15	112	2	22	0	1	0	1	0	0	0	0	37	24.0	8	5.2	0	0.2	25.3	31.8	0	5 13	11	34	55	29 7	1	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
06-22	165	15	121	3	23	0	1	0	1	0	0	0	0	39	23.5	8	5.0	0	0.2	25.2	31.7	0	6 15	11	36	59	30 7	1	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
06-00	166	15	122	3	23	0	1	0	1	0	0	0	0	39	23.5	8	5.0	0	0.2	25.2	31.7	0	6 15	11	36	59	31 7	1	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
00-00	167	15	123	3	23	0	1	0	1	0	0	0	0	39	23.6	9	5.3	0	0.2	25.2	31.7	0	6 15	12	36	60	31 8	1	0	0	0	0 0	0	0	0	0 0	0	0	0	0	0	0 0	0	0

		Virtual We	eek (1)																			Virtual V	Veek (1)																					
Time	Total						Classif	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Sp	eed Bins	(mph)											
		1	2	3	4	5	6	7	8	9	10	11	12	30	30	35	35	45	45		85	ا ا	5 - 10 -	15 -	20 -	25 - 20 - 2	35 -	40 -	45 -	50 - 5	5 - 60	65 -	70 -	75 -	80 - 8	35 - 9 0	- 95	- 100 ·	- 105 -	110 -	115 -	120 - 125	5 - 130 -	135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5	10 15	20	25	30 - 3	40	45	50	55	60 65	70	75	80	85	90 9	100) 105	110	115	120	125 13	0 135	140
Mon	151	11	118	2	18	0	1	0	0	0	1	0	0	40	26.5	8	5.3	0	0.0	26.6	32.5	0	2 11	5	28	65 32	6	2	0	0	0 0	0	0	0	0	0 (0	0	0	0	0	0 0	0	0
Tue	144	14	107	1	22	0	0	0	0	0	0	0	0	28	19.4	6	4.2	0	0.0	24.8	31.5	0	5 12	11	34	54 22	6	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
Wed	265	20	190	2	48	0	1	1	2	1	0	0	0	81	30.6	20	7.5	2	0.8	26.9	33.1	0	2 13	20	60	89 61	16	2	0	2	0 0	0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
Thu	192	12	139	3	29	2	2	2	2	0	1	0	0	37	19.3	8	4.2	0	0.0	23.3	30.4	0	13 27	12	43	60 29	6	2	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
Fri	154	2	129	4	17	0	2	0	0	0	0	0	0	35	22.7	7	4.5	0	0.0	24.1	31.1	0	6 23	12	27	51 28	7	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
Sat	139	24	96	2	17	0	0	0	0	0	0	0	0	33	23.7	10	7.2	0	0.0	25.1	32.4	1	4 12	12	33	44 23	9	1	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
Sun	126	25	82	4	13	0	2	0	0	0	0	0	0	22	17.5	3	2.4	0	0.0	24.7	30.3	0	7 6	9	28	54 19	3	0	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0	0 0	0 0	0
5 Day Ave.	181	12	137	2	27	0	1	1	1	0	0	0	0	44	24.3	10	5.5	0	0.0	25.1	31.7	0	6 17	12	38	64 34	8	1	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
7 Day Ave.	167	15	123	3	23	0	1	0	1	0	0	0	0	39	23.6	9	5.3	0	0.2	25.2	31.7	0	6 15	12	36	60 31	8	1	0	0	0 0	0	0	0	0	0 0	0	0	0	0	0	0 0	0	0
	1171	108	861	18	164	2	8	3	4	1	2	0	0	276	23.6	62	5.3	2	0.2	25.2	31.7	1 :	39 104	81	253	417 214	53	7	0	2	0 0	0	0	0	0	0 (0	0	0	0	0	0 0	0	0






	A83 approx 300m north of the A83/ B828 junction							Jur	ne 2021	A83 approx 300m north of the A83/ B828 junction
	North South						Automat	tic Traffic	Count	North South
	Virtual Day (7)									Virtual Day (7)
tal	Classification]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp	

		Virtual Da	ay (7)																			Virtual D	ay (7)																				
Time	Total						Classifi	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Spe	ed Bins ((mph)										
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	5	i - 10 -	15-	20 -	25 -	35	- 40 -	45 - 5	50 - 55 -	60 -	65 -	70 -	75 - 80	- 85 -	90 -	95 -	100 - 10	5 - 110	- 115 -	120 - 1	125 - 130	- 135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ΔRT5	ART6	BD	DRT				ACPO		DfT			0 - 5 1	0 15			30 30) - 35 40			55 60	65	70	75	80 85	5 90							130 135	
0000	24	1		201	102	0	0	0	0	AKIS	0	00		0	1.0	ACIO		0	0.0	27.8	51.3	1	0 13	20	1	0	1 2	2	20	2 1	00	,,,	0	0 0	70	75	0	0 (0 113	120	0	0 0	140
	24		21	-	2		0			0		0	0	U	1.2	0	0.6	-					8 2	-	1		1 2	2	3	3 1	0	0	0	0 0	0	0	0	0 (0 0	0	-	0 0	- 0
0100	22	0	17	0	2	0	0	0	0	0	1	0	0	0	2.0	0	0.7	0	0.0	27.2	47.7	1	3 4	3	2	1	1 2	1	2	2 0	0	0	0	0 0	0	0	0	0 (0 0	0		0 0	0
0200	11	0	7	0	2	0	0	0	0	1	1	0	0	0	2.6	0	1.3	0	0.0	41.2	49.6	0	0 0	0	0	0	1 3	2	3	1 0	0	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
0300	10	0	5	0	2	1	0	0	0	1	1	0	0	0	0.0	0	0.0	0	0.0	43.7	-	0	0 0	0	0	0	1 1	4	3	1 0	0	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
0400	23	0	12	0	7	1	0	0	0	1	1	0	0	1	5.5	0	0.6	0	0.0	47.5	55.6	0	0 0	0	0	0	1 2	3	5	7 3	1	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
0500	35	0	20	1	7	1	0	0	0	1	4	0	0	2	4.8	1	1.6	0	0.4	46.6	55.3	0	0 0	0	0	1	1 5	9	6	7 4	1	1	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
0600	93	0	60	2	16	4	1	0	1	2	7	0	0	2	2.6	1	0.6	0	0.2	44.8	53.4	0	0 0	1	2	3	5 12	22	19	17 8	2	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
0700	154	1	106	3	25	6	2	1	1	3	7	0	0	3	2.1	0	0.0	0	0.0	42.9	52	0	0 0	1	8	7	9 24	39	34	21 8	3	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
0800	203	4	147	5	29	5	6	1	1	2	4	0	0	4	1.8	1	0.4	0	0.1	43.1	50.7	0	0 0	5	6	8	9 28	59	51	24 9	3	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
0900	258	8	194	5	33	4	3	1	2	2	5	0	0	3	1.2	1	0.3	0	0.1	41	49	0	0 1	5	13	12	24 49	73	51	21 8	2	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
1000	365	16	285	5	40	4	3	1	1	2	6	0	0	6	1.6	2	0.4	1	0.2	40.7	48.5	0	0 1	5	11	19	36 98	96	62	22 11	3	1	1	0 0	0	0	0	0 (0 0	0	0	0 0	0
1100	394	18	317	7	36	5	4	1	1	2	4	0	0	2	0.5	1	0.2	1	0.2	39.2	46.8	0	0 2	10	18	15	49 10	5 109	56	19 7	1	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
1200	400	14	322	9	37	3	3	0	1	3	6	0	0	3	0.9	1	0.2	0	0.0	39.9	46.7	0	0 2	8	9	15	44 11	6 119	60	19 6	2	0	1	0 0	0	0	0	0 (0 0	0	0	0 0	0
1300	391	18	308	7	42	3	3	0	2	3	4	0	0	3	0.9	0	0.1	0	0.0	40.6	47.5	0	0 1	7	9	16	35 10	5 118	64	24 8	3	1	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
1400	400	17	312	8	43	4	4	1	1	3	6	0	1	3	0.8	1	0.2	0	0.0	40.5	47.6	0	0 2	3	8	18	46 10	9 114	65	24 9	2	1	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
1500	379	18	299	6	42	3	2	0	1	0	6	0	0	5	1.4	1	0.3	0	0.1	41.3	48.5	0	0 0	5	10	12	38 88	109	74	26 10	4	1	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
1600	355	15	292	4	34	1	3	1	1	2	3	0	0	5	1.4	1	0.4	0	0.0	42.3	49.4	0	0 0	6	9	10	26 74	102	80	31 11	2	2	1	0 0	0	0	0	0 (0 0	0	0	0 0	0
1700	287	12	239	3	24	1	1	1	0	1	4	0	0	6	2.1	1	0.4	0	0.1	42.7	50.7	0	0 0	5	10	9	19 48	79	67	32 12	4	1	1	0 0	0	0	0	0 (0 0	0	0	0 0	0
1800	260	6	215	4	26	2	1	1	1	1	4	0	0	3	1.3	0	0.2	0	0.0	42.3	50.1	0	0 0	4	10	9	19 40	81	59	28 8	2	1	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
1900	202	5	172	2	12	4	2	0	1	2	2	0	0	4	2.0	1	0.5	0	0.1	35.6	49.4	0 1	17 17	8	7	9	18 30) 41	28	18 6	3	1	1	0 0	0	0	0	0 (0 0	0	0	0 0	0
2000	119	3	99	1	9	2	1	0	0	1	2	0	0	2	1.9	0	0.0	0	0.0	37.4	50.8	0 1	16 4	2	1	4	7 1	23	23	11 6	2	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
2100	78	1	67	1	4	1	1	0	1	1	1	0	0	2	2.8	0	0.4	0	0.0	36.4	52.5	0 1	13 3	1	2	1	5 10	15	10	9 5	1	1	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
2200	58	0	48	0	5	1	2	0	0	1	1	0	0	1	2.0	0	0.5	0	0.0	29.5	48.9	1 1	19 3	0	0	1	2 6	0	8	5 2	1	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
2300	34	0	29	0	2	1	0	0	0	0	0	0	0	1	2.1	0	0.4	0	0.0	28.6	47	0	8 7	0	0	0	1 5	5	5	1 1	0	0	0	0 0	0	0	0	0 (0 0	0	0	0 0	0
07-19	3846	146	3037	67	411	39	36	9	14	25	60	1	2	47	1.2	10	0.4	3	0.0	41.1	48.8	0	2 9	63	121	149	354 88	2 1098	722	291 108	32	9	4	1 1	0	0	0	0 (0 0	0	0	0 0	0
06-22	4338	155	3434	72	452	50	42	9	17	30	72	2	2	58	1.3	12	0.3	3	0.1	40.8	49	1 1	18 33	75			389 95			345 133		11	5	1 1	0	0	0	0 (0 0	0	0	0 0	
06-22	4429	156	3511	73	460	51	44	10	18	30	73	2	2	60	1.4	12	0.3	3	0.1	40.5	49	2 7	75 43	76			393 96			352 135	_	12	6	1 1	0	0	0	0 (0	0	0	0 0	
00-00	4555	156	3593	75	481	55	45	10	19	31	81	2	2	64	1.4	13	0.3	3	0.1	40.5	49.2	4 0	35 49	70			393 96			372 144			4	1 1	0	0	0	0 (0 0	0	0	0 0	0
00-00	4055	156	3093	/5	481	55	45	10	19	36	81	2	2	04	1.4	13	0.3	3	0.1	40.5	49.2	4 8	19	19	13/	170	398 97	1 1235	839	3/2 144	42	13	0	1 1	0	0	U	0 (0	0	U	0 0	U

				-																																				4				
		Virtual We	eek (1)																			Virtual W	eek (1)																					
Time	Total						Classific	cation]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										9	Speed Bi	ins (mph	1)										
		1	2	3	4	5	6	7	8	9	10	11	12	60	60	68	68	75	75		85	_ 5	- 10 -	15 -	20 -	25 -	35	- 40 -	45 -	50 -	55 - 6	0 - 65	- 70 -	75 -	80 -	85 - 9	0 - 95	- 100	- 105 -	110 -	115 - 120) - 125	- 130 - 13	35 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5	15	20	25	30	- 35 40	45	50	55	60 6	65 70	75	80	85	90 1	95 10	00 105	5 110	115	120 125	5 130	135 1	140
Mon	4188	78	3177	80	560	42	59	6	33	51	98	3	1	55	1.3	8	0.2	2	0.0	43	49.8	0 4	14	7	16	79 2	90 979	9 1245	949	395	155	42 9	2	0	0	0	0 0	2	0	0	0 0	0	0	0
Tue	4166	100	3084	92	533	73	53	9	21	43	156	1	1	130	3.1	24	0.6	0	0.0	45.4	53.1	1 1	8	27	27	26 1	49 640	1219	1034	636	268 8	86 30	14	0	0	0	0 0	0	0	0	0 0	0	0	0
Wed	4395	132	3289	75	540	89	74	16	20	37	118	0	5	68	1.5	23	0.5	7	0.2	38.3	49.5	9 42	3 185	25	23	107 2	91 78	4 1137	819	367	157	38 12	11	4	3	0	0 0	0	0	0	0 0	0	0	0
Thu	4502	122	3526	67	489	72	46	13	18	46	94	4	5	7	0.2	1	0.0	0	0.0	30.8	41.6	15 12	0 93	432	790	675 7	28 76	3 496	267	100	16	5 2	0	0	0	0	0 0	0	0	0	0 0	0	0	0
Fri	5390	187	4277	78	600	50	49	13	15	41	75	3	2	75	1.4	16	0.3	6	0.1	42.6	49.3	1 29	9 11	17	19	69 3	377 131	0 1782	1076	466	158	46 15	8	2	4	0	0 0	0	0	0	0 0	0	0	0
Sat	4804	342	3980	67	330	26	16	0	14	17	11	0	1	69	1.4	8	0.2	3	0.1	42.1	48.6	0 2	1	5	22	102 5	29 122	7 1422	925	356	144 !	54 8	4	0	2	1	0 0	0	0	0	0 0	0	0	0
Sun	4440	134	3815	63	317	31	21	12	11	18	18	0	0	45	1.0	12	0.3	4	0.1	41.1	48.1	1 15	5 34	41	65	135 4	124 113	9 1346	802	282	111 2	26 13	2	2	0	2	0 0	0	0	0	0 0	0	0	0
5 Day Ave.	4528	124	3471	78	544	65	56	11	21	44	108	2	3	67	1.5	14	0.3	3	0.1	40.0	48.7	5 11	5 62	102	175	191 3	867 89	5 1176	829	393	151	43 14	7	1	1	0	0 0	0	0	0	0 0	0	0	0
7 Day Ave.	4555	156	3593	75	481	55	45	10	19	36	81	2	2	64	1.4	13	0.3	3	0.1	40.5	49.2	4 85	5 49	79	137	170 3	398 97	7 1235	839	372	144	42 13	6	1	1	0	0 0	0	0	0	0 0	0	0	0
	31885	1095	25148	522	3369	383	318	69	132	253	570	11	15	449	1.4	92	0.3	22	0.1	40.5	49.2	27 59	4 346	554	962	1193 2	788 684	2 8647	5872	2602	1009 2	97 89	41	8	9	3	0 0	2	0	0	0 0	0	0	0






June 2021	A85 approx 200m east of the A85/ B845 junction
Automatic Traffic Count	North South


T1																						Virtual D	Juj (,)																				
lime	Total						Classific	cation]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										S	peed Bir	ns (mph)										
		1	2	3	4	5	6	7	8	9	10	11	12	30	30	35	35	45	45		85	o _ 5	5 - 1	0 - 15 -		25 -		35 - 40	- 45 -	50 -	55 - 60	0 - 65 -	70 -	75 - 80 -	- 85 -	90 -	95 - 10	00 - 105	5 - 110 -			25 - 130 -	
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5 1	10 1	15 20	25	30	50 - 35	40 45	50	55	60 6	5 70	75	80 85	90	95	100 1	05 110	0 115	120	125 1	130 135	140
0000	14	0	10	1	2	0	0	0	0	1	1	0	0	10	67.0	6	45.0	1	10.0	35.3	42.6	0 (0	0 0	0	5	3	3 2	1	0	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0100	10	0	7	0	0	0	0	0	0	1	1	0	0	8	79.4	5	51.5	0	4.4	34.9	-	0 (0	0 0	0	2	3	4 1	0	0	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0200	13	0	9	0	1	0	1	0	0	1	1	0	0	11	81.5	5	39.1	0	3.3	34.6	39.3	0 (0	0 0	0	2	6	3 1	0	0	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0300	10	0	8	0	1	0	0	0	0	0	1	0	0	8	85.3	5	55.9	1	11.8	35.8	-	0 (0	0 0	0	1	3	3 1	0	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0400	20	0	14	0	2	0	0	0	0	1	1	0	0	16	81.8	11	55.5	2	9.5	35.9	42.6	0 (0	0 0	1	3	5	7 2	1	0	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0500	47	1	29	1	10	1	1	0	0	2	2	0	0	37	78.8	19	40.9	4	9.1	35	41.6	0 (0	0 0	1	9	18	10 5	3	1	1 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0600	85	1	57	1	17	1	1	0	1	3	3	0	0	65	77.2	30	35.2	5	5.9	34.3	40.9	0 (0	0 0	1	18	36	15 10	3	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0700	179	2	134	2	34	2	2	0	0	1	3	0	0	119	66.6	49	27.2	4	2.3	32.8	38	0 (0	0 0	2	58	71	30 15	3	0	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0800	268	3	212	5	39	2	2	1	1	2	1	0	0	161	60.1	59	22.0	4	1.6	31.9	36.9	0 (0	0 1	9	97	102	38 16	3	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
0900	326	11	249	7	46	3	4	0	2	3	2	0	0	217	66.6	77	23.5	5	1.6	32.2	37	0 (0	1 1	9	98	140	52 19	4	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
1000	396	13	312	9	50	3	4	0	1	1	2	0	0	276	69.8	105	26.5	7	1.8	32.6	37.4	0 (0	1 1	8	110	171	75 23	6	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
1100	392	14	308	9	52	2	2	1	1	1	2	0	0	259	66.2	97	24.7	8	2.2	32.3	37.4	0 (0	0 1	14	118	163	68 21	6	2	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
1200	426	10	339	10	56	3	2	1	1	1	2	0	0	278	65.4	104	24.4	6	1.5	32.4	37.2	0 (0	0 1	11	135	175	70 28	5	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
1300	371	14	291	8	48	2	3	1	1	2	2	0	0	251	67.7	100	26.9	6	1.7	32.5	37.9	0	1	1 2	13	102	151	68 25	4	2	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
1400	407	18	325	8	47	2	2	1	1	1	2	0	0	272	66.7	104	25.6	9	2.1	32.6	37.6	0 (0	1 1	11	123	167	70 26	6	1	1 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
1500	401	15	326	6	48	2	2	1	1	0	1	0	0	259	64.7	103	25.6	9	2.2	32.3	37.5	0 (0	0 2	15	124	157	70 24	7	1	1 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
1600	388	10	324	4	41	4	2	1	1	1	1	0	0	255	65.9	97	25.1	8	2.1	32.4	37.4	0 (0	1 0	12	119	158	68 22	6	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
1700	351	9	295	4	38	1	1	0	1	1	1	0	0	239	68.0	93	26.4	8	2.4	32.6	37.7	0 (0	1 2	7	103	146	62 22	6	2	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
1800	252	4	213	3	25	2	2	0	1	1	2	0	0	170	67.5	64	25.6	7	2.7	32.6	37.9	0 (0	0 1	6	75	106	42 16	6	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
1900	176	6	147	1	16	1	1	0	1	2	1	0	0	123	70.0	53	30.2	6	3.2	33.2	38.6	0 (0	0 0	3	49	70	35 13	4	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
2000	131	1	112	1	13	1	0	0	1	0	1	0	0	94	71.9	44	33.8	7	5.7	33.8	40	0 (0	0 0	1	36	50	25 12	5	2	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
2100	93	1	79	1	10	0	0	0	1	1	0	0	0	69	73.8	33	35.8	5	5.7	34	40.5	0 (0	0 0	2	22	35	18 10	4	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
2200	55	1	47	0	6	0	0	0	0	1	0	0	0	38	68.2	17	30.8	4	6.7	33.5	39.3	0 (0	0 0	2	16	21	9 4	2	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
2300	28	0	20	1	5	0	0	0	0	2	0	0	0	20	71.5	10	37.8	2	6.2	34.2	41.3	0 (0	0 0	1	7	9	6 3	1	1	0 (0 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
07-19	4158	121	3327	75	523	27	29	6	12	15	22	1	0	2759	66.4	1051	25.3	82	2.0	32.4	37.5	0 :	2	7 12	116	1262	1708	712 257	63	13	3 2	2 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
06-22	4643	130	3722	79	580	31	31	6	15	21	27	1	0	3111	67.0	1212	26.1	106	2.3	32.6	37.7	0 :	2	7 13	124		1899 8	305 301	79	19	5	2 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
06-00	4726	131	3788	80	591	31	31	7	15	23	28	1	0	3168	67.0	1239	26.2	111	2.4	32.6	37.7	0 :	2	8 13	127	1409	1929 8	320 308	83	20	5 2	2 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
00-00	4840	132	3865	82	607	33	33	7	16	29	35	1	0	3257	67.3	1291	26.7	121	2.5	32.6	37.8	0	2	8 13	129			350 321	89	22	6	2 0	0	0 0	0	0	0	0 0	0	0	0	0 0	0
2300 07-19 06-22 06-00	28 4158 4643 4726	121 130 131	20 3327 3722 3788	79 80	580 591	0 27 31 31	29 31 31	0 0 6 6 7	15 15	21 23	22 27		0 0 0	20 2759 3111 3168	71.5 66.4 67.0 67.0	10 1051 1212 1239	37.8 25.3 26.1 26.2	106 111	6.2 2.0 2.3 2.4	34.2 32.4 32.6 32.6	41.3 37.5 37.7	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0 0 2 2 2 2 2	0 0 7 12 7 13	_	7 1262 1387 1409	9 1708 3 1899 8 1929 8	320 308	83	19	0 0 0 3 2 5 2 5 2 5	0 0 0 0 2 0 2 0 2 0	0 0 0 0 0	0 0 0 0 0 0 0 0	0 0 0 0	0 0 0 0	0 0 0 0 0	0 0 0 0 0 0 0 0	0 0 0	0 0	0 0 0 0 0	0 0 0 0 0 0	0 0


·		Virtual We	eek (1)		<u> </u>	<u> </u>	<u> </u>					·	<u> </u>		<u> </u>	<u> </u>			<u> </u>	<u> </u>	·	Virtual W	leek (1)					<u> </u>			·	·											
Time	Total						Classifi	ication]PSL]PSL%]SL1]SL1%]SL2]SL2%	Mean	Vpp										Speed I	Bins (mp	h)										
		1	2	3	4	5	6	7	8	9	10	11	12	30	30	35	35	45	45		85	5	- 10 -	15 -	20 -	25 -	35 -	40 - 4	5 - 50 -	55 -	60 - 65	- 70	- 75 -	80 -	85 - 1	90 - 9	5 - 110	0 - 105 - /	110 -	115 - 12	20 - 125 -	- 130 -	135 -
		MCL	SV	SVT	TB2	TB3	T4	ART3	ART4	ART5	ART6	BD	DRT			ACPO	ACPO	DfT	DfT			0 - 5	0 15	20	25	30 30 - 31	40	45	50 55	60	65 7	0 75	80	85	90	95 1/	00 10		115	120 1	25 130	135	140
Mon	4853	88	3787	93	718	36	28	6	21	32	43	0	1	3125	64.4	1179	24.3	89	1.8	32.2	37.1	0 3	3 5	25	137	1558 1946	832	258	63 21	5	0 (0	0	0	0	0 1	0 (0	0	0	0 0	0	0
Tue	4839	112	3767	70	720	29	44	2	20	35	39	1	0	3130	64.7	1131	23.4	98	2.0	32.2	37.1	0 2	2 6	8	139	1554 1999	746	287	79 13	6	0 (0	0	0	0	0 /	0 (0	0	0	0 0	0	0
Wed	4871	142	3722	83	713	43	41	4	24	48	49	2	0	3278	67.3	1283	26.3	116	2.4	32.6	37.6	0 3	3 9	10	129	1442 1995	880	287	87 20	6	1 (0	0	0	0	0 /	0 (0	0	0	0 0	2	0
Thu	4726	107	3691	95	649	38	50	7	14	35	39	1	0	3251	68.8	1280	27.1	118	2.5	32.8	37.7	0 () 4	7	106	1358 1971	848	314	84 24	5	4	0	0	0	0	0 /	0 (0	0	0	0 0	0	0
Fri	5431	128	4354	82	680	45	30	12	21	33	45	0	1	3713	68.4	1490	27.4	157	2.9	32.7	37.9	0 2	2 20	18	150	1528 2223	971	362	14 32	8	3 (0	0	0	0	0 /	0 (0	0	0	0 0	0	0
Sat	5104	204	4367	71	378	22	27	9	7	10	8	1	0	3541	69.4	1525	29.9	148	2.9	33	38.7	0 2	2 6	15	158	1382 2016	950	427	15 22	5	5 () 1	0	0	0	0 /	0 (0	0	0	0 0	0	0
Sun	4055	140	3368	83	389	17	12	6	7	11	21	1	0	2764	68.2	1151	28.4	119	2.9	32.9	38.3	0 5	5 3	6	82	1195 1613	723	309	79 24	10	4	2 0	0	0	0	0 /	0 (0	0	0	0 0	0	0
5 Day Ave.	4944	115	3864	85	696	38	39	6	20	37	43	1	0	3299	66.7	1273	25.7	116	2.3	32.5	37.5	0 2	2 9	14	132	1488 2027	855	302	85 22	6	2 (0	0	0	0	0	0 (0	0	0	0 0	0	0
7 Day Ave.	4840	132	3865	82	607	33	33	7	16	29	35	1	0	3257	67.3	1291	26.7	121	2.5	32.6	37.8	0 2	2 8	13	129	1431 1966	850	321	89 22	6	2 (0	0	0	0	0	0 (0	0	0	0 0	0	0
	33879	921	27056	577	4247	230	232	46	114	204	244	6	2	22802	67.3	9039	26.7	845	2.5	32.6	37.8	0 1	7 53	89	901	10017 13763	5950	2244 6	21 156	45	17 :	3 1	0	0	0	0	0 (0	0	0	0 0	2	0








Annex C - Network Flow Diagrams














































Annex D - Road Links
























Annex E - Road Accident History









































Annex F - Construction Traffic Programme



Project Name	Project Number	Document N
Balliemeanoch PSH	60710998	
Created By:	Checked By:	Approved by:
AC	TP	DL

AND	Marganetic Mar	Column	onstruction Area	Contoxtiles (Fleating Access)	Material	Length (m)	Width (m) / Height (m)	Quantity / Area (m²)		Density (kg/m³)	- ' '	Vehicle Trips	Comments 100mm thich gootsytiles (grids and toytiles)
See	Second Column Second Secon	March Marc		Geotextiles (Floating Access) Stone for Access Track	Geotextile Aggregate	4,995.00 4,995.00	10 10	49,950.00 49,950.00	4,995.00 29,970.00	970 2650	4,845.15 79,420.50		
See Michael Service (1964) Se	Commonwealth	Section Control Cont											
Second S	March Cont. Cont	Section Sect		Change of the Assess Total		12,301.91	10.00	123,019.08	61,509.54	2650	163,000.28	1/ 200	500 I I 1
Comment Comm	Company	Seminary Company of the property of the proper				11 394 06	10.00	113 940 56	56 970 28	2650	150 971 24		
Company Comp	Appendix Company Com	Amount A											
Commonweight Comm	March Marc	March Control Contro	ccess (Water crossings)	Rebar (Reinforcement)	Rebar				5.40	7850	42.39	4	
Property	THE PROPERTY OF THE PARTY OF TH	STATE STAT	ampounds (Pormanont)	Concrete	Concrete	-	-	1,058.00	529.00	2400	1,269.60	120	
Second	Part	Company Comp				-	-		5.29	7850	41.53		
Common C	Manual M	Property									45.40		
Company Comp	March Marc	March Marc	ampounds (Pormanont)	Foncing Mosh	Calvanisad Stool (Mosh)	1,746.00	-	140.00	-	-	15.40	2	
Page	Part	Part	impounds (Fermanent)	rending - iviesii	Galvariiseu Steer (Mesri)	1.71/.00		500.00		775			
Part	Second S	Property Caleborn State Property State	ompounds (Permanent)			1,746.00	3	582.00	1.00	7750	7.75	1	50mm D x 3m (H)
March Marc	Company	Color Colo	mana and (Darmanant)									1/	
Property	Second Systems Seco	Part	ompounds (Permanent)	Equipment)	various	 						10	
Property Property Service of strateging Service	Second Property Second Property Second 1998	Part				- 1	-		-	-	-		Stop logs x 2
Part	Contact Cont	Property			ridire			22.24/.02	7.707.20	2/50	20 (22 02		
Processor Company Co	Second Annexes Second Seco	Process Process Authors Sept	ompounds (Permanent)	Stone for Hardstanding	Aggregate							2,063	
Property	Second Company Second Content and Second Conten	THE PROPERTY OF STATE OF CONTROL BY A CONTRO	empounds (Permanent)	Safety grate for Surge shaft openings	Steel	15.00	15.00	1.00	11.25	7750	87.19	9	
April Apri	1966 1966	April				10.00	10.00	3.00	15.00	7750	116.25		50mm deep grate
Part Command Company	Part	Company Comp	empounds (Permanent)	Safety grate for Ventillation Shaft openings	Steel	10.00	10.00	3.00	15.00	7730	110.25	12	
Property	The state of the property of t	Property				9 505 99		00.994			75.60		
Page	Part	Proceed Company Compan	ompounds (Temporary)	Fencing - Mesh	Galvanised Steel (Mesh)	8,595.88	-	688.00	-	-	/5.08	8	
Proceedings Proceedings Process Proces	Mode March	Part	pourius (vorriporus)/		- Carramesa eresi (mesin)	0 505 00	2	2.045.20	1.00	7750	7.75		
	Secretary Secr	Second part Part Company Part Company Part Company Part				0,040.00							
Appendix	Part	Part				-							
Machinest	March Marc	Marie Mari				+		157,432.62					
Section Company Comp	Section Sect	Section Sect		, and the state of					200.00	7000	EJEE T.UE	222	10 x Excavators
Authority County	According to the property of												
Angel	Second Control Contr	Part											0 x Loaders
Section Company Comp	Company	Company Comp			Tonsoil			225 000 51	22 500 05	1600	27745 26200	3 775	0 x Seeder
Appendix County Appendix County Appendix Ap	Secretary Secr	Company Comp	sauponu Embankments	ropsoli for seeding	Topson	+		235,908.51				3,775	
Subport Natif Charlet Structure Marker	Seed of the Country of Seed Seed Seed Seed Seed Seed Seed See	Segment For Card Street Segment Segmen		Concrete	Concrete	-	-	-	7,000.00	2400	16,800.00		625mm Concrete Depth
Season Intell' Collect Broutster Season Seas	Separative of the Services Separative Se	Anthony Company Comp				-	-		70.00	7850	549.50		Concrete:Rebar Ratio: 1%
Support of Color Structure Su	Segment of Control Students Segment Segmen	Segment of Color Studies Segment of Color Stud							13,265.60	2800	37,143.68		
Application	Separate House Services	Authority (April 1992) Author	eadpond Inlet / Outlet Structure	Rock Armour	Rock	+						3,714	
	A	Segrecated of Chine Browners Segrec	adpond Inlet / Outlet Structure	Formwork / Plant	Plant	varies	25	10768.75	1,292.25	550	710.74	71	
Accordance Acc	Company	Anthony											
Accordance Acc	Accordance Color Structure	Secondary Control Co					-		-	-	-		
Submort Principle (Charles) Courted (Charles)	Second	Second control (A)										16	2 x Loaders
Concrete 18 10 16.26 16.20 260 390.24 3.50 300 300.04 3.50 3.5	The facility	Company Comp											
Age Concrete Con	April	Later Facility	eadpond inlet / Outlet Structure	Gates								37	
See	Page	Part	arine Facility	Concrete	Concrete	18	10	16.26	162.60	2400	390.24	43	
Part	March Marc		,			5	E	72	1 005 00	7750	9.496.25		600mm Deep
10	Part	Part	arine Facility	Bridge Deck	Steel	3	5	73	1,095.00	7750	0,400.25	849	
Section Control Cont	Agreement Agre	and failty											
March Part March	Perfect Perf	March Part Margorish M				10	0.6	72	203.58	7750	1,577.71		
Second S	Part	amer Facility (without processing) (oliginal	arine Facility	Piles	Steel							158	
	Note Concrete Co	Part Concrete Co											
Retail (Control Retail (Control Retail (Control Retail (Control Retail (Retail (Control Retail (Retail (Re	See Course of Course of Septiment (Course) Social Conference of Course of Septiment (Course)	Seed Common Seed (Information Seed S											
Inter/Wood 120 25 14500 2,175 00 550 1,196,25 120 Estimates	wer Covern Funderhalm Fermwork / Florit Imper/Wood 120 25 14500 550 1,196.25 120 climates covern Funderhalm Fermwork / Florit Imper/Wood 120 20 8600 1,260.00 550 693.00 66 Climates covern Funderhalm Fermwork / Florit Imper/Wood 120 20 8600 1,260.00 550 693.00 66 Climates covern Funderhalm covern Fun					-	-						
	Net Courte Front Front Fall					120	25	14500					
Turbins Turb	Make Plant and Epigement Plant P	Number N	wer Cavern- Transformer hall	Formwork / Plant	Timber/Wood	120	20	8400	1,260.00	550	693.00	69	Estimates
Transformer half MAE Plant and Equipment Plant Controle Concrole	Part	Mac Plant and Equipment Part Pa											Overhead Gantry Crane x 2
New Cavernand Transformer half Mac Plant and Equipment Plant Concrete 65 32 2880 1,040.00 240 2,496.00 270 57 tournal from the first production Concrete Concrete 65 32 2880 1,040.00 7850 816.40 81 Concrete Rebar Relation (% Concrete Rebar Relation	Mac Plant and Equipment Mac Plant and Equipment Plant Control (Springer) Contro	Application Control Systems Control System				- 1	-		-	-		64	
Concrete	Charged Concrete	witchyard Schart (Reinforcement) 8 Abar	was Causen and Transformer hall	MAR F Dignt and Equipment	Diant								
Rebar Reinforcement Recommended Reinforcement Recommende	Interligent Rebar (Reinforcement) Rebar	Rebur Peter Pete				65	32	2080	1.040.00	2400	2,496.00	274	
April	Part	Addressed Structure (April Structure (Ap				-							Concrete:Rebar Ratio: 1%
1 2 2 2 2 2 2 2 2 2	Technique Fancing - Mish Galvanised Steel (Mesh)	1 2 2 2 2 5 5 5 5 5 5											
Steel 490.00 3 164.00 1.00 7750 7.75 Pole every 3m	tichyard Fancing - Posts Steel 490.00 3 164.00 1.00 7750 7.75 1 Pole every 3m (Activated Formwork / Plant Timber/Wood	April Apri	vitchvard	Foncing Moch	Calvanicad Stock (Advants)	490.00	-	40.00		0	4.40		
Victorary Fencing - Posts Steel 490.00 3 164.00 1.00 7750 7.75 1 50mm p x 3m (H)	Steel Stee	Seed	vitchyaru	rending - iviesh	Galvanised Steel (Mesh)	+						1	
Street Formwork / plant Timber / Wood -	Interview of Commonts Flant Timber / Wood - - 1500 - - 25.20 2 Hievel estinate Hievel of Lithrate Hievel of Lithrate Mark Plant and Equipment Various - - Store for Hardstanding Aggregate - - 13.243.20 3.972.96 2650 10.528.34 1.05.3 Max. 0.3m gravel pond intel / Outlet Structure Rebar (Reinforcement) Rebar - - 14.228 2.400 34.176.3 3.744 30.0 uput Proportion	International Content	vitchyard		Steel	490.00	3		1.00	7750		1	
Stone for Hardstanding Aggregate - -	Chyard Stone for Hardstanding Aggregate 13.243.20 3.972.96 2650 10.528.34 1.053 Max. Out of Max. Out	Stone for Huristandring Aggregate - -	vitchyard	Formwork /plant	Timber/Wood	-	-	1500	-	-	25.20		Hi level estimate
Ilpond Inlet / Outlet Structure Concrete	Separation Concrete Concret							40.040.00	2.072.07	2450	10 500 04	4.050	
Illipond Inlet / Outlet Structure Rebar (Reinforcement) Rebar	Poor Inlet Outlet Structure Rebar (Reinforcement) Rebar	Rebar (Reinforcement) Rebar						13,243.20					
2 x Pre-fabricated Inlet Screen (75m x 20m) to be ste. 3	2 FPG-flaticated Inlet Screens (75m x 20m) to be joined interformation of the plant of the production of the plant of the	2 500 0.24 7750 930 3 2 Fer-fabricated Inlet Screens (75m x 20m) to be join size.						-					Concrete:Rebar Ratio: 1%
Screen (Pre-fab) Steel S	Screen (Pre-Fab) Steel Screen (Pre-Fab) Screen (Pre-Fa	Screen (Pre-fab) Steel											2 x Pre-fabricated Inlet Screens (75m x 20m) to be joined
lipond Inlet / Outlet Structure Rock Armour Rock Ro	Delivery in 2000 Steel S	Steel Stee				3	2	500	0.24	7750	930		
State Stat	Part	Call Output	ilpond Inlet / Outlet Structure	Screen (Pre-fah)	Steel							ຄາ	40mm deep
Some of the property of the			po.ia mior, Outlet situiture	sarcon (rio rab)	31001	+			0.001.70	2000	00.447.77	93	
Formwork / Plant P	pond Inlet / Outlet Structure Cofferdam - Sheet Piles Steel 585 5 488 54.00 7750 418.5 Pile Thickness: 0.0085m bepth of Embeddent: 5m bep		ilpond Inlet / Outlet Structure	Rock Armour	Rock		-	•	8,016.70	2800	22,446.76	2,245	1:3 Slope from base of Screen to EG
Ilpond Inlet / Outlet Structure Cofferdam - Sheet Piles Steel S85 5 488 54.00 7750 418.5 42 Assume that Bracing (T) = Sheet Pile (T)		Independ Independent Steel Ste				505		400	F1.00	7756	410.5		
Illpond Inlet / Outlet Structure		Illipond Inlet / Outlet Structure Cofferdam - Bracing Steel 585 5 488 54.00 7750 418.5 42 Assume that Bracing (T) - Sheet Pile (T)		Cofferdam - Sheet Piles	Steel	585	5	488	54.00	//50	418.5	42	
Ilpond Inlet / Outlet Structure Formwork / Plant Index	Plant Plan	Ilpond Inlet / Outlet Structure Formwork / Plant Plant S152 S152 S152 S152 S152 S152 S152 S152	Inond Inlet / Outlet Structure			585	5	488	54.00	7750	418.5		
Ilpond Inlet / Gate house Formwork / Plant - 5152 - 61.824 6 40% extra considered for the uncertainity in the decision of a construction of the uncertainity in the decision o	pond inlet / Outlet Structure Formwork / Plant Plant	ilipond Inlet / Outlet Structure Formwork / Plant Plant 5152 61.824 6 40% extra considered for the uncertainity in the design of the second of the uncertainity in the design of the uncertainity in the d			1				-	-			C3D Output.
ipond linet / gate house Formwork / Plant 6 40% extra considered for the uncertaintly in the d 2x Excavators 0 x Graders	pond inlet / plant Plant		lpond Inlet / Outlet Structure			1 -	-	10400	-	-	197	20	25% FOS
ipond linet / gate house Formwork / Plant 6 40% extra considered for the uncertaintly in the d 2x Excavators 0 x Graders	pond inlet / plant Plant		lpond Inlet / Outlet Structure		Plant						41.024		Î.
0 x Graders	Contract	Achinery Plant	ilpond Inlet / Outlet Structure ilpond Inlet / Outlet Structure	Formwork / Plant		-	-	5152	-		01.824		40% ovtra considered for the uncertainty in the state
0.0 7 1 1 1 1 1 1.	2 x Dump Trailers 2x Mobile Crane 2 x Dump Trailers 2x	Support Supp	ilpond Inlet / Outlet Structure ilpond Inlet / Outlet Structure	Formwork / Plant			-	5152	-		01.824	6	
22 Jump Irray Plant 22 Jump Irray Plant Plant	Inels Lining Concete Concrete 70,316.07 2400 168,758.57 18,504 400mm Concrete Lining Inels Rebar (Reinforcement) Rebar 7,316.1 7850 55,198.11 5,50 Concrete: Rebar Ratio: 1% For Stumel states (3x Access, 2x Waterways) 20x Excavators 20 x Graders 20 x Graders	nnels Lining Concete Concrete 70,316.07 2400 168,758.57 18,504 400mm Concrete Lining nnels Rebar (Reinforcement) Rebar - 7,031.61 7850 55,198.11 5,50	ilpond Inlet / Outlet Structure ilpond Inlet / Outlet Structure	Formwork / Plant				5152				6	2x Excavators 0 x Graders
	nels Rebar (Reinforcement) Rebar 7,031.61 7850 55,198.11 5,520 Concrete.Rebar Ratio: 1% For Stunders (as Cacess, 2x Waterways) 20x Excavators 20 x Graders 20 x Caders	nnels Rebar (Reinforcement) Rebar 7,031.61 7850 55,198.11 5,520 Concrete:Rebar Ratio: 1% For 5 tunnels (3x Access, 2x Waterways) 20x Excevators 20x Carders 20x Carders 20x Loaders	ilpond Inlet / Outlet Structure Ilpond Inlet / Outlet Structure Ilpond Inlet / gate house	Formwork / Plant Formwork / Plant	Plant			5152 -	-	-		6	2x Excavators 0 x Graders 2 x Dump Trailers 2x Mobile Crane
nnels Rebar (Reinforcement) Rebar 7,031.61 7850 55,198.11 5,520 Concrete:Rebar Ratio: 1%	20x Excavators 20 x Graders 20 x Graders	nnels Machinery Various 20x Excavators 20x Graders 20x Graders 20x Graders 20x Loaders 20x Loaders 50x Dump Trailers 50x Dump Trailers 22x 50x Dump Trailers 25x Best Considered for the tunnel invert, 1/2" thick pit 25x Best Considered for the tunne	ilpond Inlet / Outlet Structure ilpond Inlet / Outlet Structure ilpond Inlet / gate house ilpond Inlet / Outlet Structure	Formwork / Plant Formwork / Plant Machinery	Plant		-					16	2x Excavators 0 x Graders 2 x Dump Trailers 2x Mobile Crane 2 x Loaders
	20 x Graders 20 x Loaders	nnels Machinery Various	ilpond Inlet / Outlet Structure ilpond Inlet / Outlet Structure ilpond Inlet / gate house ilpond Inlet / Outlet Structure innels	Formwork / Plant Formwork / Plant Machinery Lining Concete	Plant Plant Concrete	+			70,316.07	2400	168,758.57	16 18,504	2x Excavators 0 x Graders 2 x Dump Trailers 2x Mobile Crane 2 x Loaders 400mm Concrete Lining Concrete:Rebar Ratio: 1%
20 x Graders	20 x Loaders	nnels Machinery Various 20 x Loaders 20 x Loaders 50 x Dump Traillers 50 x Comp Traillers 25% less considered for the tunnel invert, 1/2" thick pit	ilpond Inlet / Outlet Structure ilpond Inlet / Outlet Structure ilpond Inlet / gate house ilpond Inlet / Outlet Structure innels	Formwork / Plant Formwork / Plant Machinery Lining Concete	Plant Plant Concrete	+			70,316.07	2400	168,758.57	16 18,504	2x Excavators 0 x Graders 2 x Dump Trailers 2x Mobile Crane 2 x Loaders 400mm Concrete Lining Concrete:Rebar Ratio: 1% For 5 tumel sites (3x Access, 2x Waterways)
		25% less considered for the tunnel invert, 1/2" thick pl	ilipond Inlet / Outlet Structure ilipond Inlet / Outlet Structure ilipond Inlet / gate house ilipond Inlet / Outlet Structure nnels	Formwork / Plant Formwork / Plant Machinery Lining Concete	Plant Plant Concrete	+	-		70,316.07	2400 7850	168,758.57	16 18,504	2x Excavators 0 x Graders 2 x Dump Trailers 2x Mobile Crane 2 x Loaders 400mm Concrete Lining Concrete:Rebar Ratio: 1% For 5 turnel sites (3x Access, 2x Waterways) 20x Excavators 20 x Graders
			ilipond Inlet / Outlet Structure ilipond Inlet / Outlet Structure ilipond Inlet / gate house ilipond Inlet / Outlet Structure innels innels	Formwork / Plant Formwork / Plant Machinery Lining Concete Rebar (Reinforcement)	Plant Plant Concrete Rebar	+	-		70,316.07	2400 7850	168,758.57	16 18,504	2x Excavators 0 x Graders 2 x Dump Trailers 2x Mobile Crane 2 x Loaders 400mm Concrete Lining Concrete:Rebar Ratio: 1% For 5 tunnel sites (3x Access, 2x Waterways) 20x Excavators 20 x Graders 0 x Loaders
nnels Machinery Various 220 50 x Dump Trailers	125% less considered for the tunnel invert 1/2" thick ply	131,842.63 1,582.11 considered for the formwork system and weight 12kg/	ilipond Inlet / Outlet Structure ilipond Inlet / Outlet Structure ilipond Inlet / gate house ilipond Inlet / Outlet Structure nnels nnels	Formwork / Plant Formwork / Plant Machinery Lining Concete Rebar (Reinforcement)	Plant Plant Concrete Rebar	+	-		70,316.07	2400 7850	168,758.57	16 18,504	2x Excavators 0 x Graders 0 x Graders 2 x Dump Trailers 2x Mobile Crane 2 x Loaders 400mm Concrete Lining Concrete:Rebar Ratio: 1% For 5 tunnel sites (3x Access, 2x Waterways) 20x Excavators 20 x Graders 20 x Loaders 50 x Dump Trailers
nnels Machinery Various 20 50 x Dump Trailers 25% less considered for the tunnel invert, 1/2" thic	131,842.63 1,582.11 considered for the formwork system and weight 12kg/m	Tourney (Dept. Dept. Dept.	ilpond Inlet / Outlet Structure ilpond Inlet / Outlet Structure ilpond Inlet / gate house ilpond Inlet / Outlet Structure nnels nnels	Formwork / Plant Formwork / Plant Machinery Lining Concete Rebar (Reinforcement) Machinery	Plant Concrete Rebar Various	+		-	70,316.07 7,031.61	2400 7850	168,758.57 55,198.11	16 18,504 5,520 220	2x Excavators 0 x Graders 2 x Dump Trailers 2x Mobile Crane 2 x Loaders 400mm Concrete Lining Concrete:Rebar Ratio: 1% For 5 tunnel sites (3x Access, 2x Waterways) 20 x Excavators 20 x Graders 50 x Dump Trailers 25% less considered for the tunnel invert, 1/2" thick ply considered for the formwork system and weight 12kg/m

Assumptions
1. Quantities are high-level estiamtes and are to inform the transport assessment for the EIA
2. Vehicle trips is only for on and off site trips



Project Details

Project Name	Project Number	Document l	No.
Balliemeanoch PSH	60710998		
Created By:	Checked By:	Approved by:	
ΔC	TP	DI	

			of 2-way Trips per Month			
Task Name Duration Start	Months 1 2 3 4 5	6 7 8 9 10 11 2027	12 1 2 3 4 5 6	7 8 9 10 11 12 028	Total 0	Check = 0
Baliemeanoch PSH 114 01/10/202 PROJECT DEVELOPMENT AND DESIGN						
Environmental studies and pre-feed design 18 01/10/202 FEED design, Tendering and contract 24 14/02/202						
CIVIL WORKS Enabling Works	25 1771272020					
Existing access Improvements 6 19/01/202 General Mobilisation	27 05/07/2027 3,174 3,174 3,174 3,174 3,174	3,174			19,044 TR2 2,744 TR3 16,300	Total 19,044 0
Construction compound set up (permanent and temporary) 6	27 20/12/2027	7,399 7,399 7,399 7,399 7,399	7.399		TR7 139 TR8 4 TR13 2,063 TR18 42,159 TR11 16 TR12 12	Total 0
Safety and security measures 4 21/12/202 Burrow pit open and operation 9 06/07/202			8 8 8 8		31 TR9 1.54 TR10 1 TR14 9 TR15 12 TR16 8 TR17 1	Total 31 0
Demobilisation2301/01/203Test Audit and and confirmatory site investigations906/07/203	30 03/11/2031				312 TR21 60 TR27 16 TR55 16 TR58 220 0	Total 312 0
Form access to borrow pits 9 06/07/202 Jetty works / pontoon 12 06/07/202	27 13/03/2028 27 05/06/2028 28 29 29 29 20 20 20 20 20 20 20 20 20 20 20 20 20	89 89 89 89	89 89 89 89 89 89 89 89 89		0 1,064 TR30 43 TR31 849 TR32 158 TR33 13 TR34 1	Total 1,064 0
Upper Reservoir Form access including bridge / culverts 9 06/07/202	27 13/03/2028	2,625 2,625 2,625 2,625	2,625 2,625 2,625		0 23,623 TR1 8,427 TR4 15,097 TR5 95 TR6 4	Total 23,623 0
Removal of top soil 2 14/03/202 Construction diversion 2 14/03/202	28 08/05/2028 28 08/05/2028		38 38		76 TR21 60 TR27 16 0	Total 76 0
Stabilisation works409/05/202Void reprofiling229/08/202Foundation improvement works / grout curtain624/10/202	28 23/10/2028					
Concrete Core / concrete lining U/s face Embankment 1 construction and burrow pit operation 23 10/04/202 10/04/202	29 10/02/2031				7,680 TR19 7,457 TR20 222 3,775 TR22 3,775	Total 7,680 0 Total 3,775 0
Embankment 2 construction and burrow pit operation 12 22/10/202 Spillway Construction 9 22/10/202	28 20/09/2029				0 0	19.41
Upper reservoir Inlet and gate shaft works Lower Reservoir 17 14/03/202			340 340 340 340	340 340 340 340 340	5,772 TR23 1,842 TR24 55 TR25 3,714 TR26 71 TR28 53 TR29 37	Total 5,772 0
B840 Diversion works 4 06/07/202 Coffering inlet area 4 26/10/202	27 25/10/2027 27 14/02/2028	21	21 21 21		0 84 TR51 42 TR52 42	Total 84 0
Removal of top soil 1 26/10/202		16			16 TR55 16	Total 16 0
Upen a deep trench for gate house and birucation works Inlet shaft and Gate house 17 01/08/202	28 17/12/2029			0 0 0 0 0	0 6 TR54 6 200 TR52 2744 TR40 412 TR40 02	Total 6 0
Inlet/outlet structure 17 01/08/202 Rock excavation infront of inlet and armouring works 3 18/12/202 Dismantel coffering works and reinstating area 3 12/03/193	29 11/03/2030				3,969 TR53 20 TR47 3,744 TR48 112 TR49 93 2,245 TR50 2,245	Total 3,969 0 Total 2,245 0
Dismantel coffering works and reinstating area 3 12/03/193 Tunnelling works Form access to portal sites 2 06/07/203		110 110			0 0 220 TR58 220	Total 220 0
Form access to portal sites 2 06/07/202 Tunnel Portal - Construction 4 31/08/202 Tunnel Portal - Emergency egress 4 31/08/202		40 40 40	40		158 TR59 158 0	Total 158 0
Ancilliary works - tunnelling 4 15/02/202 Construction Tunnel	28 05/06/2028					
Tunnel excavation (D&B / TBM) - Construction2421/12/202Tunnel lining - Construction2421/12/202	27 22/10/2029					
Vertical ventilation shaft on construction tunnel621/02/202Conveyor set up and spoil transport2421/12/202						
Emergency Egress and Access Tunnel (EE&AT) Tunnel excavation (D&B / TBM) - EE&AT 24 21/12/202						
Tunnel lining -EE&AT2421/12/202Vertical ventilation shaft on emergency tunnel621/02/202Conveyor set up and spoil transport2421/12/202	29 07/08/2029					
Conveyor set up and spoil transport 24 21/12/202 Headrace Tunnel (low pressure)- HTLP 3 31/07/202						
Tunnel lining -HTLP 3 31/07/202 Conveyor set up and spoil transport 3 31/07/202	29 22/10/2029					
Surge Shaft works - SS 9 23/10/202 SS lining -HTLP 9 23/10/202	29 01/07/2030 29 01/07/2030					
Conveyor set up and spoil transport 9 23/10/202 Headrace Tunnel (high pressure) - HTHP	29 01/07/2030					
Tunnel excavation - HTHP 5 02/07/203 Tunnel lining -HTHP 5 02/07/203	30 18/11/2030					
Conveyor set up and spoil transport 5 02/07/203 Tailrace Tunnel -TT Tunnel excavation - TT from Power cavern 29 17/12/203						
Tunnel excavation - 11 from Power cavern 29 17/12/203 Tunnel lining -TT 29 17/12/203 Conveyor set up and spoil transport 29 17/12/203	30 04/04/2033				10,296 TR56 7,930 TR57 2,366	Total 10,296 0
Power Tunnel -PT Tunnel Portal -PT 4 06/07/202						
Tunnel excavation - from Tunnel Portal-PT 37 26/10/202 Tunnel lining -PT 37 26/10/202	27 18/11/2030	371	371 371 371 371 371 371 371 371	371 371 371 371 371 371	0 13,728 TR56 10,574 TR57 3,154	Total 13,728 0
Conveyor set up and spoil transport 37 26/10/202 Ventilation Tunnel - VT	27 18/11/2030					
Excavation Horizontal ventilation tunnel -HVT 12 17/12/203 Main vertical ventilation shafts 12 18/11/203	31 18/10/2032					
Short ventilation shafts 10 18/11/203 Lining -Vertical and Horizontal ventilation tunnels 24 17/12/203 Company and an all transports 24 17/12/203	30 23/10/2032					
Conveyor set up and spoil transport 24 17/12/203 Switchroom Building and HV Switchyard 6 06/07/203	30 23/10/2032	176 176 176 176 176	176		0 0 1,057 TR42 1 TR43 1 TR44 2 TR46 1,053	Total 1,057 0
Super structures 12 21/12/202 AIS Switchyard - civil 12 21/11/202	27 20/11/2028	170 170 170			0 282 TR40 274 TR41 8	Total 282 0
Powerhouse / Power Cavern Cavern excavation - Turbine hall 15 23/10/202	29 16/12/2030				0 0	
Cavern excavation - Transformaer hall923/10/202Lining and support works14.523/10/202	29 16/12/2030			1	0 23,853 TR35 120,163 TR36 3,584 TR37 67 TR38 39	Total 123,853 0
Conveyor set up and spoil transport1523/10/202Crane Structure201/07/203	31 25/08/2031					
Superstructure 11.5 17/12/203 M&E Installation	30 17/11/2031				98,228 TR35 95,302 TR36 2,843 TR37 53 TR38 31 0	Total 98,228 0
M&E installation complete Procurement and Manufacture 45 01/01/202						
Transport 17 14/06/203 Installation 24 18/11/203 Dry Commissioning 3 20/09/203	31 19/09/2033				64 TR39 64 TR45 0	Total 64 0
Dry Commissioning 3 20/09/203 Wet Commissioning 4 13/12/203 Grid Connection	33					
Grid connection 24 23/10/202 Double circuit cable 18 19/11/203						
Interface works TSO to client infrastructure Commissioning 3 19/11/203 20/09/203 4 13/12/203	33 12/12/2033					
		1 3,174 10,399 10,399 10,328 10,328 10,736 1	10,720 3,113 3,113 3,432 845 837 799	711 944 944 948 968 3	359,976	359,976 0
		144 473 473 469 469 488		32 43 43 43 44 44		
		154 154 154 154 154	154 154 154 154 154 154	154 154 154 154 154		
Daily Total Ve	ehicle Movements 298 298 298 298 298	298 627 627 623 623 642	641 296 296 310 192 192 190	186 197 197 198 198	Daily Max High-Intensity Average Daily Traffic Routine	
Daily Vehicle Mo	ovements (Balanced) 300 300 300 300 300	300 628 628 624 624 644	642 296 296 310 194 194 192	188 198 198 198 198	644 581 341 199	
Daily HGV Mov			488 142 142 156 40 40 38			
Daily Car & LGV N	Movements (Balanced) 154 154 154 154 154	154 154 154 154 154	154 154 154 154 154 154 154	154 154 154 154 154 154	154 154 154	



Project Details

Project Name	Project Number	Docur	nent No.
Balliemeanoch PSH	60710998		
Created By:	Checked By:	Approved by:	
AC	TP	DI	

								Number of 2-w	ay Trips per Month							
			Monti Yea	hs 1 2	3 4 5	6 7 2029	8 9 10	11 12	1 2 3	4 5	6 7 8	9 10	11 12 Tota			Check = 0
Task Name Baliemeanoch PSH	Duration Start	01/10/2024	sh 03/04/2034										0 0			
PROJ Environmental studies and pre-feed design	JECT DEVELOPMENT AND DESIG	01/10/2023	13/02/2025										0 0			
FEED design, Tendering and contract	24 CIVIL WORKS	14/02/2025	17/12/2026										0 0			
Enabling Works Existing access Improvements	6	19/01/2027	05/07/2027										0 19,04	4 TR2 2,744 TR3 16,300 To	Г otal 19,044	0
General Mobilisation													0			
Construction compound set up (permanent and temporary) Safety and security measures	6 4	06/07/2027 21/12/2027	20/12/2027 10/04/2028										44,39	4	Γ otal 44,394 Γ otal 31	0
Burrow pit open and operation Demobilisation	9	06/07/2027 01/01/2030	13/03/2028 03/11/2031						14 14 14	14 14	14 14 14	14 14	0 14 14 312		Г otal 312	0
Test Audit and and confirmatory site investigations Form access to borrow pits	9	06/07/2027 06/07/2027	13/03/2028 13/03/2028										0			
Jetty works / pontoon Upper Reservoir	12	06/07/2027	05/06/2028										1,06-	TR30 43 TR31 849 TR32 158 TR33 13 TR34 1	Total 1,064	0
Form access including bridge / culverts Removal of top soil	9	06/07/2027 14/03/2028	13/03/2028 08/05/2028										23,62		Γotal 23,623 Γotal 76	0
Construction diversion Stabilisation works	2	14/03/2028 09/05/2028	08/05/2028 28/08/2028										0		70	
Void reprofiling Foundation improvement works / grout curtain	2	29/08/2028 24/10/2028	23/10/2028 09/04/2029										0			
Concrete Core / concrete lining U/s face Embankment 1 construction and burrow pit operation	23	10/04/2029 10/04/2029	10/02/2031 10/02/2031		334 334 164 164	334 334 164 164	334 334 334 164 164 164	334 334 164 164	334 334 334 164 164 164	334 334 164 164	334 334 334 164 164 164	334 334 164 164	334 334 7,680 164 164 3,779	TR19 7,457 TR20 222 TR22 3,775	Γotal 7,680 Γotal 3,775	0
Embankment 2 construction and burrow pit operation Spillway Construction	12	22/10/2028 22/10/2028	20/09/2029 28/06/2029		104	104	104 104	104	101	104	101	104	0	11.22 0,770	5,775	
Upper reservoir Inlet and gate shaft works Lower Reservoir	17	14/03/2028	30/07/2029	340 340	340 340 340	340 340							5,772	TR23 1,842 TR24 55 TR25 3,714 TR26 71 TR28 53 TR29 37 T 6	Γotal 5,772	0
B840 Diversion works	4	06/07/2027	25/10/2027										0	TDE4 40 TDE0 40	Satal 94	0
Coffering inlet area Removal of top soil	1	26/10/2027 26/10/2027	14/02/2028 22/11/2027										84		Γotal 84 Γotal 16	0
Open a deep trench for gate house and bifucation works	9	23/11/2027	31/07/2028										0	TDEA 6	Total 0	
Inlet shaft and Gate house Inlet/outlet structure Pack execution infront of inlet and armouring works	17 17	01/08/2028 01/08/2028	17/12/2029 17/12/2029	233 233	0 0 0 233 233 233	233 233	0 0 0 0 233 233	233 233	740				3,96	7 TR53 20 TR47 3,744 TR48 112 TR49 93 Te	Fotal 6 Fotal 3,969 Fotal 3,245	0
Rock excavation infront of inlet and armouring works Dismantel coffering works and reinstating area	3	18/12/2029 12/03/1930	11/03/2030 03/06/2030						748 748 748				2,24	TR50 2,245	Fotal 2,245	0
Tunnelling works Form access to portal sites	2	06/07/2027	30/08/2027										0 220	TR58 220 To	Total 220	0
Tunnel Portal - Construction Tunnel Portal - Emergency egress	4 4	31/08/2027 31/08/2027	20/12/2027 20/12/2027										158	TR59 158	Fotal 158	0
Ancilliary works - tunnelling Construction Tunnel	4	15/02/2028	05/06/2028										0 0			
Tunnel excavation (D&B / TBM) - Construction Tunnel lining -Construction	24 24	21/12/2027 21/12/2027	22/10/2029 22/10/2029										0 0			
Vertical ventilation shaft on construction tunnel Conveyor set up and spoil transport	6 24	21/02/2029 21/12/2027	07/08/2029 22/10/2029										0 0			
Emergency Egress and Access Tunnel (EE&AT) Tunnel excavation (D&B / TBM) - EE&AT	24	21/12/2027	22/10/2029										0 0			
Tunnel lining -EE&AT Vertical ventilation shaft on emergency tunnel	6	21/12/2027 21/02/2029	22/10/2029 07/08/2029										0 0			
Conveyor set up and spoil transport Headrace Tunnel (low pressure)- HTLP	24	21/12/2027	22/10/2029										0 0			
Tunnel excavation - HTLP Tunnel lining -HTLP	3 3	31/07/2029 31/07/2029	22/10/2029 22/10/2029										0 0			
Conveyor set up and spoil transport Surge Shaft works - SS	9	31/07/2029 23/10/2029	22/10/2029 01/07/2030										0 0			
SS lining -HTLP Conveyor set up and spoil transport	9	23/10/2029 23/10/2029	01/07/2030 01/07/2030										0 0			
Headrace Tunnel (high pressure) - HTHP Tunnel excavation - HTHP	5	02/07/2030	18/11/2030										0			
Tunnel lining -HTHP Conveyor set up and spoil transport	5	02/07/2030 02/07/2030	18/11/2030 18/11/2030										0			
Tailrace Tunnel -TT Tunnel excavation - TT from Power cavern	29	17/12/2030	04/04/2033										0 0			
Tunnel lining -TT Conveyor set up and spoil transport	29 29	17/12/2030 17/12/2030	04/04/2033 04/04/2033										355 10,29	TR56 7,930 TR57 2,366	Total 10,296	0
Power Tunnel -PT Tunnel Portal -PT	4	06/07/2027	25/10/2027										0 0			
Tunnel excavation - from Tunnel Portal-PT Tunnel lining -PT	37 37	26/10/2027 26/10/2027	18/11/2030 18/11/2030	371 371	371 371 371	371 371	371 371 371	371 371	371 371 371	371 371	371 371 371	371 371	0 371 13,72	8 TR56 10,574 TR57 3,154 T	Fotal 13,728	0
Conveyor set up and spoil transport Ventilation Tunnel - VT	37	26/10/2027	18/11/2030										0			
Excavation Horizontal ventilation tunnel -HVT Main vertical ventilation shafts	12 12	17/12/2030 18/11/2031	17/11/2031 18/10/2032										0 0			
Short ventilation shafts Lining -Vertical and Horizontal ventilation tunnels	10 24	18/11/2031 17/12/2030	23/08/2032 23/10/2032										0 0			
Conveyor set up and spoil transport Switchroom Building and HV Switchyard	24	17/12/2030	23/10/2032										0			
Ground works Super structures	6 12	06/07/2027 21/12/2027	20/12/2027 20/11/2028										1,05	7 TR42 1 TR43 1 TR44 2 TR46 1,053 Te	Total 1,057	0
AIS Switchyard - civil Powerhouse / Power Cavern	12	21/11/2028	22/10/2029	23 23	23 23 23	23 23	23 23 23						282	TR40 274 TR41 8	Total 282	0
Cavern excavation - Turbine hall Cavern excavation - Transformaer hall	15 9	23/10/2029 23/10/2029	16/12/2030 01/07/2030										0 0			
Lining and support works Conveyor set up and spoil transport	14.5 15	23/10/2029 23/10/2029	16/12/2030 16/12/2030				8542	8542 8542	8542 8542 8542	8542 8542	8542 8542 8542	8542 8542	8542 4271 123,88	TR35 120,163 TR36 3,584 TR37 67 TR38 39	Fotal 123,853	0
Crane Structure Superstructure	2 11.5	01/07/2031 17/12/2030	25/08/2031 17/11/2031										0 4271 98,22	8 TR35 95,302 TR36 2,843 TR37 53 TR38 31 T 6	Fotal 98,228	0
	M&E Installation												0			
M&E installation complete Procurement and Manufacture Transport	45	01/01/2027	13/06/2030								4 4 4	A	0 0	TR39 64 TR45 0	Cotal 64	^
Transport Installation Dry Commissioning	24	14/06/2030 18/11/2031	30/10/2031 19/09/2033								4 4	4 4	4 64 0	TR39 64 TR45 0	Fotal 64	U
Dry Commissioning Wet Commissioning Crid Composition	4	20/09/2033 13/12/2033	12/12/2033 03/04/2034										0			
Grid Connection Grid substation	24	23/10/2029	25/08/2031										0			
Double circuit cable Interface works TSO to client infrastructure	18 3	19/11/2030 20/09/2033	05/04/2032 12/12/2033										0			
Commissioning	4	13/12/2033	03/04/2034										0			
		Total Monthly HGV M			968 1,466 1,466									76	359,976	0
		Daily HGV move		44 44		*					429 429 429		<u> </u>			
		Daily Worker Car & LGV					154 154 154					154 154				
		Daily Total Vehicle IV			198 221 221	1			616 616 616			<u>'</u>	583 582	Daily Max High-Intensity Average Daily Traffic Routine		
		Daily Vehicle Movemer		•	198 222 222								· · · · · · · · · · · · · · · · · · ·	644 581 341 199		
		Daily HGV Movement			44 68 68								<u> </u>	490 427 187 45		
		Daily Car & LGV Moveme	ents (Balanced)	154 154	154 154 154	154 154	154 154 154	154 154	154 154 154	154 154	154 154 154	154 154	154 154	154 154 154		



Project Details

Project Name

Balliemeanoch PSH

Created By:

AC Project Number Docu
60710998

Checked By: Approved by:
TP DL

								Number of 2-way Trips per Month									
Task Namo	Duration	Start Finish	Mont Yea	hs 1 2 r	3	2031	10	11 12 1 2 3	4	5	6 7 8 9 10 11	12	2033	Total			Check = 0
Baliemeanoch PSH	114 CT DEVELOPMENT AND D	01/10/2024	03/04/2034											0			
Environmental studies and pre-feed design FEED design, Tendering and contract	18	01/10/2023 14/02/2025	13/02/2025 17/12/2026											0			
Enabling Works	CIVIL WORKS	1,702,2323												0			
Existing access Improvements General Mobilisation	6	19/01/2027	05/07/2027											19,044	TR2 2,744 TR3 16,300 Total	19,044	0
Construction compound set up (permanent and temporary)	6	06/07/2027	20/12/2027											44,394	TR7 139 TR8 4 TR13 2,063 TR18 42,159 TR11 16 TR12 12 Total	44,394	0
Safety and security measures Burrow pit open and operation	9	21/12/2027 06/07/2027	10/04/2028 13/03/2028											31 0	TR9 1.54 TR10 1 TR14 9 TR15 12 TR16 8 TR17 1 Total		0
Demobilisation Test Audit and and confirmatory site investigations	9	01/01/2030 06/07/2027 06/07/2027	03/11/2031 13/03/2028 13/03/2028	14 14	14	14 14 14 14 14 14	14	14						312	TR21 60 TR27 16 TR55 16 TR58 220 Total	312	0
Form access to borrow pits Jetty works / pontoon Upper Reservoir	12	06/07/2027	05/06/2028											1,064	TR30 43 TR31 849 TR32 158 TR33 13 TR34 1 Total	1,064	0
Form access including bridge / culverts Removal of top soil	9 2	06/07/2027 14/03/2028	13/03/2028 08/05/2028											23,623	TR1 8,427 TR4 15,097 TR5 95 TR6 4 Total TR21 60 TR27 16 Total	23,623 76	0
Construction diversion Stabilisation works	2 4	14/03/2028 09/05/2028	08/05/2028 28/08/2028											0 0			
Void reprofiling Foundation improvement works / grout curtain	2 6	29/08/2028 24/10/2028	23/10/2028 09/04/2029											0			
Concrete Core / concrete lining U/s face Embankment 1 construction and burrow pit operation	23 23	10/04/2029 10/04/2029	10/02/2031 10/02/2031	334 334 164 164										7,680 3,775	TR19 7,457 TR20 222 TR22 3,775 Total	7,680 3,775	0 0
Embankment 2 construction and burrow pit operation Spillway Construction	12 9	22/10/2028 22/10/2028	20/09/2029 28/06/2029											0			
Upper reservoir Inlet and gate shaft works Lower Reservoir B840 Diversion works	17	14/03/2028	30/07/2029											5,772	TR23 1,842 TR24 55 TR25 3,714 TR26 71 TR28 53 TR29 37 Total	5,772	0
Coffering inlet area	4	26/10/2027 26/10/2027	25/10/2027 14/02/2028											0 84 16	TR51 42 TR52 42 Total	84	0
Removal of top soil Open a deep trench for gate house and bifucation works	9	26/10/2027 23/11/2027	22/11/2027 31/07/2028											0	TR55 16 Total	16	O O
Inlet shaft and Gate house Inlet/outlet structure	17	01/08/2028 01/08/2028	17/12/2029 17/12/2029											6 3,969	TR54 6 Total TR53 20 TR47 3,744 TR48 112 TR49 93 Total	6 3,969	0
Rock excavation infront of inlet and armouring works Dismantel coffering works and reinstating area	3 3	18/12/2029 12/03/1930	11/03/2030 03/06/2030											2,245	TR50 2,245 Total	2,245	0
Tunnelling works Form access to portal sites	2	06/07/2027	30/08/2027											0 220	TR58 220 Total	220	0
Tunnel Portal - Construction Tunnel Portal - Emergency egress	4 4	31/08/2027 31/08/2027	20/12/2027 20/12/2027											158 0	TR59 158	158	0
Ancilliary works - tunnelling Construction Tunnel	4	15/02/2028	05/06/2028											0			
Tunnel excavation (D&B / TBM) - Construction Tunnel lining -Construction	24 24	21/12/2027 21/12/2027	22/10/2029 22/10/2029											0			
Vertical ventilation shaft on construction tunnel Conveyor set up and spoil transport	6 24	21/02/2029 21/12/2027	07/08/2029 22/10/2029											0			
Emergency Egress and Access Tunnel (EE&AT) Tunnel excavation (D&B / TBM) - EE&AT	24	21/12/2027	22/10/2029											0			
Tunnel lining -EE&AT Vertical ventilation shaft on emergency tunnel Conveyor set up and spell transport	6	21/12/2027 21/02/2029	22/10/2029 07/08/2029 22/10/2029											0			
Conveyor set up and spoil transport Headrace Tunnel (low pressure)- HTLP Tunnel excavation - HTLP	24	21/12/2027	22/10/2029											0			
Tunnel lining -HTLP Conveyor set up and spoil transport	3 3	31/07/2029 31/07/2029	22/10/2029 22/10/2029 22/10/2029											0			
Surge Shaft works - SS SS lining -HTLP	9	23/10/2029 23/10/2029	01/07/2030 01/07/2030											0			
Conveyor set up and spoil transport Headrace Tunnel (high pressure) - HTHP	9	23/10/2029	01/07/2030											0			
Tunnel excavation - HTHP Tunnel lining -HTHP	5 5	02/07/2030 02/07/2030	18/11/2030 18/11/2030											0			
Conveyor set up and spoil transport Tailrace Tunnel -TT	5	02/07/2030	18/11/2030											0			
Tunnel excavation - TT from Power cavern Tunnel lining -TT	29 29	17/12/2030 17/12/2030	04/04/2033 04/04/2033	355 355	355 3	55 355 355 355 355	355	355 355 355 355	355	355	355 355 355 355 355	355	355 355	0 10,296	TR56 7,930 TR57 2,366 Total	10,296	0
Conveyor set up and spoil transport Power Tunnel -PT Tunnel Portal -PT	4	17/12/2030 06/07/2027	04/04/2033 25/10/2027											0			
Tunnel excavation - from Tunnel Portal-PT Tunnel lining -PT	37	26/10/2027 26/10/2027 26/10/2027	18/11/2030 18/11/2030											0	TR56 10,574 TR57 3,154 Total	13,728	
Conveyor set up and spoil transport Ventilation Tunnel - VT	37	26/10/2027	18/11/2030											0	100 10,014 1107 0,104	10,720	
Excavation Horizontal ventilation tunnel -HVT Main vertical ventilation shafts	12 12	17/12/2030 18/11/2031	17/11/2031 18/10/2032											0			
Short ventilation shafts Lining -Vertical and Horizontal ventilation tunnels	10 24	18/11/2031 17/12/2030	23/08/2032 23/10/2032											0			
Conveyor set up and spoil transport Switchroom Building and HV Switchyard	24	17/12/2030	23/10/2032											0			
Ground works Super structures	6 12	06/07/2027 21/12/2027	20/12/2027 20/11/2028											0		1,057	0
AIS Switchyard - civil Powerhouse / Power Cavern	12	21/11/2028	22/10/2029											282	TR40 274 TR41 8 Total	282	0
Cavern excavation - Turbine hall Cavern excavation - Transformaer hall Lining and support works	9	23/10/2029 23/10/2029 23/10/2029	16/12/2030 01/07/2030 16/12/2030											0 23,853	TR35 120,163 TR36 3,584 TR37 67 TR38 39 Total	123,853	0
Lining and support works Conveyor set up and spoil transport Crane Structure	15	23/10/2029 23/10/2029 01/07/2031	16/12/2030 16/12/2030 25/08/2031											0	100 120,103 1030 3,304 1031 01 1030 39	123,633	
Superstructure	11.5 M&E Installation	17/12/2030	17/11/2031	8542 8542	8542 85	542 8542 8542 8542 8542 8542	8542	8542						98,228	TR35 95,302 TR36 2,843 TR37 53 TR38 31 Total	98,228	0
M&E installation complete Procurement and Manufacture	45	01/01/2027	13/06/2030											0			
Transport Installation	17 24	14/06/2030 18/11/2031	30/10/2031 19/09/2033	4 4	4	4 4 4 4 4	4							64	TR39 64 TR45 0 Total	64	0
Dry Commissioning Wet Commissioning	3 4	20/09/2033 13/12/2033	12/12/2033 03/04/2034											0			
Grid Connection Grid substation	24	23/10/2029	25/08/2031											0			
Double circuit cable Interface works TSO to client infrastructure	18	19/11/2030 20/09/2033	05/04/2032 12/12/2033											0 0			
Commissioning	4	13/12/2033	03/04/2034											0			
		Total Monthly HGV Mov				914 8,914 8,914 8,914 8,914 8,914				355			355 355	359,976		359,976	0
		Daily HGV moveme						405 16 16 16 16		16			<u> </u>				
		Daily Worker Car & LGV M				54 154 154 154 154 154											
		Daily Total Vehicle Mov				59 559 559 559 559				170	170 170 170 170 170 170 170		170 170		Daily Max High-Intensity Average Daily Traffic Routine		
		Daily Vehicle Movements				60 560 560 560 560 560				172	172 172 <td></td> <td>172 172</td> <td></td> <td>644 581 341 199</td> <td></td> <td></td>		172 172		644 581 341 199		
		Daily HGV Movements (E				06 406 406 406 406 406 54 154 154 154 154 154	•					*	-		490 427 187 45 154 154 154 154		
		Daily Car & LGV Movements	s (baiailleu)	104 154	104	on 104 104 154 154 154 154 154 154 154 154 154 154 154 154 154 154 154 154	154	104 104 154 154	154	104	154 154 154 154 154 154	104	104 154		154 154 154		




Project Details

Project Name	Project Number	Docum	nent No.
Balliemeanoch PSH	60710998		
Created By:	Checked By:	Approved by:	
AC	TP	DI	

		_														
			Monti	ths 1 2	3 4 5	6 7	8 9 10		ay Trips per Month 1 2 3	4 5	6 7 8	9 10	11 12 Total			Check = 0
Task Name	Duration S	Start Fin	Year	ar		2033					2034		0			
Baliemeanoch PSH	114 ECT DEVELOPMENT AND D	01/10/2024	03/04/2034										0			
Environmental studies and pre-feed design	18	01/10/2023	13/02/2025										0			
FEED design, Tendering and contract	CIVIL WORKS	14/02/2025	17/12/2026										0 0			
Enabling Works Existing access Improvements	6	19/01/2027	05/07/2027										0 19,04	4 TR2 2,744 TR3 16,300 Total	l 19,044	0
General Mobilisation													0			
Construction compound set up (permanent and temporary) Safety and security measures	6	06/07/2027 21/12/2027	20/12/2027 10/04/2028										44,39	TR7 139 TR8 4 TR13 2,063 TR18 42,159 TR11 16 TR12 12 Total TR9 1.54 TR10 1 TR14 9 TR15 12 TR16 8 TR17 1 Total	44,394	0
Burrow pit open and operation Demobilisation	9	06/07/2027 01/01/2030	13/03/2028 03/11/2031										0 312			0
Test Audit and and confirmatory site investigations	9	06/07/2027	13/03/2028										0	TR21 60 TR27 16 TR55 16 TR58 220 Total	l 312	
Form access to borrow pits Jetty works / pontoon	12	06/07/2027 06/07/2027	13/03/2028 05/06/2028										1,064	TR30 43 TR31 849 TR32 158 TR33 13 TR34 1 Total	ıl 1,064	0
Upper Reservoir Form access including bridge / culverts	9	06/07/2027	13/03/2028										23,62		l 23,623	0
Removal of top soil Constrruction diversion	2 2	14/03/2028 14/03/2028	08/05/2028 08/05/2028										76 0	TR21 60 TR27 16 Total	l 76	0
Stabilisation works Void reprofiling	2	09/05/2028 29/08/2028	28/08/2028 23/10/2028										0 0			
Foundation improvement works / grout curtain Concrete Core / concrete lining U/s face	6 23	24/10/2028 10/04/2029	09/04/2029 10/02/2031										7,680			0
Embankment 1 construction and burrow pit operation Embankment 2 construction and burrow pit operation	23 12	10/04/2029 22/10/2028	10/02/2031 20/09/2029										3,775	5 TR22 3,775 Total	d 3,775	0
Spillway Construction Upper reservoir Inlet and gate shaft works	9	22/10/2028 14/03/2028	28/06/2029 30/07/2029										0 5,772	2 TR23 1,842 TR24 55 TR25 3,714 TR26 71 TR28 53 TR29 37 Total	l 5,772	0
Lower Reservoir B840 Diversion works	4	06/07/2027	25/10/2027										0 0			
Coffering inlet area Removal of top soil	4	26/10/2027 26/10/2027 26/10/2027	14/02/2028 22/11/2027										84 16	11.02	l 84 l 16	0
Open a deep trench for gate house and bifucation works	9	23/11/2027	31/07/2028										10	Total		
Inlet shaft and Gate house Inlet/outlet structure	17	01/08/2028 01/08/2028	17/12/2029 17/12/2029										6 3,969	TR54 6 Total 7 TR53 20 TR47 3,744 TR48 112 TR49 93 Total 7 Tot		0
Rock excavation infront of inlet and armouring works	3	18/12/2029	11/03/2030												3,969 I 2,245	0
Dismantel coffering works and reinstating area Tunnelling works	3	12/03/1930	03/06/2030										0 0			
Form access to portal sites Tunnel Portal - Construction	4	06/07/2027 31/08/2027	30/08/2027 20/12/2027										220 158	TR58 220 Total TR59 158 Total	l 220 l 158	0
Tunnel Portal - Emergency egress Ancilliary works - tunnelling	4 4	31/08/2027 15/02/2028	20/12/2027 05/06/2028										0 0			
Construction Tunnel Tunnel excavation (D&B / TBM) - Construction	24	21/12/2027	22/10/2029										0 0			
Tunnel lining -Construction Vertical ventilation shaft on construction tunnel	6	21/12/2027 21/02/2029	22/10/2029 07/08/2029										0 0			
Conveyor set up and spoil transport Emergency Egress and Access Tunnel (EE&AT)	24	21/12/2027	22/10/2029										0 0			
Tunnel excavation (D&B / TBM) - EE&AT Tunnel lining -EE&AT	24	21/12/2027 21/12/2027	22/10/2029 22/10/2029										0			
Vertical ventilation shaft on emergency tunnel Conveyor set up and spoil transport	6 24	21/02/2029 21/12/2027	07/08/2029 22/10/2029										0			
Headrace Tunnel (low pressure)- HTLP Tunnel excavation - HTLP	3	31/07/2029	22/10/2029										0			
Tunnel lining -HTLP	3	31/07/2029 31/07/2029 31/07/2029	22/10/2029 22/10/2029 22/10/2029										0			
Conveyor set up and spoil transport Surge Shaft works - SS	9	23/10/2029	01/07/2030										0			
SS lining -HTLP Conveyor set up and spoil transport	9	23/10/2029 23/10/2029	01/07/2030 01/07/2030										0			
Headrace Tunnel (high pressure) - HTHP Tunnel excavation - HTHP	5	02/07/2030	18/11/2030										0			
Tunnel lining -HTHP Conveyor set up and spoil transport	5 5	02/07/2030 02/07/2030	18/11/2030 18/11/2030										0 0			
Tailrace Tunnel -TT Tunnel excavation - TT from Power cavern	29	17/12/2030	04/04/2033										0 0			
Tunnel lining -TT Conveyor set up and spoil transport	29 29	17/12/2030 17/12/2030	04/04/2033 04/04/2033	355 355	355 355								10,29	6 TR56 7,930 TR57 2,366 Total	l 10,296	0
Power Tunnel -PT Tunnel Portal -PT	4	06/07/2027	25/10/2027										0 0			
Tunnel excavation - from Tunnel Portal-PT Tunnel lining -PT	37 37	26/10/2027 26/10/2027	18/11/2030 18/11/2030										0 13,72	8 TR56 10,574 TR57 3,154 Total	l 13,728	0
Conveyor set up and spoil transport Ventilation Tunnel - VT	37	26/10/2027	18/11/2030										0 0			
Excavation Horizontal ventilation tunnel -HVT Main vertical ventilation shafts	12	17/12/2030 18/11/2031	17/11/2031 18/10/2032										0			
Short ventilation shafts Lining -Vertical and Horizontal ventilation tunnels	10	18/11/2031 17/12/2030	23/08/2032 23/10/2032										0			
Conveyor set up and spoil transport Switchroom Building and HV Switchyard	24	17/12/2030	23/10/2032										0			
Ground works Super structures	6 12	06/07/2027 21/12/2027	20/12/2027 20/11/2028										1,057	7 TR42 1 TR43 1 TR44 2 TR46 1,053 Total	1,057	0
AIS Switchyard - civil	12	21/11/2028	22/10/2029										282	TR40 274 TR41 8	l 282	0
Powerhouse / Power Cavern Cavern excavation - Turbine hall Cavern excavation - Transformers hall	15	23/10/2029	16/12/2030										0			
Cavern excavation - Transformaer hall Lining and support works	9 14.5	23/10/2029 23/10/2029	01/07/2030 16/12/2030										123,85	TR35 120,163 TR36 3,584 TR37 67 TR38 39 Total	l 123,853	0
Conveyor set up and spoil transport Crane Structure	15 2	23/10/2029 01/07/2031	16/12/2030 25/08/2031										0 0			
Superstructure	11.5 M&E Installation	17/12/2030	17/11/2031										98,226	8 TR35 95,302 TR36 2,843 TR37 53 TR38 31 Total	l 98,228	0
M&E installation complete Procurement and Manufacture	45	01/01/2027	13/06/2030										0 0			
Transport Installation	17	14/06/2030 18/11/2031	30/10/2031 19/09/2033										64	TR39 64 TR45 0	l 64	0
Dry Commissioning Wet Commissioning	3 4	20/09/2033 13/12/2033	12/12/2033 03/04/2034										0			
Grid Connection	,												0			
Grid substation Double circuit cable	18	23/10/2029 19/11/2030	25/08/2031 05/04/2032										0 0			
Interface works TSO to client infrastructure Commissioning	3 4	20/09/2033 13/12/2033	12/12/2033 03/04/2034										0 0			
		Total Monthly HGV I	Movements*	355 355	355 355 0	0 0	0 0 0	0 0	0 0 0	0 0	0 0 0	0 0	0 0 359,97	76	359,976	0
		Daily HGV mov		16 16	16 16 0	0 0	0 0 0	0 0	0 0 0	0 0	0 0 0	0 0	0 0			
		Daily Worker Car & LG			154 154 154	154 154	154 154 154	· '	154 154 154		154 154 154	154 154				
		Daily Total Vehicle				154 154			154 154 154			154 154		Daily Max High-Intensity Average Daily Traffic Routine		
		Daily Vehicle Moveme	·								154 154 154			644 581 341 199		
		Daily HGV Movemer			18 18 0									490 427 187 45		
		Daily Car & LGV Moven	· · · · · · · · · · · · · · · · · · ·										154 154			
		Daily Cal & LGV IVIOVEN	ויטווט (שמומווגכע)	10 4 154	10 4 104 154	154 154	j 194 154 154	104 154	10 4 154 154	154 154	10 4 154 154	10 4 154	104 104	154 154 154		

Annex G- Marine Facility



AECOM

PROJEC

Balliemeanoch
Pumped Storage Hydro

CLIENT

ILI (Borders PSH) Ltd.

The Shires, 33 Bothwell Road Hamilton, ML3 0AS

CONSULTANT

AECOM
1 Tanfield
Edinburgh, EH3 5DA
+44 (0) 131 301 8600 tel 8699 fax
www.AECOM.com

LEGEND

RED LINE BOUNDARY

— — EXISTING GROUND LEVEL

MEAN HIGH WATER SPRING (MHWS)

—— MEAN LOW WATER SPRING (MLWS)

NOTES

- DRAWING IS FOR INDICATIVE PURPOSES
- 2. 600mm Ø PILES SHOWN INDICATIVELY IN 5m x 5m ARRANGEMENT. FINAL ARRANGEMENT, DIAMETER AND DEPTH OF PILES TO BE CONFIRMED AT DETAILED DESIGN STAGE.
- 3. JETTY DECK SHOWN INDICATIVELY AS 600mm DEEP PRE-FABRICATED STEEL BRIDGE. FINAL ARRANGEMENT TO BE CONFIRMED AT DETAILED DESIGN STAGE.
- 4. MAKEUP OF EXISTING A83 UNKNOWN AT THIS STAGE.
- 5. TRANSPORT VEHICLE TO CROSS A83 SUBJECT TO TRAFFIC MANAGEMENT.

APPROVED FOR ISSUE

A	AC	DL	
I/F	DRAWN BY	CHECKED	APPROVED

ISSUE/REVISION

r liedy			
3	Α	09.11.2023	DESIGN FREEZE
OIGH.	I/R	DATE	DESCRIPTION
D			

SHEET TITLE


BALLIEMEANOCH PSH ZONE 2 - TEMPORARY JETTY PLAN & SECTION


SHEET NUMBER

S03-Z2-06-DR-CE-326301

Annex H - B840 Realignment







GI	RADIENTS @ 20	00m INCREMEN	TS
RANGE	Level 1 (mAOD)	Level 2 (mAOD)	GRADIENT (%)
0 - 200m	43.7	53	4.7
200m - 400m	53	61.8	4.4
400m - 600m	61.8	71	4.6
600m - 800m	71	75	2
800m - 1,000m	75	76	2.5
1,000m - 1,200m	76	61.6	(-) 7.2
1,200m - 1,400m	61.6	41.6	(-) 10
1,400m - 1,492m	41.6	43.4	(-) 2

A B840 DIVERSION LONGSECTION

NOT FOR CONSTRUCTION FOR INFORMATION ONLY

AECOM

PROJECT

Balliemeanoch Pumped Storage Hydro

CLIENT

ILI (Borders PSH) Ltd.

The Shires, 33 Bothwell Road Hamilton, ML3 0AS

CONSULTANT

AECOM 1 Tanfield Edinburgh, EH3 5DA +44 (0) 131 301 8600 tel 8699 fax www.AECOM.com

LEGEND

RED LINE BOUNDARY

EXISTING B840 PUBLIC ROAD

B840 DIVERSION - NEW ACCESS TRACK B840 DIVERSION - NEW ACCESS TRACK

EARTHWORKS EXTENT

CUT/FILL TADPOLES

TRACK / DITCH EXTENTS

- DRAWING IS FOR INDICATIVE PURPOSES
- 2. EXISTING FARMER'S TRACK TO BE WIDENED TO ACCOMMODATE TEMPORARY B-ROAD TRAFFIC
- 3. ALIGNMENTS BASED ON 5m DTM AND OS MASTERMAP. ANY DISCREPANCIES BASED ON MAPPING IS PURELY VISUAL
- ACCESS TRACK TO THE NORTH SHOWN INDICATIVELY FOR REFERENCE



APPROVED FOR ISSUE

) po				
onpc				
reproduced	Α	AC	ST	
dified,	I/R	DRAWN BY	CHECKED	APPROVED
ਰ				

ISSUE/REVISION



SHEET TITLE

BALLIEMEANOCH PSH B840 ROAD DIVERSION PLAN & LONG SECTION

SHEET NUMBER

S03-Z1-02-DR-CE-312301

Annex I - Fear and Intimidation

Baseline Fear and Intimidation Level

		Average traffic flow over	Total 18-hour heavy	Average Vehicle	Degree of Hazard	Degree of Hazard	Degree of Hazard	Degree of Hazard	Level of Fear and	
Road Link	18 Hour Flow	18 hour day	vehicle flow	Speed	Score A	Score B	Score C	Score Total	Intimdiation	Magnitude of Change
A85 Taynuilt	5,078	282	157	33	0	0	20	20	Small	
A85 West	4,361	242	131	47	0	0	30	30	Moderate	
A85 East	3,874	215	134	43	0	0	30	30	Moderate	
B840 Cladich	351	20	8	24	0	0	10	10	Small	
A819 Dalmally	1,605	89	65	49	0	0	30	30	Moderate	
Site Access Track	0	0	0	0	0	0	0	0	Small	
A819 Site Access	1,658	92	68	52	0	0	30	30	Moderate	
A819 Inveraray	1,664	92	65	55	0	0	30	30	Moderate	
A819 Inveraray Town Centre	1,807	100	66	40	0	0	20	20	Small	
Inveraray Bypass	0	0	0	0	0	0	0	0	Small	
A83 Aray Bridge	4,202	233	173	34	0	0	20	20	Small	
A83 Garron Bridge	4,096	228	160	49	0	0	30	30	Moderate	
A83 Rest and Be Thankful	4,573	254	239	41	0	0	30	30	Moderate	
A815 Strachur	2,295	128	91	39	0	0	20	20	Small	
A83 Inveraray Town Centre	3,666	204	44	25	0	0	10	10	Small	
Upper Avenue AIL Route	0	0	0	0	0	0	0	0	Small	
A83 Lochgilphead	3,434	191	168	46	0	0	30	30	Moderate	
B840 Ford	171	10	2	25	0	0	10	10	Small	


Proposed Development Magnitude of Change


	J	Average traffic flow over	Total 18-hour heavy	Average Vehicle	Degree of Hazard	Degree of Hazard	Degree of Hazard	Degree of Hazard	Level of Fear and	
Road Link	18 Hour Flow	18 hour day	vehicle flow	Speed	Score A	Score B	Score C	Score Total	Intimdiation	Magnitude of Change
A85 Taynuilt	5,722	318	647	33	0	0	20	20	Small	Negligible
A85 West	5,005	278	621	47	0	0	30	30	Moderate	Negligible
A85 East	4,518	251	624	43	0	0	30	30	Moderate	Negligible
B840 Cladich	505	28	8	24	0	0	10	10	Small	Negligible
A819 Dalmally	2,249	125	555	49	0	0	30	30	Moderate	Negligible
Site Access Track	644	36	490	0	0	0	0	0	Small	Negligible
A819 Site Access	2,302	128	558	52	0	0	30	30	Moderate	Negligible
A819 Inveraray	2,308	128	555	55	0	0	30	30	Moderate	Negligible
A819 Inveraray Town Centre	1,961	109	66	40	0	0	20	20	Small	Negligible
Inveraray Bypass	490	27	490	0	0	0	0	0	Small	Negligible
A83 Aray Bridge	4,356	242	173	34	0	0	20	20	Small	Negligible
A83 Garron Bridge	4,740	263	650	49	0	0	30	30	Moderate	Negligible
A83 Rest and Be Thankful	5,217	290	729	41	0	0	30	30	Moderate	Negligible
A815 Strachur	2,939	163	581	39	0	0	20	20	Small	Negligible
A83 Inveraray Town Centre	3,820	212	44	25	0	0	10	10	Small	Negligible
Upper Avenue AIL Route	0	0	0	0	0	0	0	0	Small	Negligible
A83 Lochgilphead	4,078	227	658	46	0	0	30	30	Moderate	Negligible
B840 Ford	325	18	2	25	0	0	10	10	Small	Negligible


Cumulative Development Magnitude of Change

		Average traffic flow over	Total 18-hour heavy	Average Vehicle	Degree of Hazard	Degree of Hazard	Degree of Hazard	Degree of Hazard	Level of Fear and	
Road Link	18 Hour Flow	18 hour day	vehicle flow	Speed	Score A	Score B	Score C	Score Total	Intimdiation	Magnitude of Change
A85 Taynuilt	6,540	363	1,322	33	0	10	20	30	Moderate	Medium
A85 West	6,021	335	1,420	47	0	10	30	40	Moderate	Negligible
A85 East	5,773	321	1,464	43	0	10	30	40	Moderate	Negligible
B840 Cladich	516	29	6	24	0	0	10	10	Small	Negligible
A819 Dalmally	3,439	191	1,283	49	0	10	30	40	Moderate	Negligible
Site Access Track	644	36	490	0	0	0	0	0	Small	Negligible
A819 Site Access	3,853	214	1,503	52	0	10	30	40	Moderate	Negligible
A819 Inveraray	3,859	214	1,496	55	0	10	30	40	Moderate	Negligible
A819 Inveraray Town Centre	3,545	197	1,007	40	0	10	20	30	Moderate	Low
Inveraray Bypass	490	27	490	0	0	0	0	0	Small	Negligible
A83 Aray Bridge	5,223	290	608	34	0	0	20	20	Small	Negligible
A83 Garron Bridge	5,612	312	1,081	49	0	10	30	40	Moderate	Negligible
A83 Rest and Be Thankful	5,374	299	866	41	0	0	30	30	Moderate	Negligible
A815 Strachur	3,124	174	618	39	0	0	20	20	Small	Negligible
A83 Inveraray Town Centre	4,886	271	550	25	0	0	10	10	Small	Negligible
A83 Lochgilphead	5,116	284	1,329	46	0	10	30	40	Moderate	Negligible
B840 Ford	341	19	2	25	0	0	10	10	Small	Negligible


Annex J - Swept Path Analysis











AECOM


Balliemeanoch Pumped Storage Hydro

ILI (Borders PSH) Ltd. The Shire, 33 Bothwell Road Hamilton, MI3 0AS

AECOM 1 Tanfield EDINBURGH, EH3 5DA +44 (0) 131 301 8600 tel +44 (0) 131 301 8699 fax www.aecom.com





A 2024-02-26 FIRST ISSUE I/R DATE DESCRIPTION




PORT TO SITE ACCESS EGRESS











Contains Ordnance Survey data © Crown copyright and database right 2024 Ordnance Survey 0100031673



PROJECT


Balliemeanoch
Pumped Storage Hydro

CLIENT


ILI (Borders PSH) Ltd.
The Shire, 33 Bothwell Road
Hamilton, MI3 0AS

CONSULTANT

AECOM 1 Tanfield EDINBURGH, EH3 5DA +44 (0) 131 301 8600 tel +44 (0) 131 301 8699 fax www.aecom.com



ISSUE/REVISION



A 2024-02-26 FIRST ISSUE

I/R DATE DESCRIPTION

KEY PLAN





SHEET TITLE

A85-A819 TRACKING

SHEET NIIMBED

SHEET NUMBER
S03-Z0-02-DR-TR-302210





Annex K – Cumulative Development

Road Link	Crua	chan II Hydro Sc	heme	Bla	arghour Wind Fa	rm	Upper Sonachan Wind Farm			Ladyfield Wind Farm		
	HGVs	Cars / Vans	Total	HGVs	Cars / Vans	Total	HGVs	Cars / Vans	Total	HGVs	Cars / Vans	Total
.85 Taynuilt	320	0	320	76	0	76	0	0	0	267	128	395
N85 West	464	0	464	76	0	76	0	0	0	267	128	395
.85 East	320	0	320	76	0	76	0	0	0	267	128	395
8840 Cladich	0	0	0	0	0	0	0	0	0	0	0	0
\819 Dalmally	0	0	0	108	0	108	180	0	180	267	128	395
Site Access Frack	0	0	0	0	0	0	0	0	0	0	0	0
A819 Site Access	0	0	0	108	0	108	180	0	180	267	128	395
A819 nveraray	0	0	0	108	0	108	180	0	180	267	128	395
A819 nveraray Town	0	0	0	108	0	108	180	0	180	267	128	395
Inveraray Bypass	0	0	0	0	0	0	0	0	0	0	0	0
A83 Aray Bridge	0	0	0	54	0	54	0	0	0	0	0	0
A83 Garron Bridge	0	0	0	54	0	54	0	0	0	0	0	0
A83 Rest and Be Thankful	0	0	0	54	0	54	0	0	0	0	0	0
A815 Strachur	0	0	0	0	0	0	0	0	0	0	0	0
Upper Avenue AIL Route	0	0	0	0	0	0	0	0	0	0	0	0
A83 Inveraray	0	0	0	54	0	54	0	0	0	267	128	395
\83 _ochgilphead	0	0	0	54	0	54	0	0	0	267	128	395
3840 Ford	0	0	0	0	0	0	0	0	0	0	0	0
	HGVs	Cars / Vans	Total	HGVs	Cars / Vans	Total	HGVs	Cars / Vans	Total	HGVs	Cars / Vans	Tota
A85 Taynuilt	0	0	0	0	0	0	0	0	0	0	0	0
A85 West	0	0	0	0	0	0	0	0	0	0	0	0
A85 East	10	0	10	0	0	0	82	150	232	0	0	0
B840 Cladich	0	0	0	0	0	0	0	0	0	0	0	0
A819 Dalmally	10	0	10	0	0	0	82	150	232	0	0	0
Site Access Track	0	0	0	0	0	0	0	0	0	0	0	0
A819 Site Access	10	0	10	0	0	0	82	150	232	0	0	0
A819 nveraray	0	0	0	0	0	0	0	0	0	0	0	0
A819 nveraray Town	10	0	10	0	0	0		150	232	0	0	
nveraray Bypass	0	0	_	_			82					0
A83 Aray Bridge	10		0	0	0	0	82	0	0	0	0	0
A83 Garron Bridge	_	0	10	0	0	0		0 150	0 232	0 74	0 40	0
\83 Rest and	10	0					0					0
Be Thankful	0		10	0	0	0	0 82	150	232	74	40	0
A815		0	10	0	0	0	0 82 82	150 150	232	74 74	40	0 114 114 0
A815 Strachur Jpper Avenue AIL	0	0	10 10 0	0 0	0 0	0 0	0 82 82 0	150 150 0	232 232 0	74 74 0	40 40 0	0 114 114 0
A815 Strachur Jpper Avenue AIL Route	0	0 0	10 10 0	0 0 0	0 0 0	0 0 0	0 82 82 0	150 150 0	232 232 0	74 74 0	40 40 0	0 114 114 0
Be Thankful A815 Strachur Upper Avenue AIL Route A83 Inveraray A83 Lochgilphead	0 0	0 0 0	10 10 0 0	0 0 0 0	0 0 0 0	0 0 0 0	0 82 82 0 0	150 150 0 0	232 232 0 0	74 74 0 0	40 40 0 0	0 114 114 0 0

B840 Ford

Road Link	An C	Carr Dubh Wind F	-arm	33kv Overhead Line - ETU 166 - Dalmally			Crea	ag Dhubh Substa	ation	Inverary to Crossaig OHL			
	HGVs	Cars / Vans	Total	HGVs	Cars / Vans	Total	HGVs	Cars / Vans	Total	HGVs	Cars / Vans	Total	
A85 Taynuilt	0	0	0	0	0	0	0	0	0	0	0	0	
A85 West	0	0	0	0	0	0	0	0	0	0	0	0	
A85 East	0	0	0	0	0	0	54	150	204	0	0	0	
B840 Cladich	0	0	0	0	0	0	0	0	0	0	0	0	
A819 Dalmally	0	0	0	0	0	0	54	150	204	0	0	0	
Site Access Track	0	0	0	0	0	0	0	0	0	0	0	0	
A819 Site Access	100	58	158	0	0	0	54	150	204	118	69	187	
A819 Inveraray	0	0	0	0	0	0	0	0	0	0	0	0	
A819 Inveraray Town	100	58	158	0	0	0	54	150	204	118	69	187	
Inveraray Bypass	0	0	0	0	0	0	0	0	0	0	0	0	
A83 Aray Bridge	100	58	158	0	0	0	54	150	204	0	0	0	
A83 Garron Bridge	100	58	158	0	0	0	54	150	204	0	0	0	
A83 Rest and Be Thankful	0	0	0	0	0	0	0	0	0	0	0	0	
A815 Strachur	0	0	0	0	0	0	0	0	0	0	0	0	
Upper Avenue AIL Route	100	0	100	0	0	0	0	0	0	0	0	0	
A83 Inveraray	0	0	0	0	0	0	0	0	0	0	0	0	
A83 Lochgilphead	100	58	158	0	0	0	0	0	0	118	69	187	
B840 Ford	0	0	0	0	0	0	0	0	0	0	0	0	

Road Link	An	Suidhe Substati	ion	Total					
	HGVs	Cars / Vans	Total	HGVs	Cars / Vans	Total			
A85 Taynuilt	0	0	0	663	128	791			
A85 West	0	0	0	807	128	935			
A85 East	0	0	0	809	428	1237			
B840 Cladich	0	0	0	0	0	0			
A819 Dalmally	0	0	0	701	428	1129			
Site Access Track	0	0	0	0	0	0			
A819 Site Access	0	0	0	919	555	1474			
A819 Inveraray	0	0	0	555	128	683			
A819 Inveraray Town	0	0	0	919	555	1474			
Inveraray Bypass	0	0	0	0	0	0			
A83 Aray Bridge	0	0	0	374	398	772			
A83 Garron Bridge	0	0	0	374	398	772			
A83 Rest and Be Thankful	0	0	0	54	0	54			
A815 Strachur	0	0	0	0	0	0			
Upper Avenue AIL Route	0	0	0	100	0	100			
A83 Inveraray	0	0	0	321	128	449			
A83 Lochgilphead	0	0	0	613	295	908			
B840 Ford	0	0	0	0	0	0			

Annex L- Axle Loadings


Component	No. Units	Estimated Size (m) [L x W x H]	Appx Weight (t)
Turbine Head Cover	4	4.5 x 4.5 x 2.5	70
Generator Shaft	4	11	90
Stator Frame	4	7 x 5 x 5	55
Generator Hub	4	4 x 4 x 4	165
Transformer	4	12 x 8 x 6	280
Powerhouse	2	25 x 3 x 3	55
Crane			

Turbine Head	
Cover	

4.5 x 4.5 x 2.5

70

2.2. Transportation Arrangement




6 axle modular trailer = 14.57 Te per axle 8 axle modular trailer = 11.65 Te per axle.

2.2. Transportation Arrangement Side the state of the st

10 axle modular trailer = 11.90 Te per axle

7 x 5 x 5

55




8 axle modular trailer = 9.77 Te per axle

4 x 4 x 4


165

2.2. Transportation Arrangement



12 axle modular trailer = 16.65 Te per axle

Powerhouse	2	25 x 3 x 3	55
Crane			




6 axle Step Trailer ~ 10.5 Te per axle

Transformer

4

12 x 8 x 6

280



Trailer Tare = 160 Te

Girder Trailer = 2 x Bogies @ 14 x axles per Bogie

Load per Bogie = (280 + 160)/2 = 220 Te

Load per AxIe = 220 / 14 = 15.7 Te

Ground Block Loading = $3.49 \text{ Te} / \text{m}^2$

Annex M – Accident Forecast

	Forecast Annual Injury Accidents by Severity (Cumulative Development)												
Road				Link	Annual Flow	Vehicle Kms	Acci	dents Per Veh	KM	Cumulative Development	(Annuai)		
	Slight	Serious	Fatal	Length	ngth Flow Slight Serious Fatal Additional KMs		Additional KWS	Slight	Serious	Fatal			
A85 Taynuilt	7	8	1	16.8	1804560	30316608	4.6179E-08	5.2776E-08	6.597E-09	4874284.8	0.2	0.3	0.0
A85 West	0	0	0	0.65	1570230	1020649.5	0	0	0	270956.4	0.0	0.0	0.0
A85 East	0	0	0	2.7	1375685	3714349.5	0	0	0	645136.8	0.0	0.0	0.0
B840 Cladich	0	0	0	12.4	128115	1588626	0	0	0	40656	0.0	0.0	0.0
A819 Dalmally	1	5	0	10.6	588745	6240697	3.2048E-08	1.6024E-07	0	2773214.4	0.1	0.4	0.0
Site Access Track	0	0	0	0	0	0	0	0	0	0	0.0	0.0	0.0
A819 Site Access	0	3	0	8.1	613200	4966920	0	1.208E-07	0	2119154.4	0.0	0.3	0.0
A819 Inveraray	1	1	0	2.7	615390	1661553	1.2037E-07	1.2037E-07	0	706384.8	0.1	0.1	0.0
A819 Inveraray Town Centre	0	0	0	1.9	677440	1287136	0	0	0	419839.2	0.0	0.0	0.0
Inveraray Bypass	0	0	0	0	0	0	0	0	0	0	0.0	0.0	0.0
A83 Aray Bridge	1	2	0	2	1518765	3037530	6.5843E-08	1.3169E-07	0	109824	0.0	0.0	0.0
A83 Garron Bridge	3	3	0	3.6	1483360	5340096	1.1236E-07	1.1236E-07	0	344044.8	0.0	0.0	0.0
A83 Rest and Be Thankful	4	7	0	11.7	1652720	19336824	4.1372E-08	7.2401E-08	0	1118145.6	0.0	0.1	0.0
A815 Strachur	3	3	2	15.3	876730	13413969	4.4729E-08	4.4729E-08	2.982E-08	1244073.6	0.1	0.1	0.0
Upper Avenue AIL Route	0	0	0	0	0	0	0	0	0	0	0.0	0.0	0.0
A83 Inveraray Town Centre	0	0	0	1.2	1514020	1816824	0	0	0	191030.4	0.0	0.0	0.0
A83 Lochgilph ead	0	0	0	1.5	1259615	1889422.5	0	0	0	299772	0.0	0.0	0.0
B840 Ford	0	0	0	21.7	66065	1433610.5	0	0	0	882235.2	0.0	0.0	0.0

	Forecast Annual Injury Accidents by Severity (Proposed Development)													
Road	Reco	orded 2018-	-2022	Link	Annual	Vehicle Kms	Accidents Per Veh KM			Proposed Development	Proposed Development (Annual)			
	Slight	Serious	Fatal	Length	Flow		Slight	Serious	Fatal	Additional KMs	Slight	Serious	Fatal	
A85 Taynuilt	7	8	1	16.8	1804560	30,316,608	4.6179E-08	5.2776E-08	6.597E-09	1,366,042	0.1	0.1	0.0	
A85 West	0	0	0	0.65	1570230	1,020,650	0	0	0	52,853	0.0	0.0	0.0	
A85 East	0	0	0	2.7	1375685	3,714,350	0	0	0	219,542	0.0	0.0	0.0	
B840 Cladich	0	0	0	12.4	128115	1,588,626	0	0	0	504,134	0.0	0.0	0.0	
A819 Dalmally	1	5	0	10.6	588745	6,240,697	3.2048E-08	1.6024E-07	0	861,907	0.0	0.1	0.0	
Site Access Track	0	0	0	0	0	0	0	0	0	0	0.0	0.0	0.0	
A819 Site Access	0	3	0	8.1	613200	4,966,920	0	1.208E-07	0	658,627	0.0	0.1	0.0	
A819 Inveraray	1	1	0	2.7	615390	1,661,553	1.2037E-07	1.2037E-07	0	219,542	0.0	0.0	0.0	
A819 Inveraray Town Centre	0	0	0	1.9	677440	1,287,136	0	0	0	77,246	0.0	0.0	0.0	
Inveraray Bypass	0	0	0	0	0	0	0	0	0	0	0.0	0.0	0.0	
A83 Aray Bridge	1	2	0	2	1518765	3,037,530	6.5843E-08	1.3169E-07	0	81,312	0.0	0.0	0.0	
A83 Garron Bridge	3	3	0	3.6	1483360	5,340,096	1.1236E-07	1.1236E-07	0	292,723	0.0	0.0	0.0	
A83 Rest and Be Thankful	4	7	0	11.7	1652720	19,336,824	4.1372E-08	7.2401E-08	0	951,350	0.0	0.1	0.0	
A815 Strachur	3	3	2	15.3	876730	13,413,969	4.4729E-08	4.4729E-08	2.982E-08	1,244,074	0.1	0.1	0.0	
Upper Avenue AIL Route	0	0	0	0	0	0	0	0	0	0	0.0	0.0	0.0	
A83 Inveraray Town Centre	0	0	0	1.2	1514020	1,816,824	0	0	0	48,787	0.0	0.0	0.0	
A83 Lochgilphead	0	0	0	1.5	1259615	1,889,423	0	0	0	121,968	0.0	0.0	0.0	
B840 Ford	0	0	0	21.7	66065	1,433,611	0	0	0	882,235	0.0	0.0	0.0	

aecom.com

